



10/27/2022

City of Cartersville - Fibercom  
Gatlin Pruitt  
1 N Erwin St  
Cartersville, GA 30120  
404-520-2944  
gpruitt@cartersvillega.gov

Thank you for giving Network Cabling Infrastructures the opportunity to provide you with a proposal for the HWY 41 Bridge Crossing project. Please take the time to review the below scope of work and feel free to contact me if you have any questions or concerns.

All work will meet state and local codes, follow strict industry standards set forth by the Building Industry Consulting Service International, Inc. (BICSI).

**Safety Standards:**

All NCI (Network Cabling Infrastructures, LLC.) on-site technicians shall be aware of, and strictly adhere to any and all safety requirements mandated by OSHA, General Contractor and any applicable governmental agency.

**Assumptions:**

Technicians will have free access to required work areas.  
Aerial Work Platforms, bucket trucks, or other overhead equipment will be provided by NCI.  
Customer's employees, visitors, and others will be kept clear of active construction areas.  
Work will be completed during normal business hours (7AM to 5PM, Monday-Friday).  
Additional time requirements or delays may incur additional cost.

Bridge truck scheduled for five consecutive days with a single site delivery and pickup. Additional days or deliveries will incur additional cost at a rate of \$3,591.00 per delivery and \$2,010.96 per day.

## Bill Of Materials

DESCRIPTION	UNITS	UNIT PRICE	EXTENDED PRICE
<b>MATERIAL</b>			
(7600) ft Fiber Pulling (HDPE installed by NCI)	7600	\$ -	\$ -
(7000) ft Install Tracer	7000	\$ -	\$ -
(3575) ft Directional Bore (2) 1-1/4" HDPE	3575	\$ -	\$ -
(450) ft 2" Galvanized Rigid Conduit	450	\$ 15.80	\$ 7,110.18
(50) ea 2" minerlac	50	\$ 5.03	\$ 251.37
(50) ea 1-3/8" Beam Clamp	50	\$ 28.73	\$ 1,436.40
(5) day Bridge Truck Rental	5	\$ 2,010.96	\$ 10,054.80
(4) ea Install 24"x36"x36" (Handhole With Gravel)	4	\$ 7.18	\$ 28.73
(4) ea 2" 90 Degree Elbow	4	\$ 31.60	\$ 126.40
(4) ea 2" 45 Degree Elbow	4	\$ 21.55	\$ 86.18
(4) ea 2" Expansion Joints	4	\$ 574.56	\$ 2,298.24
(3) ea Install Marker Pole	3	\$ -	\$ -
(2) ea Install Test Stations	2	\$ -	\$ -
(2) ea Bridge Truck Delivery	2	\$ 1,795.50	\$ 3,591.00
(1) ea Fiber Pulling Aerial	1	\$ -	\$ -
<b>LABOR</b>			
(7600) ft Fiber Pulling (HDPE installed by NCI)	7600	\$ 0.75	\$ 5,711.02
(7000) ft Install Tracer	7000	\$ 0.10	\$ 698.25
(3575) ft Directional Bore (2) 1-1/4" HDPE	3575	\$ 13.00	\$ 46,477.68
(450) ft 2" Galvanized Rigid Conduit	450	\$ 20.62	\$ 9,276.75
(50) ea 2" minerlac	50	\$ -	\$ -
(50) ea 1-3/8" Beam Clamp	50	\$ -	\$ -
(5) day Bridge Truck Rental	5	\$ -	\$ -
(4) ea Install 24"x36"x36" (Handhole With Gravel)	4	\$ 450.00	\$ 1,800.00
(4) ea 2" 90 Degree Elbow	4	\$ -	\$ -
(4) ea 2" 45 Degree Elbow	4	\$ -	\$ -
(4) ea 2" Expansion Joints	4	\$ -	\$ -
(3) ea Install Marker Pole	3	\$ 30.00	\$ 90.00
(2) ea Install Test Stations	2	\$ 37.00	\$ 74.00
(2) ea Bridge Truck Delivery	2	\$ -	\$ -
(1) ea Fiber Pulling Aerial	1	\$ 1,500.00	\$ 1,500.00

Material:       \$ 24,983.31  
 Labor:           \$ 65,627.70  
 Total:           \$ 90,611.00

*All Pricing is Valid for 7 callendar days from date at top of this proposal unless otherwise specified. Material manufacture subject to change based on distributor availability. All substituted products will be of similar quality and functionally interchangeable.*

## Scope of Work

Directional bore (3575 ft) of dual 1.25" HDPE conduit. Install (4) 24\*36\*36 handholes (provided by others). Install tracer wire and fiber optic cable (provided by others). Install marker poles and test stations (provided by others). Provide bridge truck and transportation for equipment. This scope does not include optional aerial install along Peachtree Street and Tennessee Street.

NCI would like to thank you for this great opportunity and once again feel free to contact me if you have any questions or concerns.

Sincerely,

Logan Ghorley  
Project Manager  
Phone: 470-255-4476  
Fax: 770-495-6220  
Email: [logan.ghorley@ncicabling.com](mailto:logan.ghorley@ncicabling.com)