

FOX SYSTEMS, INC

P.O. BOX 1777
1771 US Hwy 41 SW
CALHOUN, GA 30703
(706) 625-5520 FAX: (706) 602-8416
www.foxsystemsinc.com



Estimate **E01142025EJ0230389**
Date: **January 14, 2025**

Prepared By: **Fox Systems, Inc.**
 Eric Jones
 (770) 547-4199
 ejones@foxsystemsinc.com

Customer
City of Cartersville – Waste Water Plant
102 Walnut Grove Rd.
Cartersville, GA 30120

Bart Sears
(678) 247-4069
bsears@cityofcartersville.org

Mr. Bart Sears,

Fox Systems, Inc. is pleased to provide the following estimate for the **“Dryer Project”** at the City of Cartersville Water Treatment Plant in Cartersville, GA.

The scope of work is to include the following:

Fox Systems will meet or exceed the National Electrical Code (NEC) requirements on all wiring installations. The materials and techniques used in the installation will comply with applicable code articles of the NEC.

1. Supply and install conduit and 15kV cable for the 500 kVA transformer.
 - a. Conduit to be fed from existing switchgear discussed.
 - i. Overhead conduit inside electrical building and underground (PVC) to transformer pad.
 - b. 500kVA transformer and pad to be supplied and installed by others.
2. Excavate trench for feeder to and from transformer.
 - a. Primary feeder approximately 10’ from building.
 - b. Secondary feeder approximately 180’ from transformer.
3. Supply and install conduit (PVC) and conductors (copper) for a 600 amp feeder from the transformer.
4. Supply and install a 600 amp, 480 volt, NEMA3R rated disconnect.
5. Supply and install conduit (PVC) and conductors (copper) for a 600 amp feeder from the disconnect to the main control panel (approximately 35’).
6. Sawing and removal of concrete from disconnect to main control to be performed by **others**.
7. Provide aerial lift.

Clarifications/Exclusions

1. This estimate does not include a transformer pad.
2. This estimate does not include cutting and removing of any concrete.
3. Fox Systems, Inc. shall not be responsible for damage to underground utilities, relocation of any utilities or damages resulting for the loss of service. Removal and/or relocation of any electrical, utility, sprinkler or plumbing lines are not included. Marking of utilities to be performed by others.
4. This estimate does not include removal of excess soil from the jobsite.
5. Does not include start up assistance for OEM equipment.

Estimate and Payment:

The estimated cost for the **“Dryer Project”** is **\$77,685.00**.

The invoice will be submitted upon projects completion.

We appreciate this opportunity and look forward to working with you on this project.

If you need any additional information, please call.

FOX SYSTEMS, INC

P.O. BOX 1777
1771 US Hwy 41 SW
CALHOUN, GA 30703
(706) 625-5520 FAX: (706) 602-8416
www.foxsystemsinc.com



Respectfully,

Eric Jones
Office: (706) 625-5520 ext.17
Cell: (770) 547-4199
E-Mail: ejones@foxsystemsinc.com

The fluid market conditions create delays and many other challenging conditions which may affect material delivery, costs and project completion times. This quote is valid for 30 days, however, due to the volatility of the materials market, Fox Systems will pass along any price increases that may affect this project. We appreciate your patience and understanding as we continue to do our best in these changing times.

This proposal was prepared by Fox Systems, Inc. and is protected by Copyright Laws. It is to be used solely with respect to our quotation. Fox Systems, Inc. retains ownership of all drawings, equipment lists and system design. This proposal and all associated enclosures are confidential and are not to be copied or used to obtain pricing from other suppliers, contractors or sub-contractors without our prior written consent.