

CHANGE ORDER



Order No.: 02 (Revised)
Date: July 25, 2024
Agreement Date: February 1, 2024

CTI PROJECT NO.: G21033
NAME OF PROJECT: LEAKE STREET & ERWIN STREET DRAINAGE IMPROVEMENTS
OWNER: CITY OF CARTERSVILLE, GA
CONTRACTOR: SITE ENGINEERING, INC

The following changes are hereby made to the Contract Documents:

Change to Contract Price

Original Contract Price:	\$ 2,166,530.00
Deductive Change Order 1	\$ (276,250.00)
Contract Price after Change Order 1	\$ 1,890,280.00
The Contract Price due to this Change Order will be increased by:	\$ 15,415.00
The new Contract Price including this Change Order will be:	\$ 1,905,695.00

Change to Contract Time

The Contract Time will be increased/decreased 0 calendar days.


The date for completion of all work will be December 31, 2021.

Justification

This change order addresses an unforeseen condition that requires immediate repair to protect the originally contracted, new construction as well as correcting an existing damaged storm drain and six-inch sewer line outside the original limits of construction. During the execution of the contract a client requested change to reinforce the asphalt subgrade in the intersection of Erwin and Leake Streets, (items 03 30 00a, 31 20 00j) are increased by 29 cubic yards as shown in the attached Change Order Summary spreadsheet. The unit price for item 03 30 00a has been decreased from \$500.00 to \$300.00 per cubic yard. (Items 33 31 00e, and 33 40 00m) are required to repair a broken storm drain and sewer main outside of the limits of construction, identified during execution of the original contract's work. Please see the attached detailed spreadsheet for a summary of this additive change order.

Approvals Required

Accepted by:

 J. David Hess - Vice President Site Engineering, Inc.

Recommended by:

 CTI Engineers, Inc.

Ordered by:

Mayor, City of Cartersville, Georgia

City Clerk, City of Cartersville, Georgia

CHANGE ORDER SUMMARY

CTI Project No.: G21033
 Project Name: LEAKE STREET & ERWIN STREET DRAINAGE IMPROVEMENTS
 Client: CITY OF CARTERSVILLE, GA
 Contractor: SITE ENGINEERING, INC

Item No.	Description	Unit	Est. No. Of Units	UNIT PRICE	Total Contract Amount
CHANGE ORDER 2 (REVISED)					
03 30 00	Cast-In-Place Concrete. All Material and Labor, Including Form Work, Reinforcing, Concrete, and Finishing, Complete in Place as Specified and/or Shown on the Drawings				
03 30 00a	Cast-In-Place Concrete - 3,000 PSI Class B for Thrust Blocks, Pipe Encasement, and Pipe Protection	CY	29	\$ 300.00	\$ 8,700.00
31 00 00	Earthwork				
31 20 00d	Demolition of Existing Pavement, Including Saw-cutting, Excavation, and Asphalt Disposal	LF	29	\$ 35.00	\$ 1,015.00
31 20 00j	Concrete Cap Excavation, Including Hauling and Proper Disposal of Spoil Materials	CY	29	\$ 100.00	\$ 2,900.00
33 31 00	Polyvinyl Chloride (PVC) Pipe and Fittings for Sewer Services, ASTM D3034 (SDR 26), Including Excavation, Installation, Standard Bedding and Backfill, and Testing				
33 31 00e	6-Inch SDR 26 PVC Service Line	LF	18	\$ 100.00	\$ 1,800.00
33 40 00	Storm Sewerage				
33 40 00m	Patch Existing 15" Storm Sewer, 0-6 feet deep,	LS	1	\$ 1,000.00	\$ 1,000.00
TOTAL CHANGE ORDER 2				\$	15,415.00
CHANGE ORDER SUMMARY					
TOTAL ORIGINAL BASE BID AMOUNT				\$	2,166,530.00
TOTAL DEDUCTIVE CHANGE ORDER 1				\$	(276,250.00)
TOTAL ADJUSTED CONTRACT AMOUNT AFTER CHANGE ORDER NO. 1				\$	1,890,280.00
TOTAL CHANGE ORDER 2				\$	15,415.00
TOTAL ADJUSTED CONTRACT AMOUNT AFTER CHANGE ORDER NO. 2				\$	1,905,695.00