CGS Waterproofing LLC 6040 Dawson Blvd Suite K Norcross, GA 30093 404-234-0248 info@cgswaterproofing.com/ https://cgswaterproofing.com/



Estimate

ADDRESS

City of Cartersville 1 North Erwin St Cartersville, GA 30120 SHIP TO City of Cartersville 1 North Erwin St Cartersville, GA 30120 ESTIMATE # 10046 DATE 05/01/2024

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT				
Interior Waterproofing	Basement Interior Waterproofing Install interior waterproofing system - Sub-floor system Sub-floor drain system discharge by SUMP PUMP Install system on PERIMETER OF BASEMENT (FRONT, LEFT, REAR) 122 LF of sub-floor system 10-15 LF of discharge lane away from property Cut concrete floor to create a trench for sub-floor drain system GRADE IS 0 FT HIGH SQFT OF ENCAP: 950 sqft ENCAPSULATE ALONG SYSTEM Repair concrete cut after installing drainage system Install (POP UP/ FLEX DRAIN) drains LIFETIME WARRANTY * CLIENT IS RESPONSIBLE TO CLEAR WORKSPACE AREA CGS IS NOT LIABLE FOR PERSONAL ITEMS LEFT IN	122	75.00	9,150.00				
	 * PLEASE NOTE: THERE IS A DISCHARGE LANE THAT WILL RESULT IN TRENCHING. CGS IS NOT LIABLE FOR DEAD SOD, GRASS, OR WHATEVER YOU MAY HAVE IN WORKSPACE AREA* Final note : DO NOT NAIL ANYTHING INTO NEW SYSTEM THIS VOIDS ANY WARRANTY GIVEN (opt for liquid nail if necessary) Quote valid for 30 days There is a 3.5% fee when paying with card ** PLEASE NOTE WE DO NOT ACCEPT WIRE/ACH PAYMENT UNLESS VERIF 	ED VENDOF	\ **					

ACTIVITY	DESCRIPTION		QTY	RATE	AMOUNT
Exterior Drainage .	Exterior Drainage / French Drains Total LF: 125 LF		125	45.00	5,625.00
	Cut surface prior to excavation to save u Dig down to create trench for French dra Install 10 Linear feet of French drain Install French drain among REAR ELEV Pour gravel bed prior to French drain ins system Install discharge lane 20 LF away from F Install pop up drain	ATION tallation and on top of			
Sump Pump (B)	 S2033-DFC2 - AC Pump with Dual Float and Deluxe Controller 1/2 HP Energy efficient motor 3200 GPH at 10' pumping capacity Cast iron construction Cast iron 6 blade vortex impeller Pumps solids up to 1/2" Monitoring system for security and pear USB Data Port and Remote Terminal a connect to remote notification devices 4 year manufacturer warranty 		2	650.00	1,300.00
		SUBTOTAL TAX TOTAL		16,075.00 0.00 \$16,075.00	

Accepted By

Accepted Date

Quote valid for 30 days There is a 3.5% fee when paying with card

** PLEASE NOTE WE DO NOT ACCEPT WIRE/ACH PAYMENT UNLESS VERIFIED VENDOR **