



11/21/2023

NWGP, Inc.
 P.O. Box 578
 Calhoun, GA 30703
 Office: (706) 383-5314
 Fax: (706) 383-5315
 Cell: (770) 542-8872
 E-Mail: emcmanus@nwgpinc.com

Dalton Airport Rehabilitation
 Dalton, GA

GeoHydro Field Report dated 11-21-23

ITEM NUMBER	DESCRIPTION OF WORK	QUANTITY	UNIT	UNIT PRICE	SUBTOTAL	TOTAL PRICE
28,812 SF	Option A- Undercut 36"- Install #3 Stone on Fabric- Cap with 8" GAB					
	Excavate and Haul off 36" of material	3201.00	CY	\$ 94.00	\$ 300,894.00	
	Geotextile Fabric- 2 layers	6402.00	SY	\$ 5.50	\$ 35,211.00	
	#3 Stone	4482.00	TON	\$ 78.13	\$ 350,178.66	
	Install 8"GAB- 4" Included in Contract	705.00	TON	\$ 63.64	\$ 44,866.20	
					Budget	\$ 731,149.86
43,340 SF	Option #B- Soil Cement 18" @ 120 lbs. per/sy					
	Haul off material	200.00	CY	\$ 94.00	\$ 18,800.00	
	Additional GAB- Highly Unstable Areas-	530.00	TON	\$ 63.64	\$ 33,729.20	
	Install 4" GAB- Included in Contract					
	Soil Cement 18"	4816.00	SY	\$ 22.50	\$ 108,360.00	
	Cement	289.00	TON	\$ 210.00	\$ 60,690.00	
	LAYOUT- SOIL CEMENT AREAS	1.00	LS	\$ 1,500.00	\$ 1,500.00	
					Budget	\$ 223,079.20
	Actual Quantities will be verified in the field					
	Waterline relocation, replacement, repair is excluded					
	Proposed Time Extension					30 Days

Signed: Eli McManus
 Eli McManus, Project Manager
 NWGP, Inc.
 P.O. Box 578
 Calhoun, GA 30703
 Office: (706) 383-5314, ext. 150
 Fax: (706) 383-5315
 Cell: (770) 542-8872
 E-Mail: emcmanus@nwgpinc.com

Date: 11/21/2023