

CONTRACT CHANGE ORDER

CHANGE ORDER NO.: 001

CONTRACT: 2018 Milling and Resurfacing
Various City Streets
Project # PW-2018-LMIG

CONTRACTOR: Northwest Georgia Paving, Inc.

Contractor (Northwest Georgia Paving, Inc.) and the City of Dalton mutually agree to add supplemental work (i.e. Tibbs Road deep patching) to the above referenced project at unit pricing as identified in Northwest Georgia Paving, Inc.'s proposal dated 02/08/2019.

Four (4) locations of 8-inch deep patching is included as part of this scope of work on Tibbs Road from Shugart Road to Ella Lane in the southbound lane. The total estimate of deep patching is 1,910 L.F. equating to approximately 1,120 tons of deep patching.

The anticipated contract increase of \$169,120.00 and a summary of quantities correlating with this amount is shown on the attached proposal from Northwest Georgia Paving, Inc.

Additionally, specifications for how the work is to be completed is shown in the proposal.

No additional contract completion time was requested by contractor as part of this Change Order.

Contract completion date: Friday, May 31, 2019

BY:

P. Andrew Parker
Assistant Public Works Director

Enclosed: Proposal from Northwest Georgia Paving, Inc. dated 02/08/2019

Northwest Georgia Paving, Inc.
P.O. Box 578
Calhoun, GA 30703
Office: (706) 383-5306
Fax: (706) 383-5305
Cell: (770) 547-4028
Email: broberts@nwgpinc.co



Job Name: City of Dalton
Job Location: Tibbs Rd ,
Proposal Dated: 2-8-19
Company:
Contact: Mr. Andrew Parker
Cell:
Office: 706-278-7077
Email: aparker@cityofdalton-ga.gov

Proposal

Description
Subtotal Description

Work to Include the following Patching on Tibbs Rd Request for Additional Work

Mobilization to the Site
Traffic Control
Milling out and hauling off site 8" depth patches at the following locations
313 to Tiffany Lane 1435 lf
Speed Limit Sign to Greenbush Place 175 lf
102 Tibbs 100 lf
105 Tibbs 200 lf
Furnish and install 6" of 25mm in (2) 3" lifts
Furnish and Install 2" of 12.5mm Approximately 1,120 tons at a unit rate of \$151.00 Approximate Cost \$169,120.00

Proposal Certification

NOTES:

- We have the following locations with are all in the Southbound lane starting at Red Light at Shugart Rd/Tibbs Terrace to Red Light Ella Lane.
- Work to be done during the daylight hours.
- The lengths are as shown and by the width of the lane figured 12' wide. NWGP is planning on leaving the center line in because no temp or perm markings are included in the number below.
- We thank you for the opportunity of quoting this work and if our proposal is found to be satisfactory, please sign the original of this letter as indicated, and return to us for our files so this project can be scheduled.

Submitted By: **Bryan S Roberts**
Estimator & Project Manager

Acceptance of Proposal – The above prices, specifications and conditions are satisfactory and are hereby accepted. I will be responsible for all attorney's fees incurred during collection. You are authorized to do the work as specified. Payment will be made as outlined above. This proposal may be withdrawn by us if not accepted within 15 days.

Authorized Signature: _____

Date of Acceptance _____



