

20 4/471

Change Order HEIMAN INC. (BODY)

Fire Department: City of Deadwood / Deadwood Fire Department
Attention: Chief Rakow
102 Sherman Street
Deadwood, SD 57732

06/07/2021
Date: 06/21/2021

Change Order Requested From XX Fire Dept. Dealer Central Change Order No. (1A)

We Hereby Agree to Make the change(s) specified below:

<p>#1 CLARIFY that in the chassis specification that it is noted that the batteries will be located under the cab on the Driver's side.</p> <p style="text-align: center;">Note: A relocation of the batteries will NOT be needed and the batteries will be accessible through the lid of the battery box mounted to the frame rails.</p> <p style="text-align: right;">No Charge</p>
<p>#2 CLARIFY that the Production Specification will get noted to install the Shore Inlet inside the cab next to the Driver's seat and on the floor next to the "Master Switch".</p> <p style="text-align: right;">No Charge</p>
<p>#3 CHANGE the air horn control from a single foot switch on the floor to a switch on the center console (towards the officer's side).</p> <p style="text-align: right;">No Charge</p>
<p>#4 CLARIFY that the images viewed through the screen inside the cab for the backup camera system are in color.</p> <p style="text-align: right;">No Charge</p>
<p>#5 ADD a GoLight LED spotlight with wireless remote to the roof of the crew module.</p> <p style="text-align: right;">Add: \$849.00</p>

#6 CLARIFY the Emergency Lighting Colors. The perimeter warning lights and colors will be installed as follows:

	Driver's Side	(center)	Officer's Side
◇ Lightbar	RED	CLEAR	BLUE
◇ Upper Rear Side	BLUE		RED
◇ Upper Rear	RED		BLUE
◇ Low Front	BLUE		RED
◇ Intersection	RED		BLUE
◇ Low Mid-Body	BLUE		RED
◇ Low Rear Side	BLUE		RED
◇ Low Rear	BLUE		RED

Add: \$160.00

#7 ADD a high priority, multi-mode GTT OptiCom (792HM) installed on the cab roof by the lightbar.

Add: \$2,068.00

#8 CHANGE the storage area at the front of the crew area from a single to one (1) compartment each side below the talk through.

Add: \$395.00

#9 ADD a fuel gauge that shows tank levels in ¼ tank increments at the Operator's Panel in L-3.

Add: \$481.00

#10 CLARIFY that the Production Specification will get noted for installation of the Deck Gun at the rearward most outboard side (driver's) of the upper body as discussed at your Pre-Construction Conference.

Note: In addition to the location of the monitor it will get noted to hold the aluminum cover back on that side for a landing centered around the monitor.

No Charge

#11 ADD a wireless remote control for the monitor up in the hosebed in addition to the tethered remote already noted for installation in the pumphouse.

Note: The bracket for the wireless remote will get installed in L-3 also.

Add: \$1,789.00

#12 CLARIFY that it is a standard that when there is an electric monitor discharge on top of an extenda-gun (electric), the controls for the telescopic pipe are included in the handheld remote specified for the monitor.

No Charge

#13 CLARIFY that the Production Specification will get edited to read "Hinged" doors in lieu of roll-up for L-3 (pumphouse door).

No Charge

#14 CLARIFY the left (Driver's) side body compartment tray and shelf installations. The LH side body compartments will have the following equipment installed:

- ◁ L-1: Two (2) adjustable shelves (mid-upper portion)
- ◁ L-2: One (1) roll-out tray (floor mounted) and two (2) roll-out/tilt-down trays (mid/upper)
- ◁ L-3: One (1) roll-out tray (floor mounted)

Note: Turtle Tile will be provided in each tray installed.

Note: Two (2) adjustable shelves, one (1) roll-out tray, one (1) pull-out/drop-down tray, and more Turtle Tile has been added from what was originally specified.

Add: \$1,930.00

#15 CLARIFY the right (Officer's) side body compartment tray and shelf installations. The RH side body compartments will have the following equipment installed:

- ◁ R-1: One (1) roll-out tray (floor mounted) and one (1) adjustable shelf (mid-upper portion)
- ◁ R-2: One (1) roll-out tray (floor mounted) and two (2) roll-out/tilt-down trays (mid/upper)
- ◁ R-3: Two (2) adjustable shelves
- ◁ R-4: One (1) roll-out tray (floor mounted) and one (1) adjustable shelf (mid-upper portion)

Note: Turtle Tile will be provided in each tray installed.

Note: The compartment divider originally specified for R-4 will be deleted and the shelf and tray will be full-width inside the compartment.

Note: Two (2) adjustable shelves, one (1) roll-out tray, and more Turtle Tile has been added from what was originally specified.

Add: \$1,034.00

#16 ADD another set of Duplex receptacles for the crew area. Two (2) sets of receptacles will get installed as follows:

- ◁ one (1) Driver's forward wall, below the talk through, near the entry door
- ◁ one (1) Officer's forward wall, below the talk through, near the entry door

Note: Both outlets will be powered through shoreline and the generator, in addition they will be wired through the auto-matic transfer switch.

Add: \$578.00

#17 CLARIFY the lettering instructions for completed apparatus, Goldleaf Letters outlined in Black will be applied the rear (center) roll-up doors as follows:

HISTORIC PRESERVATION
THRU FIRE PREVENTION
& SUPPRESSION

4" Straight
3" Straight
3" Straight and Center on the Rear Door

Note: All lettering to be "Sized-to-Fit".

No Charge

#18 CLARIFY that it will get noted that the BLACK Reflective Perimeter Stripe will need to Reflect WHITE when illuminated at dark.

No Charge

#19 ADD another set of wheel chocks and brackets for the officer's side, to match the drivers.

Note: The wheel chocks for the officer's side will get installed below
Compartment R-1.

Add: \$1,064.00

#20 CHANGE the couplings for the three (3) suction hoses that are to be provided from LHFH x RLM to 5" Storz on both ends.

Add: \$764.00

#21 DELETE the three (3) hard suction hoses completely from the specifications

DEDUCT \$ 2,745.00

WE AGREE hereby to make change(s) specified above at this price \$4,471.00

(Body) PREVIOUS CONTRACT AMOUNT \$ 404,666.00

(Body) REVISED CONTRACT TOTAL \$ 409,137.00 +

Chassis
109,300

Due to lead times of components and in fabrication this change order may delay delivery.

ACCEPTED -The above price and specifications of the Change Order are satisfactory and are hereby accepted. All work to be performed under same terms and conditions as specified in original contract unless otherwise stipulated.

Total

\$ 518,437.00

Authorized Signature (contractor)

Date of acceptance / /

Authorized Signature (Fire Department)

Date of acceptance / /