



December 29, 2021

Bob Nelson  
Public Works Director  
City of Deadwood

RE: Rodeo Grounds – Concrete Slab

Dear Bob,

We are writing in regards to the proposal that you requested for concrete work at the rodeo grounds in Deadwood, SD. Our estimate is based on the site visit performed and red lined plan received from Albertson Engineering.

Notes/Includes:

- Excavate and cap the two existing water lines
- Remove approx. 6" of fill dirt and install 4" of gravel
- Install #4 rebar per Albertson plan
- Place slab 4" thick with thickened edge at front and back (no foundation wall included) (thickened edge to be approx. 12" x 12")

Exclusions:

No foundation wall or stoop included  
No Rigid insulation required per conversation with Jared at Albertson  
Bond; Permit Fees, Rock excavation

**Proposed Estimate: \$27,400.00**

This proposal is valid for 14 days.

If you should have any questions, please contact our office at 605-342-3787.

Thank You,

*Josiah Scull*

Josiah Scull  
R.C.S. Construction, Inc.  
Project Manager/Estimator

Safety • Quality • Communication • Timeliness

P.O. Box 9337 • Rapid City, SD 57709-9337  
Phone (605) 342-3787 • Fax (605) 348-4041

[www.rcsconst.com](http://www.rcsconst.com)

