Estimate

MCD Sealcoating & Asphalt Services 605-641-3450 605-645-8988

Date:5/2/2024

FOR: Hearth Building Grounds

BILL TO

City Of Deadwood ATTN Jim Lee

Sealcoat * Crack Fill * Striping * Patch Work * Blasting

mike@mcdasphalt.com / chris@mcdasphalt.com
4225 Old Belle Road Spearfish SD 57783

	Description	Rate	QTY	AMOUNT
ealer	This estimate is for sealcoating 96,010 SQFT (See attached maps with GPS measurements). There was a deduction of 12,152 Sqft for the building in the middle of the lot. Lot will be broomed with a In-Sweep skid steer broom, debris will be hauled off. Lot will then be blown off with high speed air. Sealer is an asphalt emulsion sealer containing sand, slate, and fiber.	\$ 0.2	96,010 SQFT	\$ 24,002.50
rack Fill 1	4024 Lin Ft of field cracks. Cracks will be cleaned with 9" wire power wheel, then blown out with air. Rubber is 3405 Modified (DOT SPEC).	\$ 1.3	4,024 Lin FT	\$ 5,432.40
rack Fill 2	2,768 Lin Ft of Perimeter cracks, drain pans & cold joint cracks against new asphalt. Cracks will be cleaned	\$ 1.3	35 2,768 Lin FT	\$ 3,736.80
An	with 9" wire power wheel, then blown out with air. Rubber is 3405 Modified (DOT SPEC).			
	All cracks not seen due to construction eqp, materials and debris would be billed at the \$1.35 /LINFT as an additional charge if the City od Deadwood agrees they want them filled MCD agrees to come back one (1) time with no mobile fee, to seal cracks and sealcoat where RCS has wall blocks staged behind the engine building. If excise tax is exempt please provide the form 2040 with payment or excise will be considered DUE AT TIME OF PAYMENT			
	PAYMENT TERMS AND CONDITIONS		MATERIAL & LABOR	\$ 33,171.70
	nvoices are due in FULL no more than 5 days past the date receiv		SD EXCISE TAX	33,171.75
	rinvoices not paid in full within the 5 days, will be assed a DAILY la ment penalty fee of 2% of the Total Due	ate	EXCISE TAX TOTAL	
	GROSS MATERIA	L AND LABOR PL	US EXCISE TAX TOTAL	

JOB WILL BE BILLED BASED ON FINAL MEASURMENTS

THANK YOU FOR YOU BUSINESS