



To: Ice Wolves Youth Hockey
ATTN: Kyle Levetzow
Email: icewolvesprez@gmail.com

Date: 2/21/2025
Proposal Title: Ice Wolves Speaker Replacement
Dodgeville WI

Grounded Electric, Inc pleased to furnish this Proposal for installation of wiring, material, and/or equipment for the above referenced project. This proposal is submitted per your request and includes the clarifications listed below.

Total Lump Sum Proposal \$31,925.00

Scope of Work:

- Furnish and install (1) replacement ceiling mount speaker in concession area.
- Furnish and install (2) replacement ceiling mount speakers in the lobby area.
- Furnish and install (7) replacement exterior wall mount speakers.
- Furnish and install (14) replacement suspended pendant mount speakers above ice.
- Furnish and install (4) new wall mount speakers. (2) behind each bleacher area.
- Replace head end equipment and replace with:
 - Wall mounted rack to provide system with proper ventilation.
 - LEA professional amplifier.
 - Tascam CD-4000U media player supporting Bluetooth, AM/FM, SD/SDHC, CD, and 3.5mm audio connections.
 - (8) channel power conditioner.
 - Includes system programming and owner training.
- New system will be broken into (4) individually controlled zones.
 - Ice rink, concession, exterior, lobby.
 - Surface mount wall controls will be added to control volume for each zone. Location TBD onsite.
- Demo, remove, recycle and/or dispose of (24) speakers and associated mounting brackets/boxes/hardware.

Clarifications:

- We've included electrical permit fee.
- We've included (1) week of lift rental to complete work in ice arena.
- All work to be performed during normal business hours, Monday thru Friday 7am to 5pm.
- Pricing is valid for (15) days.

Proposal may be withdrawn if not accepted by 15 Days

Payment to be made within 30 Days

Authorized Signature: _____

Matt Yorde


Title: Project Manager

Phone Number: 608-250-0225

The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified in the proposal above.

Signature of Acceptance: _____

Date: _____

PROPOSAL

25-0444 AV - Dodgeville Ice Wolves

Grounded Electric

3753 County Road Z

Dodgeville

WI 53533-8935

Revision: 0

Modified: 2/20/2025

Project No : 25-0444



Presented By:

Omni Technologies, LLC

900 Oregon Center Drive

Oregon, WI 53575 United States

(608) 819-1980

www.omnitechologiesllc.com



SCOPE OF WORK

Omni Technologies LLC is pleased to present this AV proposal for the Dodgeville Ice Wolves in Dodgeville, WI. This is a Parts & Smarts proposal.

Note:

- New (Optional) rack to house AV equipment
- LEA Professional Amplifier - 4 zones, Microphone Ducking, room for expansion
- Wall Mounted Volume Controls for each zone: Ice Rink, Concession, Exterior, Lobby
- Existing Microphone to be integrated into system
- Tascam CD-400U media player includes Bluetooth, AM/FM, SD/SDHC, CD-ROM, and 3.5mm audio inputs for flexibility and ease of use

Includes:

- (Optional) AV Rack to house equipment - locking door - wall-mount
- (1) LEA Professional Amplifier
- (1) 8 Channel IP Power Conditioner
- (1) Tascam Media Player
- (4) Wall-mounted Volume Controls
- (3) Ceiling Speakers
- (14) Pendant Speakers
- (11) Wall Speakers
- CAD Drawings/Design
- Labor for Device Installation, Head End/Programming, Testing, and Training

Does Not Include:

- Installation of Speakers - Device Install only covers Head End Devices/Optional Rack
- Speaker Safety Cables - Can add on a change order if necessary
- Cable or Cable Installation
- Elevator traveling cable or install labor
- 120VAC connections
- Electrical rough-in/conduit/back boxes
- Fire stopping
- Lift/scaffolding rental for work above 12 ft.
- Work performed outside normal business hours
- Equipment or services not listed within the proposal.

- 4 AtlasIED AT35D**
35W Attenuator - Decora - White
- 1 Labor CAD/Drawings**
- 1 Labor Field Device Installation**
- 1 Labor Head End/Programming Labor**
- 1 Labor Project Management**
Project Management & Coordination
- 1 Labor Testing & Configuration**
Testing and Configuration of Installed Devices
- 1 Labor Training**
End-User Product/System Training
- 1 LEA Professional CONNECT 1504D**
LEA Professional CONNECT 1504D 4-Channel High Power Smart Amp, 1500W
- 1 LEA Professional XLRF
XLRF Female XLR to Amphenol Anytek 3-Pin Connector
- 1 Misc. GROUND SHIPPING**
Shipping and Handling
- 1 Misc. MILEAGE/TRAVEL**
- 1 Netgear GS308**
8-Port Ethernet Unmanaged Switch
- 3 QSC AC-C4T**
4.5" Full-range ceiling speaker, 70/100V transformer with 8? bypass, 140° conical coverage, includes C-ring and rails for blind mount installation.
Priced individually, sold only in pairs.
- 11 QSC AC-S6T**
6.5" Two-way surface speaker, 70/100V transformer with 8? bypass, 130° conical coverage, includes Yoke Mount. Color - White. Priced individually, sold only in pairs.
- 14 QSC AD-P6T-WH**
6.5" Two-way pendant speaker, 70/100V transformer with 16? bypass, 135° conical DMT coverage, Includes cable and fastener for suspended Installation. Color - White.
- 1 Tascam CD-400U**
CD/SD/USB Player with Bluetooth Receiver and FM/AM Tuner
- 1 WattBox WB-800CH1U-IPVM-8**
1U Integrated Faceplate IP Power Conditioner | 8 Individually Metered and Controlled Outlets

Additional Options

- 1 Strong SR-WMS-10U**
10U Wall-Mount Rack with Locking Door and Locking Side Panels
- 3 Middle Atlantic EB1**
1SP FLANGED ECONO BLANK
- 1 Middle Atlantic Omni 1U Branded Blank Plate**
Omni Branded Blank Panel, 1 RU, Aluminum, Flanged
- 1 Strong SR-SHELF-2U**
2U Rack Shelf

AV System Total

\$20,872.00

Project Subtotal:

\$20,872.00

Items

Optional

Total

Grand Total:

\$20,872.00

\$738.00

\$21,610.00

Included in
lump sum quote
on page #1.