



RULE

Construction

Mike Bisbach, Project Manager

3696 State Road 23, Dodgeville, WI 53533

Cell (608) 341-7313

Office: (608) 935-2701

December 1, 2025

PROPOSAL

Project: Dodgeville Library
Added Sewer Lateral
C/O: Dylan Wadzinski

Added Sewer Lateral

The following work is included in the quote and lump sum bid price.

- New 4" SDR 35 Sewer Lateral from sewer main to 5' outside building.
- Sawcutting pavement and curb and gutter
- Temporary patch (winter)
- Permanent patch in Spring when asphalt plants open.
- Curb and Gutter replacement in spring when weather permits.
- All removals and backfill.
- Traffic control.

LUMP SUM COST = \$8,500.00

NOTES:

1. No restriping included.
2. Road will be closed during construction.
3. Rock Excavation not included. If rock excavation is required rock excavation will be billed at \$100.00 per CY.
4. Owner shall obtain all permits as required.
5. Staking if required shall be completed by general contractor.
6. Quote is good for 30 days.

ACCEPTANCE

The above prices and specifications are acceptable.
You are authorized to do the work.

City of Dodgeville

By: _____

Title: _____ Date: _____

Please return signed quote to our office

Rule Construction, Ltd.

By: 

Mike Bisbach

Title: Project Manager