

# DK CONSTRUCTION, INC.

DOCKS SEAWALLS PILEDIVING

DREDGING WELDING REPAIRS

346 West 15th Street HOLLAND, MI 49423

PH-616-494-0970 FAX-616-494-0980

[www.dkconstruction.com](http://www.dkconstruction.com)

[dkcons@sbcglobal.net](mailto:dkcons@sbcglobal.net)

**DATE:** October 23, 2024

**EMAIL:** rdyk@BDRinc.com

**TO:** Ric Dyk

**RE:** Westshore Boardwalk  
Douglas, MI 49406

## Quote

### Elevated Steel Boardwalk – Per Footprint Dated: 6/11/2024

Furnish crew, equipment and all materials to install a new 8' x 164' steel frame elevated boardwalk. Through bolt new 6" x 6" x 53" treated wood up rights every 8' on center to new steel frame. Uprights to be 3' 9" above the deck and coped on all sides. Boardwalk to run over the existing wetland and be elevated approximately 18" above the existing grade. Property staking and survey work to be done by others.

#### *Includes:*

- 4" Pipe Pile – 8' OC – *Minimum 10' Embedment*
  - *Additional Cost of \$400 per 10' Extension Beyond 21' Pile Length*
- 8" Channel Iron Frame
- 6" Channel Iron Braces
- 3" x 2" Angel Iron Stringers – 16" OC
- 2" x 4" Treated Wood Nailer
- 6" x 6" x 53" – Treated Wood Up Rights – 8' OC
- 2" x 6" Treated Wood Decking
- 2" x 6" Treated Wood Railing

**FOR THE SUM OF: \$86,592.00**

### Steel Sheet Pile Abutments

Furnish crew, equipment and all materials to install two (2) 8' x 1.5' x 1.5' of 8 gage interlocking steel sheet pile in 4' to 10' lengths. New steel sheet pile abutments to be tied into the new steel frame boardwalk. Property staking and survey work to be done by others.

#### *Includes:*

- 6" x 12# H Beam Waler
- 6" Channel Iron Cap

**FOR THE SUM OF: \$9,160.00**

**TERMS: 1/2 DOWN WITH BALANCE DUE UPON COMPLETION**