

SECTION 26 56 68

EXTERIOR ATHLETIC LIGHTING

PART 1 - GENERAL

1.1 SUMMARY

- A. Work covered by this section of the specifications shall conform to the contract documents, engineering plans as well as state and local codes.
- B. The purpose of these specifications is to define the lighting system performance and design standards for Dripping Springs Sports & Recreation Park using an LED Lighting source. The manufacturer / contractor shall supply lighting equipment to meet or exceed the standards set forth in these specifications.
- C. The sports lighting will be for the following venues:
 - 1. Baseball Field 1
 - 2. Baseball Field 2
 - 3. Soccer 7
 - 4. Soccer A-E & Soccer 6
 - 5. Soccer 5
 - 6. Soccer 1
 - 7. Soccer 2
 - 8. Soccer 3-4
 - 9. Softball Lower Field
 - 10. Softball Upper Field
- D. The primary goals of this sports lighting project are:
 - 1. Guaranteed Light Levels: Selection of appropriate light levels impact the safety of the players and the enjoyment of spectators. Therefore light levels are guaranteed to not drop below specified target values for a period of 25 years.
 - 2. Environmental Light Control: It is the primary goal of this project to minimize spill light to adjoining properties and glare to the players, spectators and neighbors.
 - 3. Cost of Ownership: In order to reduce the operating budget, the preferred lighting system shall be energy efficient and cost effective to operate. All maintenance costs shall be eliminated for the duration of the warranty.
 - 4. Control and Monitoring: To allow for optimized use of labor resources and avoid unneeded operation of the facility, customer requires a remote on/off control system for the lighting system. Fields should be proactively monitored to detect luminaire outages over a 25-year life cycle. All communication and monitoring costs for 25-year period shall be included in the bid.
- E. All lighting designs shall comply with International Dark-Sky Association and their IDA Community Friendly Outdoor Sports Lighting Program.

1.2 LIGHTING PERFORMANCE

- A. Illumination Levels and Design Factors: Playing surfaces shall be lit to an average target illumination level and uniformity as specified in the chart below. Lighting calculations shall be developed and field measurements taken on the grid spacing with the minimum number of grid points specified below. Appropriate light loss factors shall be applied and submitted for the basis of design. Average illumination level shall be measured in accordance with the IESNA LM-5-04 (IESNA Guide for Photometric Measurements of Area and Sports Lighting Installations). Illumination levels shall not to drop below desired target values in accordance

1
2
3

with IES RP-6-15, Page 2, Maintained Average Illuminance and shall be guaranteed for the full warranty period.

Area of Lighting	Average Constant Light Levels	Max to Min Uniformity Ratio	Grid Points	Grid Spacing
Baseball 1 - Infield	50 foot-candles	2.0:1.0	25	30' x 30'
Baseball 1 - Outfield	30 foot-candles	2.5:1.0	105	30' x 30'
Baseball 2 - Infield	50 foot-candles	2.0:1.0	25	20' x 20'
Baseball 2 - Outfield	30 foot-candles	2.5:1.0	70	20' x 20'
Soccer 1	30 foot-candles	2.0:1.0	18	30' x 30'
Soccer 2	30 foot-candles	2.0:1.0	24	30' x 30'
Soccer 3-4	30 foot-candles	2.5:1.0	88	30' x 30'
Soccer 5	30 foot-candles	2.0:1.0	60	30' x 30'
Soccer A-E and Soccer 6	30 foot-candles	2.5:1.0	132	30' x 30'
Soccer 7	30 foot-candles	2.5:1.0	72	30' x 30'
Softball Upper Field - Infield	50 foot-candles	2.0:1.0	25	20' x 20'
Softball Upper Field - Outfield	30 foot-candles	2.5:1.0	182	20' x 20'
Softball Lower Field - Infield	50 foot-candles	2.0:1.0	25	20' x 20'
Softball Lower Field - Outfield	30 foot-candles	2.5:1.0	181	20' x 20'

4
5
6
7
8
9
10
11
12

- B. Color: The lighting system shall have a minimum color temperature of 5700K and a CRI of 75 CRI.
- C. Mounting Heights: To ensure proper aiming angles for reduced glare and to provide better playability, minimum mounting heights shall be as described below. Higher mounting heights may be required based on photometric report and ability to ensure the top of the field angle is a minimum of 10 degrees below horizontal.

# of Poles	Pole Height
7	50'
5	60'
18	70'
11	80'

13
14
15
16
17
18
19
20
21
22
23

1.3 ENVIRONMENTAL LIGHT CONTROL

- A. Light Control Luminaires: All luminaires shall utilize spill light and glare control devices including, but not limited to, internal shields, louvers and external shields. No symmetrical beam patterns are accepted.
- B. Spill Light and Glare Control: To minimize impact on adjacent properties, spill light and candela values must not exceed the following levels taken at 3 feet above grade. Spill and Glare shall meet the IDA Community Friendly Outdoor Sports Lighting Program.

150' from field edge	Maximum
Horizontal Footcandles	.02 fc
Vertical Footcandles	.05 fc
Candela	1,000 cd

24

- 1 C. The first page of a photometric report for all luminaire types proposed showing horizontal
2 and vertical axial candle power shall be provided to demonstrate the capability of achieving
3 the specified performance. Reports shall be certified by a qualified testing laboratory with a
4 minimum of five years of experience or by a manufacturer's laboratory with a current
5 accreditation under the National Voluntary Laboratory Accreditation Program for Energy
6 Efficient Lighting Products. A summary of the horizontal and vertical aiming angles for each
7 luminaire shall be included with the photometric report.
8

9 1.4 COST OF OWNERSHIP

- 10 A. Manufacturer shall submit a 25 year Cost of Ownership summary that includes energy
11 consumption, anticipated maintenance costs, and control costs. All costs associated with
12 faulty luminaire replacement - equipment rentals, removal and installation labor, and
13 shipping - are to be included in the maintenance costs.
14
15

16 PART 2 - PRODUCT

17 2.1 SPORTS LIGHTING SYSTEM CONSTRUCTION

- 18
19 A. Manufacturing Requirements: All components shall be designed and manufactured as a
20 system. All luminaires, wire harnesses, drivers and other enclosures shall be factory
21 assembled, aimed, wired and tested.
22
23 B. Durability: All exposed components shall be constructed of corrosion resistant material
24 and/or coated to help prevent corrosion. All exposed carbon steel shall be hot dip galvanized
25 per ASTM A123. All exposed aluminum shall be powder coated with high performance
26 polyester or anodized. All exterior reflective inserts shall be anodized, coated, and protected
27 from direct environmental exposure to prevent reflective degradation or corrosion. All
28 exposed hardware and fasteners shall be stainless steel, passivated and coated with
29 aluminum-based thermosetting epoxy resin for protection against corrosion and stress
30 corrosion cracking. Structural fasteners may be carbon steel and galvanized meeting ASTM
31 A153 and ISO/EN 1461 (for hot dipped galvanizing), or ASTM B695 (for mechanical
32 galvanizing). All wiring shall be enclosed within the cross-arms, pole, or electrical
33 components enclosure.
34
35 C. System Description: Lighting system shall consist of the following:
36
37 1. Galvanized steel poles and cross-arm assembly.
38 2. Non-approved pole technology:
39 a. Square static cast concrete poles will not be accepted.
40 b. Direct bury steel poles which utilize the extended portion of the steel shaft for their
41 foundation will not be accepted due to potential for internal and external corrosive
42 reaction to the soils and long term performance concerns.
43 3. Lighting systems shall use concrete foundations. See Section 2.4 for details.
44 a. For a foundation using a pre-stressed concrete base embedded in concrete backfill
45 the concrete shall be air-entrained and have a minimum compressive design
46 strength at 28 days of 3,000 PSI. 3,000 PSI concrete specified for early pole
47 erection, actual required minimum allowable concrete strength is 1,000 PSI. All piers
48 and concrete backfill must bear on and against firm undisturbed soil.
49 b. For anchor bolt foundations or foundations using a pre-stressed concrete base in a
50 suspended pier or re-enforced pier design pole erection may occur after 7 days. Or
51 after a concrete sample from the same batch achieves a certain strength.
52

- 1 4. Manufacturer will supply all drivers and supporting electrical equipment
- 2 a. Remote drivers and supporting electrical equipment shall be mounted approximately
- 3 10 feet above grade in aluminum enclosures. The enclosures shall be touch-safe
- 4 and include drivers and fusing with indicator lights on fuses to notify when a fuse is
- 5 to be replaced for each luminaire. Disconnect per circuit for each pole structure will
- 6 be located in the enclosure. Integral drivers are not allowed.
- 7 b. Alternate: Integral drivers mounted at the top of the pole will require a pole mounted
- 8 enclosure approximately 10 feet above grade. The enclosure shall include a
- 9 disconnect per circuit, individual luminaire fusing, and surge protection.
- 10 c. Manufacturer shall provide surge protection at the pole equal to or greater than 40
- 11 kA for each line to ground (Common Mode) as recommended by IEEE
- 12 C62.41.2_2002.
- 13 5. Wire harness complete with an abrasion protection sleeve, strain relief and plug-in
- 14 connections for fast, trouble-free installation.
- 15 6. All luminaires, visors, and cross-arm assemblies shall withstand 150 mi/h winds and
- 16 maintain luminaire aiming alignment.
- 17 7. Control cabinet to provide remote on-off control, monitoring, and entertainment features
- 18 of the lighting system. See Section 2.3 for further details.
- 19 8. Contactor cabinet to provide on-off control.
- 20 9. Manufacturer shall provide lightning grounding as defined by NFPA 780 and be UL
- 21 Listed per UL 96 and UL 96A.
- 22 a. Integrated grounding via concrete encased electrode grounding system.
- 23 b. If grounding is not integrated into the structure, the manufacturer shall supply
- 24 grounding electrodes, copper down conductors, and exothermic weld kits.
- 25 Electrodes and conductors shall be sized as required by NFPA 780. The grounding
- 26 electrode shall be minimum size of 5/8 inch diameter and 8 feet long, with a minimum
- 27 of 10 feet embedment. Grounding electrode shall be connected to the structure by
- 28 a grounding electrode conductor with a minimum size of 2 AWG for poles with 75
- 29 feet mounting height or less, and 2/0 AWG for poles with more than 75 feet mounting
- 30 height.
- 31
- 32 D. Safety: All system components shall be UL listed for the appropriate application.
- 33

34 2.2 ELECTRICAL

- 35
- 36 A. Electric Power Requirements for the Sports Lighting Equipment:
- 37 1. Electric power: 240 Volt, 1 Phase
- 38 2. Maximum total voltage drop: Voltage drop to the disconnect switch located on the poles
- 39 shall not exceed three (3) percent of the rated voltage.
- 40
- 41 B. Energy Consumption: The kW consumption for the field lighting system shall not exceed 272
- 42 Kw.
- 43

44 2.3 CONTROL

- 45
- 46 A. Instant On/Off Capabilities: System shall provide for instant on/off of luminaires.
- 47
- 48 B. Lighting contactor cabinet(s) constructed of NEMA Type 4 aluminum, designed for easy
- 49 installation with contactors, labeled to match field diagrams and electrical design. Manual off-
- 50 on-auto selector switches shall be provided.
- 51
- 52 C. Dimming: System shall provide for 3-stage dimming (high-medium-low). Dimming will be set
- 53 via scheduling options (Website, app, phone, fax, email)

- 1 D. Remote Lighting Control System: System shall allow owner and users with a security code to
2 schedule on/off system operation via a web site, phone, fax or email up to ten years in
3 advance. Manufacturer shall provide and maintain a two-way TCP/IP communication link.
4 Trained staff shall be available 24/7 to provide scheduling support and assist with reporting
5 needs.
6 1. The owner may assign various security levels to schedulers by function and/or fields.
7 This function must be flexible to allow a range of privileges such as full scheduling
8 capabilities for all fields to only having permission to execute "early off" commands by
9 phone. Scheduling tool shall be capable of setting curfew limits.
10 2. Controller shall accept and store 7-day schedules, be protected against memory loss
11 during power outages, and shall reboot once power is regained and execute any
12 commands that would have occurred during outage.
13
14 E. Remote Monitoring System: System shall monitor lighting performance and notify
15 manufacturer if individual luminaire outage is detected so that appropriate maintenance can
16 be scheduled. The controller shall determine switch position (manual or auto) and contactor
17 status (open or closed).
18
19 F. Management Tools: Manufacturer shall provide a web-based database and dashboard tool
20 of actual field usage and provide reports by facility and user group. Dashboard shall also
21 show current status of luminaire outages, control operation and service. Mobile application
22 will be provided suitable for IOS, Android and Blackberry devices.
23 1. Hours of Usage: Manufacturer shall provide a means of tracking actual hours of usage
24 for the field lighting system that is readily accessible to the owner.
25 a. Cumulative hours: shall be tracked to show the total hours used by the facility
26 b. Report hours saved by using early off and push buttons by users.
27
28 G. Communication Costs: Manufacturer shall include communication costs for operating the
29 control and monitoring system for a period of 25 years.
30
31 H. Communication with luminaire drivers: Control system shall interface with drivers in electrical
32 components enclosures by means of powerline communication
33

34 2.4 STRUCTURAL PARAMETERS

- 35
36 A. Wind Loads: Wind loads shall be based on the 2012 International Building Code. Wind loads
37 to be calculated using ASCE 7-10, an ultimate design wind speed of 115 and exposure
38 category C.
39
40 B. Pole Structural Design: The stress analysis and safety factor of the poles shall conform to
41 2009 AASHTO Standard Specification for Structural Supports for Highway Signs,
42 Luminaires, and Traffic Signals (LTS-5).
43
44 C. Foundation Design: The foundation design shall be based on soil parameters as outlined in
45 the geotechnical report. If no geotechnical report is available, the foundation design shall be
46 based on soils that meet or exceed those of a Class 5 material as defined by 2015 IBC
47 Table 1806.2.
48
49

50 PART 3 - EXECUTION

1 3.1 SOIL QUALITY CONTROL

- 2
- 3 A. It shall be the Contractor's responsibility to notify the Owner if soil conditions exist other than
- 4 those on which the foundation design is based, or if the soil cannot be readily excavated.
- 5 Contractor may issue a change order request / estimate for the Owner's approval / payment
- 6 for additional costs associated with:
- 7 1. Providing engineered foundation embedment design by a registered engineer in the
- 8 State of Texas for soils other than specified soil conditions.
- 9 2. Additional materials required to achieve alternate foundation.
- 10 3. Excavation and removal of materials other than normal soils, such as rock, caliche, etc.

11

12 3.2 DELIVERY TIMING

- 13
- 14 A. Delivery Timing Equipment On-Site: The equipment must be on-site 6-8 weeks from receipt
- 15 of approved submittals and receipt of complete order information.

16

17 3.3 FIELD QUALITY CONTROL

- 18
- 19 A. Illumination Measurements: Upon substantial completion of the project and in the presence
- 20 of the Contractor, Project Engineer, Owner's Representative, and Manufacturer's
- 21 Representative, illumination measurements shall be taken and verified. The illumination
- 22 measurements shall be conducted in accordance with IESNA LM-5-04.
- 23
- 24 B. Field Light Level Accountability
- 25 1. Light levels are guaranteed not to fall below the target maintained light levels for the
- 26 entire warranty period of 25 years. These levels will be specifically stated as
- 27 "guaranteed" on the illumination summary provided by the manufacturer.
- 28 2. The contractor/manufacturer shall be responsible for conducting initial light level testing
- 29 and an additional inspection of the system, in the presence of the owner, one year from
- 30 the date of commissioning of the lighting.
- 31 3. The contractor/manufacturer will be held responsible for any and all changes needed to
- 32 bring these fields back to compliance for light levels and uniformities.
- 33 Contractor/Manufacturer will be held responsible for any damage to the fields during
- 34 these repairs.
- 35
- 36 C. Correcting Non-Conformance: If, in the opinion of the Owner or his appointed
- 37 Representative, the actual performance levels including footcandles and uniformity ratios are
- 38 not in conformance with the requirements of the performance specifications and submitted
- 39 information, the Manufacturer shall be required to make adjustments to meet specifications
- 40 and satisfy Owner.

41

42 3.4 WARRANTY AND GUARANTEE

- 43
- 44 A. 25-Year Warranty: Each manufacturer shall supply a signed warranty covering the entire
- 45 system for 25 years from the date of shipment. Warranty shall guarantee specified light
- 46 levels. Manufacturer shall maintain specifically-funded financial reserves to assure fulfillment
- 47 of the warranty for the full term. Warranty does not cover weather conditions events such as
- 48 lightning or hail damage, improper installation, vandalism or abuse, unauthorized repairs or
- 49 alterations, or product made by other manufacturers.

- 1 B. Maintenance: Manufacturer shall monitor the performance of the lighting system, including
2 on/off status, hours of usage and luminaire outage for 25 years from the date of equipment
3 shipment. Parts and labor shall be covered such that individual luminaire outages will be
4 repaired when the usage of any field is materially impacted. Manufacturer is responsible for
5 removal and replacement of failed luminaires, including all parts, labor, shipping, and
6 equipment rental associated with maintenance. Owner agrees to check fuses in the event of
7 a luminaire outage.
8

9
10 PART 4 - DESIGN APPROVAL

11
12 4.1 PRE-BID SUBMITTAL REQUIREMENTS (NON-MUSCO)

- 13
14 A. Design Approval: The owner / engineer will review pre-bid submittals per section 4.0.B from
15 all the manufacturers to ensure compliance to the specification 10 days prior to bid. If the
16 design meets the design requirements of the specifications, a letter and/or addendum will be
17 issued to the manufacturer indicating approval for the specific design submitted.
18
19 B. Approved Product: Musco's Light-Structure System™ with TLC for LED™ is the approved
20 product. All substitutions must provide a complete submittal package for approval as outlined
21 in Submittal Information at the end of this section at least 10 days prior to bid. Special
22 manufacturing to meet the standards of this specification may be required. An addendum will
23 be issued prior to bid listing any other approved lighting manufacturers and designs.
24
25 C. All listed manufacturers not pre-approved shall submit the information at the end of this
26 section at least 10 days prior to bid. An addendum will be issued prior to bid; listing approved
27 lighting manufacturers and the design method to be used.
28
29 D. Bidders are required to bid only products that have been approved by this specification or
30 addendum by the owner or owner's representative. Bids received that do not utilize an
31 approved system/design, will be rejected.
32

REQUIRED SUBMITTAL INFORMATION FOR ALL MANUFACTURERS (NOT PRE-APPROVED) 10 DAYS PRIOR TO BID

All items listed below are mandatory, shall comply with the specification and be submitted according to pre-bid submittal requirements. Complete the Yes/No column to indicate compliance (Y) or noncompliance (N) for each item. **Submit checklist below with submittal.**

Yes / No	Tab	Item	Description
	A	Letter/ Checklist	Listing of all information being submitted must be included on the table of contents. List the name of the manufacturer's local representative and his/her phone number. Signed submittal checklist to be included.
	B	Equipment Layout	Drawing(s) showing field layouts with pole locations
	C	On Field Lighting Design	Lighting design drawing(s) showing: Field Name, date, file number, prepared by Outline of field(s) being lighted, as well as pole locations referenced to the center of the field (x & y), Illuminance levels at grid spacing specified Pole height, number of fixtures per pole, horizontal and vertical aiming angles, as well as luminaire information including wattage, lumens and optics Height of light test meter above field surface. Summary table showing the number and spacing of grid points; average, minimum and maximum illuminance levels in foot candles (fc); uniformity including maximum to minimum ratio, coefficient of variance (CV), coefficient of utilization (CU) uniformity gradient; number of luminaires, total kilowatts, average tilt factor; light loss factor.
	D	Off Field Lighting Design	Lighting design drawing showing initial spill light levels along the boundary line (defined on bid drawings) in footcandles. Lighting design showing glare along the boundary line in candela. Light levels shall be taken at 30-foot intervals along the boundary line. Readings shall be taken with the meter orientation at both horizontal and aimed towards the most intense bank of lights.
	E	Photometric Report	Provide first page of photometric report for all luminaire types being proposed showing candela tabulations as defined by IESNA Publication LM-35-02. Photometric data shall be certified by laboratory with current National Voluntary Laboratory Accreditation Program or an independent testing facility with over 5 years' experience.
	F	Performance Guarantee	Provide performance guarantee including a written commitment to undertake all corrections required to meet the performance requirements noted in these specifications at no expense to the owner. Light levels must be guaranteed to not fall below target levels for warranty period.
	G	Structural Calculations	Pole structural calculations and foundation design showing foundation shape, depth backfill requirements, rebar and anchor bolts (if required). Pole base reaction forces shall be shown on the foundation drawing along with soil bearing pressures. Design must be stamped by a structural engineer in the state of Texas, if required by owner.
	H	Control & Monitoring System	Manufacturer of the control and monitoring system shall provide written definition and schematics for automated control system. They will also provide ten (10) references of customers currently using proposed system in the state of Texas.
	I	Electrical Distribution Plans	Manufacturer bidding an alternate product must include a revised electrical distribution plan including changes to service entrance, panels and wire sizing, signed by a licensed Electrical Engineer in the state of Texas.
	J	Warranty	Provide written warranty information including all terms and conditions. Provide ten (10) references of customers currently under specified warranty in the state of Texas.
	K	Project References	Manufacturer to provide a list of ten (10) projects where the technology and specific fixture proposed for this project has been installed in the state of Texas. Reference list will include project name, project city, installation date, and if requested, contact name and contact phone number.

L	Product Information	Complete bill of material and current brochures/cut sheets for all product being provided.
M	Delivery	Manufacturer shall supply an expected delivery timeframe from receipt of approved submittals and complete order information.
N	Non-Compliance	Manufacturer shall list all items that do not comply with the specifications. If in full compliance, tab may be omitted.
O	Cost of Ownership	Document cost of ownership as defined in the specification. Identify energy costs for operating the luminaires. Maintenance cost for the system must be included. All costs should be based on 25 Years
P	Environmental Light Control Design	Environmental glare impact scans must be submitted showing the maximum candela from the field edge on a map of the surrounding area until specified candela value or less is achieved.

The information supplied herein shall be used for the purpose of complying with the specifications for Dripping Springs Sports & Recreation Park Relight. By signing below I agree that all requirements of the specifications have been met and that the manufacturer will be responsible for any future costs incurred to bring their equipment into compliance for all items not meeting specifications and not listed in the Non-Compliance section.

Manufacturer: _____

Signature: _____

Contact Name: _____

Date: ____/____/____

Contractor: _____

Signature: _____