

# ESTIMATE

Kyle Landscaping Services  
110 DASHELLE RUN  
KYLE, TX 78640

kylelandscapingservices@live.com  
+1 (512) 787-9989  
www.kylelandscapingservices.com



## City of Dripping Springs

### Bill to

City of Dripping Springs  
511 W Mercer St  
Dripping Springs, TX 78620

### Estimate details

Estimate no.: 1039  
Estimate date: 05/30/2024

#	Date	Product or service	Description	Qty	Rate	Amount
1.		<b>Irrigation Install</b>	<ul style="list-style-type: none"><li>-New Irrigation System</li><li>-Components</li><li>- Hunter HPC 2400 WiFi/Cell Kit</li><li>Outdoor</li><li>- Hunter Rain-Freeze Sensor.</li><li>- I25-04-R Hunter 1IN Reclaimed</li><li>- Hunter PGV Globe Valve for all zones, Will be ran from controller to each individual zone.</li><li>- 16 Gauge UL rated wire for all zones</li><li>- 2" BBV-1 Full Port Threaded Ball Valve at all valves for shut off.</li><li>- Will use Sched 80 Nipples for all threaded components.</li><li>- All ball valves will be threaded brass.</li><li>- All piping &amp; rotors will be reclaimed.</li><li>- All pipping will be Sched 40</li><li>- Purple primer and Christy's Red Hot will be used to achieve maximum hold.</li><li>- All trenching will be done by AquaLED, LLC. will trench to 12" for main line and 6" for lateral lines. Once everything has been glued and let dry for a full 24H, trenches will be covered back to original grade.</li><li>- All valves will be in their own valve box as well as all boxes will have a purple lids.</li><li>- One quick couplers on field behind pitchers mound with shutoff. Will use Hunter Reclaimed Quick coupler and keys will be provided with swivel for quick couplers. Will be in its individual</li></ul>	1	\$55,796.45	\$55,796.45

1 \$42,550.20 \$42,550.20  
box with purple lid.  
- All construction debris haul off and site  
clean up.  
-Includes two baseball fields.  
- Installation will have a 1 Year  
manufacture defect warranty.  
-Irrigation system will start at the existing  
booster pump, mainline will run  
between  
both fields and T off to each field.  
-Each field will have its own shut off.

---

2.	<b>Irrigation Install</b>	-New Booster Pump. Pump on site seems to be rusting out from the main head. This includes replacing pump and wiring to the electrical panel.	1	\$4,245.25	\$4,245.25
----	---------------------------	--	---	------------	------------

---

3.		BuyBoard #705-23			
----	--	------------------	--	--	--

---

**Total** **\$60,041.70**

---