

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS

CITY OF DRIPPING SPRINGS
CONSTRUCTION PLANS FOR
ROADWAY IMPROVEMENTS ON SHANE LANE

CONT	SECT	JOB	HIGHWAY
			SHANE LN
DIST	COUNTY		SHEET NO.
AUS	HAYS		1

DESIGN SPEED
 SHANE LANE/GOLDEN EAGLE LN: 30 MPH

NET LENGTH OF PROJECT = 509.00 FEET = 0.096 MILES


HAYS COUNTY
SHANE LANE ROADWAY IMPROVEMENTS

FROM: SHANE LANE/GOLDEN EAGLE LN
 TO: SOUTH OF RUNNING DEER LN

FOR THE RECONSTRUCTION OF ROADWAY INTERSECTION

CONSISTING OF GRADING, BASE, ASPHALT, DRAINAGE,
 PEDESTRIAN FACILITIES, EROSION CONTROL, SIGNING, AND
 PAVEMENT MARKINGS.

10.04.23




Leslie D. Pollack



HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900

TDLR INSPECTION IS NOT REQUIRED



LOCATION MAP NOT TO SCALE

EXCEPTIONS: NONE
 EQUATIONS: NONE
 RAILROAD CROSSINGS: NONE

FILE: \$FILE\$
 DATE: 10/4/2023 8:30:15 AM

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF
 TRANSPORTATION ON NOVEMBER 1, 2014 SHALL GOVERN ON THIS PROJECT.

CONSULTANT:



HDR ENGINEERING, INC (TBPE FIRM REG. F-754)

SUBMITTED FOR LETTING:


10-4-2023

CHAD CARPIN
 CITY ENGINEER

CITY OF DRIPPING SPRINGS

SHEET NUMBERS	DESCRIPTION
I. GENERAL	
1	TITLE SHEET
2	INDEX OF SHEETS
3	PROJECT LAYOUT
4 - 5	TYPICAL SECTIONS
6 - 10	GENERAL NOTES
11	SUMMARY OF QUANTITIES
II. TRAFFIC CONTROL PLAN	
12	TRAFFIC CONTROL AND SEQUENCE OF CONSTRUCTION
13	DETOUR PLAN
<i>TRAFFIC CONTROL STANDARDS</i>	
14 - 18	BC(1)-21 THRU BC(5)-21 *
19 - 22	BC(7)-21 THRU BC(10)-21 *
23	WZ(RCD)-13 *
III. ROADWAY PLANS	
24	HORIZONTAL ALIGNMENT DATA
25	REMOVAL LAYOUT
26 - 27	ROADWAY PLAN AND PROFILE
28	DRIVEWAY AND SIDEWALK PLAN AND PROFILE
<i>ROADWAY STANDARDS</i>	
29	GF(31)-19 *
30	GF(31)MS-19 *
31	SGT(11S)31-18 *
32	SGT(12S)31-18 *
33	SGT(15)31-20 *
IV. DRAINAGE PLANS	
34	EXISTING DRAINAGE AREA MAP
35	PROPOSED DRAINAGE AREA MAP
36	CULVERT 01 LAYOUT
37	DRAINAGE DETAILS
<i>DRAINAGE STANDARDS</i>	
38	PDD *
39	PB *
40	PBGC *
41	PAZD-CZ *
42 - 43	SETP-CD *
44	PSET-SC *
45	PSET-RC *
46	PSET-RR *
V. SIGNING AND PAVEMENT MARKING PLANS	
47	SIGNING AND PAVEMENT MARKING PLAN
<i>SIGNING AND PAVEMENT MARKING STANDARDS</i>	
48	D & OM(1)-20 *
49	D & OM(2)-20 *
50	D & OM(3)-20 *
51	D & OM(5)-20 *
52	D & OM(VIA)-20 *
VI. ENVIRONMENTAL PLANS	
53	ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)
54	SW3P NARRATIVE
55 - 56	SW3P LAYOUT
<i>ENVIRONMENTAL STANDARDS</i>	
57	EC(1)-16 *
58	EC(2)-16 *
59	EC(3)-16 *


PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH - Index of Sheets
 PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:10:59 AM
 SCALE: 1:1



* THE STANDARD SHEETS SPECIFICALLY IDENTIFIED ABOVE HAVE BEEN SELECTED BY ME OR UNDER MY RESPONSIBLE SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.

NO.	DATE	REVISION	APPROVED
<div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> <p>HDR HDR Firm Registration No. F-754 710 Hesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900</p> </div>			
<div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> <p>THE CITY OF DRIPPING SPRINGS TEXAS © 2023</p> </div>			
ROGER HANKS			
INDEX OF SHEETS			
SHEET 1 OF 1			
DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
JC			RH
GRAPHICS	STATE	DISTRICT	COUNTY
LG	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB
CHECK			2

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH - Project Layout
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023
 TIME: 8:10 AM
 SCALE: 1:100




LEGEND

- PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
- - - EXISTING RIGHT OF WAY
- PROPOSED RIGHT OF WAY
- PROPOSED CONSTRUCTION BY OTHERS
- TRAVEL LANE
- ⊕ BENCHMARK POINT

- NOTES:**
- SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ALIGNMENT INFORMATION.
 - EXISTING ROW IS BASED ON BEST AVAILABLE INFORMATION FROM HAYS COUNTY APPRAISAL DISTRICT AND AVAILABLE SITE PLANS.

CONTROL NOTE:
 BASIS OF BEARING IS THE TEXAS COORDINATE SYSTEM, SOUTH CENTRAL ZONE (4204), NORTH AMERICA DATUM 1983 (NAD83), 2011 ADJUSTMENT (EPOCH 2010) AND A VERTICAL DATUM OF NAVD88, GEOID 12B. ALL COORDINATE VALUES AND DISTANCES SHOWN ARE GRID VALUES UNITS: US SURVEY FEET.
 THE SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE COMMITMENT. EASEMENTS OR OTHER MATTERS OF RECORD MAY EXIST WHERE NON ARE SHOWN.



STATE OF TEXAS
 FELIPE S. TUTTUD
 104836
 LICENSED PROFESSIONAL ENGINEER
 10/04/2023
Felipe Tuttud

NO.	DATE	REVISION	APPROVED

HDR
 HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900


THE CITY OF
DRIPPING SPRINGS
 TEXAS
 © 2023

ROGER HANKS
PROJECT LAYOUT


SHEET 1 OF 1

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
JC				RH
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
LG	TEXAS	AUS	HAYS	3
CHECK	CONTROL	SECTION	JOB	


PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH - Typical Sections 1 of 2
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023 TIME: 8:11:3 AM SCALE: 1:10



**SHANE LANE
EXISTING TYPICAL SECTION**



**SHANE LANE
PROPOSED TYPICAL SECTION**
BEGIN PROJECT TO STA 103+10



NO.	DATE	REVISION	APPROVED

HDR
 HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900



ROGER HANKS




TYPICAL SECTIONS

SHEET 1 OF 2


DESIGN JC	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS LG	STATE	DISTRICT	COUNTY	RH SHEET NO.
CHECK	TEXAS	AUS	HAYS	4
CHECK	CONTROL	SECTION	JOB	

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH - Typical Sections 2 of 2


PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:11:5 AM
 SCALE: 1:10



DETAIL 'A'




DETAIL 'B'



RIBBON CURB DETAIL

NOTES:

- PER HAYS COUNTY SPECIFICATIONS, WHENEVER A SOIL INVESTIGATION INDICATES THAT MORE THAN TWO FEET OF EXPANSIVE SUBGRADE SOIL WITH A P.I. OF 35 OR GREATER EXISTS BENEATH THE EXPECTED BASE LAYER, THE DESIGN PROFESSIONAL SHALL INCORPORATE A COMBINATION OF THE TWO MEASURES DESCRIBED IN (COA TCM 3.1.3).
- SECTIONS TO BE VERIFIED AFTER ROUGH CUT OF ROAD PER GEOTECHNICAL ASSESSMENT SUBGRADE CONDITIONS.
- ASPHALTIC BINDER SHALL BE PG-76 PER COLLECTORS AND ARTERIALS.



NO.	DATE	REVISION	APPROVED

HDR
 HDR
 Firm Registration No. F-754
 710 Heisters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900



ROGER HANKS
TYPICAL SECTIONS

SHEET 2 OF 2

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
JC				RH
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
LG	TEXAS	AUS	HAYS	5
CHECK	CONTROL	SECTION	JOB	

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

GENERAL NOTES:

Item	Description	**Rate
**204	Sprinkling (Dust) (Item 132) (Item 247)	30 GAL/CY 30 GAL/CY 30 GAL/CY
**210	Rolling (Flat Wheel) (Item 247) (Item 316)	1 HR/200 TON 1 HR/6000 SY
**210	Rolling (Tamping and Heavy Tamping)	1 HR/200 CY
**210	Rolling (Lt Pneumatic Tire) (Item 132) (Item 247) (Item 316 - Seal Coat) (Item 316 - Two Course)	1 HR/500 CY 1 HR/200 TON 1 HR/6000 SY 1 HR/3000 SY
247	Flexible Base (CMP IN PLC)	132 LB/CF
310	Prime Coat	0.20 GAL/SY
3076	Dense-Graded Hot-Mix Asphalt	110 LB/SY/IN
	Tack Coat	0.08 GAL/SY

** For Informational Purposes Only

GENERAL

Contractor questions on this project are to be addressed to the following individual(s):

Company: HDR Engineering, Inc. Email: Leslie.Pollack@hdrinc.com Phone: (512) 904-3728

Contractor questions and request for documents will be accepted through email, phone, and in person by the above individuals.

All Contractor questions will be reviewed by the Engineer.

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved.

If work is performed at Contractor's option, when inclement weather is impending, and the work is damaged by subsequent precipitation, the Contractor is responsible for all costs associated with replacing the work, if required.

The roadbed will be free of organic material prior to placing any section of the pavement structure.

Equip all construction equipment used in roadway work with highly visible omnidirectional flashing warning lights.

Provide a smooth, clean sawcut along the existing asphalt or concrete pavement structure, as directed. Consider subsidiary to the pertinent Items.

General Notes

Sheet A

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

Construct all manholes/valves to final pavement elevations prior to the placement of final surface. If the manholes/valves are going to be exposed to traffic, place temporary asphalt around the manhole/valve to provide a 50:1 taper. The asphalt taper is subsidiary to the ACP work.

Use a self-contained vacuum broom to sweep the roadway and keep it free of sediment as directed. The contractor will be responsible for any sweeping above and beyond the normal maintenance required to keep fugitive sediment off the roadway as directed by the Engineer.

Damage to existing pipes and SET's due to Contractor operations will be repaired at Contractor's expense.

All locations used for storing construction equipment, materials, and stockpiles of any type, within the right of way, will be as directed. Use of right of way for these purposes will be restricted to those locations where driver sight distance to businesses and side street intersections is not obstructed and at other locations where an unsightly appearance will not exist. The Contractor will not have exclusive use of right of way but will cooperate in the use of the right of way with the city/county and various public utility companies as required.

CONTROL OF THE WORK

Place construction stakes at intervals of no more than 100 ft. This work is subsidiary.

Electronic Shop Drawing Submittals.

Submit electronic shop drawing submittals according to the current [Guide to Electronic Shop Drawing Submittal](https://www.txdot.gov/business/resources/highway/bridge/shop-drawing-submittal-cycle.html) <https://www.txdot.gov/business/resources/highway/bridge/shop-drawing-submittal-cycle.html>. Pre-approved producers can be found online at <https://www.txdot.gov/business/resources/materials/material-producer-list.html>.

CONTROL OF MATERIALS

Give a minimum of 1 business day notice for materials, which require inspection.

For structures with paint containing hazardous materials, provide locations of material removal 60 days prior to begin removal. For metal elements to be removed, mechanical shear or unbolting for removal and disposal does not require paint abatement but requires 60 day advance notice.

LEGAL RELATIONS AND RESPONSIBILITIES

TxDOT will coordinate with TDLR regarding pedestrian elements and sidewalks. The contractor will procure and provide all permits, licenses, and inspections; pay all charges, fees, and taxes regarding TDLR rules governing industrialized housing and buildings.




No significant traffic generator events identified.

Refer to the Environmental Permits, Issues and Commitments (EPIC) plan sheets for additional requirements and permits.

Perform maintenance of vehicles or equipment at designated maintenance sites. Keep a spill kit on-site during fueling and maintenance. This work is subsidiary.

General Notes

Sheet B

			
			
HDR Firm Registration No. F-754 710 Hesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900			
			
THE CITY OF DRIPPING SPRINGS TEXAS © 2023			
ROGER HANKS GENERAL NOTES			
SHEET 1 OF 5			
DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS			RH
AT	STATE	DISTRICT	COUNTY
CHECK	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB
			6

PLOT DRIVER: TxDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RHGN01.dgn (General notes 01)
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023
 TIME: 8:11:16 AM
 SCALE: 1:1

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

Maintain positive drainage for permanent and temporary work for the duration of the project. Be responsible for any items associated with the temporary or interim drainage and all related maintenance. This work is subsidiary.

Suspend all activities near any significant recharge features, such as sinkholes, caves, or any other subterranean openings that are discovered during construction or core sampling. Do not proceed until the designated Geologist or TCEQ representative is present to evaluate and approve remedial action.

Locate aboveground storage tanks kept on-site for construction purposes in a contained area as to not allow any exposure to soils. The containment will be sized to capture 150% of the total capacity of the storage tanks.

Migratory Birds and Bats.

Migratory birds and bats may be nesting within the project limits and concentrated on roadway structures such as bridges and culverts. Remove all old and unoccupied migratory bird nests from any structures, trees, etc. between September 16 and February 28. Prevent migratory birds from re-nesting between March 1 and September 15. Prevention shall include all areas within 25 ft. of proposed work. All methods used for the removal of old nesting areas and the prevention of re-nesting must be submitted to the Engineer 30 business days prior to begin work. This work is subsidiary.

If active nests are encountered on-site during construction, all construction activity within 25 ft. of the nest must stop. Contact the Engineer to determine how to proceed.

Tree and Brush Trimming and Removal.

Work will be conducted September 16 thru February 28. Work conducted outside this timeframe will require a bird survey. Submit a survey request to the Engineer 30 business days prior to begin work.

No extension of time or compensation will be granted for a delay or suspension due to the above bird and tree/brush requirements.

Back Up Alarm.

For hours 9 P to 5 A, utilize a non-intrusive, self-adjusting noise level reverse signal alarm. This is not applicable to hotmix operations. This is subsidiary.

ITEM 100 - PREPARING RIGHT OF WAY

Prep ROW must not begin until accessible trees designated for preservation have been protected, items listed in the EPIC have been addressed, and SW3P controls installed in accessible areas.

Backfill material will be Type B Embankment using ordinary compaction.

Follow Item 752.4 Work Methods and Item 752 general notes when removing or working on or near trees and brush.

General Notes

Sheet C

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

Unless shown otherwise in the plans or a designated non-mow area, perform trimming or removal for areas within 30 ft. of edge of pavement under construction. Trim or remove to provide minimum of 5 ft. of horizontal clearance and 7 ft. of vertical clearance for the following: sidewalks, paths, guard fence, rails, signs, object markers, and structures. Trim to provide a minimum of 14 ft. vertical clearance under all trees. This work is subsidiary.

ITEM 105 – REMOVING TREATED AND UNTREATED BASE AND ASPHALT PAVEMENT

Existing typical is based on information available. This typical may not account for all maintenance work such as overlays or pavement repairs. A change in material type or thickness does not warrant additional payment. Payment is full compensation for removing all material to the depth specified.

ITEM 110 – EXCAVATION

The Engineer will define unsuitable material.

ITEM 132 – ALL EMBANKMENT

The Engineer will define unsuitable material. Material which the Contractor might deem to be unsuitable due to moisture content will not be considered unsuitable material.

Prior to begin embankment of existing area, correct or replace unstable material to a depth of 6 in. below existing grade. Embankment areas will be inspected prior to beginning work.

Rock or broken concrete produced by the project is allowed in earth embankments. The size of the rock or broken concrete will not exceed the layer thickness requirements in Section 132.3.4., "Compaction Methods." The material will not be placed vertically within 5 ft. of the finished subgrade elevation.

ITEM 160 - TOPSOIL

Off-site topsoil will have a minimum PI of 25.

No Sandy Loam allowed.

Obtain approval of the actual depth of the topsoil sources for both on-site and off-site sources. Construct topsoil stockpiles of no more than five (5) feet in height.

It is permissible to use topsoil dikes for erosion control berms within the right of way, as directed.

Seed or track slopes within 14 days of placement.

Salvage topsoil from sites of excavation and embankment. Maximum salvage depth is 6 inches.


Windrowing of topsoil obtained from the Right of Way (ROW) is not allowed.

ITEM 168 – VEGETATIVE WATERING

Water all areas of project to be seeded or sodded. Watering is subsidiary to pay item 164 seeding for revegetation.

General Notes


Sheet D



NO.	DATE	REVISION	APPROVED

HDR

HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900



THE CITY OF
DRIPPING SPRINGS
 TEXAS © 2023

ROGER HANKS

GENERAL NOTES

SHEET 2 OF 5

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
			RH
GRAPHICS AT	STATE	DISTRICT	COUNTY
CHECK	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB
			7

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RHGN02.dgn (General notes 02)
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023
 TIME: 8:11:22 AM
 SCALE: 1:1

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

Maintain the seedbed in a condition favorable for the growth of grass. Watering can be postponed immediately after a rainfall on the site of ½ inch or greater, but will be resumed before the soil dries out. Continue watering until grass is 1.5 inches high with 70% coverage.

Vegetative watering rates and quantities are based on ¼ inch of watering per week over a 3-month watering cycle. The actual rates used will be as directed and will be based on prevailing weather conditions to maintain the seedbed.

Obtain water at a source that is metered (furnish a current certification of the meter being used) or furnish the manufacturer's specifications showing the tank capacity for each truck used. Notify the Engineer, each day that watering takes place, before watering, so that meter readings or truck counts can be verified.

ITEM 204 – SPRINKLING

Apply water for dust control as directed. When dust control is not being maintained, cease operations until dust control is maintained. Consider subsidiary to the pertinent Items.

ITEM 216 - PROOF ROLLING

Correct and perform "Proof Rolling" retest at the Contractor's expense, to the satisfaction of the Engineer, when initial "Proof Rolling" yields a failing result.

ITEM 247 - FLEXIBLE BASE

The layer thickness will be 6 in. max unless shown on the plans. Placing in a single layer is allowed when total thickness of base is 8 in. or less. When placed in multiple layers, compact the bottom and middle layers to at least 95% and 98% of the maximum dry density, respectively. When placed in a single layer or the final layer, compact to at least 100%.

Correction of subgrade soft spots is subsidiary.

Complete per plans the subgrade, ditches, slopes, and drainage structures prior to the placement of base.

Do not use a vibratory roller to compact base placed directly on top of a drainage structure.

ITEMS 260 THRU 276 – SUBGRADE TREATMENTS AND BASE

Use ordinary compaction for subgrade treatment.

Three weeks prior to treatment, provide a sample of soil or flexible base to be treated.

ITEM 260 - LIME TREATMENT (ROAD-MIXED)

For sulfate content greater than 3000 ppm, mix in an additional 4.0% points above optimum moisture after initial mixing and prior to mellow.

If the sulfate content is greater than 7000 ppm, do not treat. Undercut the unsuitable material to the depth per bid item for lime treatment and replace unsuitable material in accordance with Item 110. Payment will be made in accordance with Item 110.

General Notes

Sheet E

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

ITEM 300s – SURFACE COURSES AND PAVEMENTS

Asphalt season is May 1 thru September 15. The latest work start date for asphalt season is August 1.

ITEM 310 – PRIME COAT

Apply blotter material to all driveways and intersections. This work is subsidiary.

When Multi Option is allowed, provide MC 30, EC 30 or AE-P.

Rolling to ensure penetration is required.

ITEM 320 - EQUIPMENT FOR ASPHALT CONCRETE PAVEMENT

Use of motor grader is allowed for placement of mixtures greater than 10 inches from the riding surface, when hot-mix is used in lieu of flexible base, or as allowed.

ITEM 3076 THRU 3082 - HOT-MIX ASPHALT PAVEMENT

Core holes may be filled with an Asphaltic patching material meeting the requirements of DMS-9203 or with SCM meeting requirements of DMS-9202.

Install transverse butt joints with 50 ft. H: 1 in. V transition from the new ACP to the existing surface. Saw cut the existing pavement at the butt joints. This work is subsidiary.

Use a device to create a maximum 3H:1V notched wedge joint on all longitudinal joints of 2 in. or greater. This work is subsidiary.

Ensure placement sequence to avoid excess distance of longitudinal joint lap back not to exceed one day's production rates.

Submit any proposed adjustments or changes to a JMF before production of the new JMF.

Tack every layer. Do not dilute tack coat. Apply it evenly through a distributor spray bar.


Irregularities will require the replacement of a full lane width using an asphalt paver. Replace the entire subplot if the irregularities are greater than 40% of the subplot area.

Lime or an approved anti-stripping agent must be used when crushed gravel is utilized to meet a SAC "A" requirement.

When using RAP or RAS, include the management methods of processing, stockpiling, and testing the material in the QCP submitted for the project. If RAP and RAS are used in the same mix, the QCP must document that both of these materials have dedicated feeder bins for each recycled material. Blending of RAP and RAS in one feeder bin or in a stockpile is not permitted.

General Notes


Sheet F



NO.	DATE	REVISION	APPROVED

HDR

HDR
Firm Registration No. F-754
710 Heisters Crossing, Suite 150
Round Rock, Texas 78681
512.685.2900



THE CITY OF
DRIPPING SPRINGS
TEXAS © 2023

ROGER HANKS

GENERAL NOTES

SHEET 3 OF 5

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
				RH
GRAPHICS AT	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	AUS	HAYS	8
CHECK	CONTROL	SECTION	JOB	

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RHGN03.dgn (General notes 03)
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023 TIME: 8:11:28 AM SCALE: 1:1

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

Asphalt content and binder properties of RAP and RAS stockpiles must be documented when recycled asphalt content greater than 20% is utilized.
No RAS is allowed in surface courses.

Department approved warm-mix additives is required for all surface mix application when RAP is used. Dosage rates will be approved during JMF approval.

The Hamburg Wheel Test will have a minimum rut depth of 3mm except for SMA with HPG or PG 76.

ITEM 3076 - DENSE-GRADED HOT-MIX ASPHALT

Use the SGC for design and production testing of all mixtures. Design all Type D mixtures as a surface mix, maximum 15% RAP and no RAS. Contractor may not use a substitute PG binder for 76-22. When using substitute binders, mold specimens for mix design and production at the temperature required for the substitute binder used to produce the HMA.

The Hamburg Wheel minimum number of passes for PG 64 or lower is reduced to 7,000. The Engineer may accept Hamburg Wheel test results for production and placement if no more than 1 of the 5 most recent tests is below the specified number of passes and the failing test is no more than 2,000 passes below the specified number of passes.

ITEM 432 - RIPRAP

Mow strip riprap will be 4 in. and all other riprap will be 5 in. unless otherwise shown on the plans. Fiber reinforcement is not allowed. GFRP is allowed reinforcement for all applications.

SGT approach taper will be seeded and graded at 10:1 or flatter per MBGF (MOW STRIP) standard and considered subsidiary to pertinent items. Placement will be ordinary compaction and does not require placement using an asphalt paver.

ITEM 465 - JUNCTION BOXES, MANHOLES, AND INLETS

Construct cast-in-place reinforced concrete apron as shown in the standards. This work is subsidiary.

Backfill shall use cohesionless material per Item 400 or flowable fill if width between structure and extent of excavation is 2 ft. or less. This is subsidiary.

ITEM 467 - SAFETY END TREATMENT

Field adjust pipe end to maintain the necessary slope. Field cutting of pipe end is allowed. Coat all metal field cuts or exposed reinforcement with asphalt paint.

ITEM 502 - BARRICADES, SIGNS, AND TRAFFIC HANDLING

Cover, relocate, or remove existing signs that conflict with traffic control. This work is subsidiary.

Install all permanent signs, delineation, and object markers required for the operation of the roadway before opening to traffic. Use of temporary mounts is allowed or may be required until

General Notes

Sheet G

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

the permanent mounts are installed or not impacted by construction. Maintain the temporary mounts. This work is subsidiary.

Place a 28-inch cone, meeting requirements of BC (10), on top of foundations that have protruding studs. This work is subsidiary.

Edge condition treatment types must be in accordance with the TxDOT standard. Installation and removal of a safety slope is subsidiary.

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

ITEM 506 - TEMPORARY EROSION, SEDIMENTATION, AND ENV CONTROLS

Install, maintain, remove control measures in areas of the right of way utilized by the Contractor that are outside the limits of disturbance required for construction. Permanently stabilize the area. This work is subsidiary.

Erosion control measures must be initiated immediately in areas where construction activities have ceased and will not resume for a period exceeding 14 calendar days. Vertical track all exposed soil, stockpiles, and slopes. Re-track after each rain event or every 14 days, whichever occurs first. Sheep foot roller is allowed for vertical tracking. This work is subsidiary.

Unless a specific pay item is provided in the plans, the installation of the 6:1 or flatter for RFD side slopes in the safety zone will be subsidiary to pertinent bid items.

ITEMS 528, 529, 530, 531, & 536 - MISCELLANEOUS CONSTRUCTION

Reinforcement will be in accordance with Section 432.3.1 unless shown on the plans. Fiber reinforcement is not allowed. GFRP is allowed reinforcement for all applications. Class A and B Concrete are allowed to use Coarse Aggregate Grades 1-8.


Unless shown on the plans, all concrete will be 5 in. thick and have 2 in. sand, base, or RAP bedding. Furnish base meeting the requirement for any type or grade in accordance with Item 247. Compressive strengths for flexible base are waived. RAP must be 100% passing a 1 in. sieve. Bedding and flexible base must be placed using ordinary compaction.



Expansion joints will be placed every 40 ft. Expansion joints must be 1 in. wide asphalt board and flush with the surface. The bottom of the asphalt board will be at half the depth of the concrete. The reinforcement will be continuous thru the expansion joint.

Sidewalk cross slope must not exceed 1.5%.

General Notes

Sheet H



NO.	DATE	REVISION	APPROVED
 <div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> HDR Firm Registration No. F-754 710 Hesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900 </div>			
 <div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> THE CITY OF DRIPPING SPRINGS TEXAS © 2023 </div>			
ROGER HANKS GENERAL NOTES			
SHEET 4 OF 5			
DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS AT	STATE	DISTRICT	COUNTY
CHECK	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB
			9

PLOT DRIVER: TxDOT_PDF_BW.pltctg
USER: LGOMEZGONZ
FILE: RHGN04.dgn (General notes 04)
PENTABLE: 10338078.tbl
DATE: 10/4/2023
TIME: 8:11:34 AM
SCALE: 1:1

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

If roots are encountered verify with the Engineer before accommodating or removing 2 in. diameter or larger roots. Root removal must be in accordance with Section 752.4.2. Roots may remain in the bedding or base. For improvements within 6 in. of a root, the concrete thickness may be reduced by 1 in. and the bedding increased by 1 in. to minimize impacts to the roots. Adjust bedding and surface profile to provide a 1 in. bedding cushion around the roots. The surface profile may be adjusted to the extent allowed by ADA. This work is subsidiary.

ITEM 530 – INTERSECTIONS, DRIVEWAYS, AND TURNOUTS

Notify property owners at least 48 hr. before beginning work on their driveway. Provide a list of each notification and contact before each closure. Only close driveways for reconstruction if duration and alternate access are approved. Install and maintain material across a work zone as temporary access. This work is subsidiary.
 For CONC, the pavement structure will be 6 in. thick and have 3 in. flexible base bedding unless detailed on the plans.

ITEMS 540, 542, & 544 - METAL BEAM GUARD FENCE AND GUARDRAIL END TREATMENTS

Furnish round timber posts for guard fence. Stake the locations for approval before installation. Adjust the limits of the fence to meet field conditions. Install delineators before opening the road to traffic.

Remove, replace, and install mow strip block out material. Construct new block outs and backfill unused block outs with class B concrete. This work is subsidiary.

Repair of mow strip damage, not caused by contractor negligence, and installation of new mow strip will be paid with appropriate bid items. Backfill and shoulder up of area around fence and mow strip will be paid using embankment item.

ITEMS 600s & 6000s – SIGNING AND MARKINGS

Meet the requirements of the Texas MUTCD, TxDOT standards, and TxDOT Standard Specifications. Notify the Engineer if existing elements to remain do not meet code or specification.

ITEM 658 – DELINEATOR AND OBJECT MARKER ASSEMBLIES

Installation and maintenance of portable CTB reflectors will be subsidiary to the barrier.

Flexible posts YFLX and WFLX must be tubular in shape. The “flat” flexible posts are not allowed.

ITEM 752 – TREE AND BRUSH REMOVAL

Follow Item 752.4 Work Methods and Item 752 general notes when removing or working on or near trees and brush even if Item 752 is not included as a pay item.

General Notes

Sheet I

Project: Roger Hanks Parkway
County: Hays

Sheets: 6-10

Flailing equipment is not allowed. Burning brush is not allowed in urban areas or on ROW. Use hand methods or other means of removal if doing work by mechanical methods is impractical.

Prior to begin tree pruning, send email confirmation to the Engineer that training and demonstration of work methods has been provided to the employees. This work is subsidiary.

Shredded vegetation may be blended, at a rate not to exceed 15 percent by volume, with Item 160 if the maximum dimension is not greater than 2 in.

ITEM 6001 – PORTABLE CHANGEABLE MESSAGE SIGN

Provide 2 PCMS. Provide a replacement within 12 hours. PCMS will be available for traffic control, event notices, roadway conditions, service announcements, etc.

Place PCMS 10 calendar days prior to begin work stating “Road Work Begin Soon, Contact 832-7000 For Info”.

Place PCMS at time of LCN request. Place the PCMS at the expected end of queue caused by the closure. When the closure is active, revise the message to reflect the actual condition during the closure, such as “RIGHT LN CLOSED XXX FT”.

ITEM 6185 – TRUCK MOUNTED ATTENUATOR AND TRAILER ATTENUATOR


The TMA/TA used for installation/removal of traffic control for a work area will be subsidiary to the TMA/TA used to perform the work.



The contractor will be responsible for determining if one or more operations will be ongoing at the same time to determine the total number of TMA/TA required for the work. TMA/TAs paid by the day is full compensation for all worksite locations during an entire day.

TMA/TAs used to protect damaged attenuators will be paid by the day using the force account item for the repair.

General Notes

Sheet J



NO.	DATE	REVISION	APPROVED
 <div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> HDR Firm Registration No. F-754 710 Hesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900 </div>			
 <div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> THE CITY OF DRIPPING SPRINGS TEXAS © 2023 </div>			
ROGER HANKS GENERAL NOTES			
SHEET 5 OF 5			
DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS			RH
AT	STATE	DISTRICT	COUNTY
CHECK	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB
			10

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RHGN05.dgn (General notes 05)

PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:11:39 AM
 SCALE: 1:1

SUMMARY OF TRAFFIC CONTROL QUANTITIES

LOCATION	0500 6001	0502 6001	6001 6002	6185 6002
	MOBILIZATION	BARRICADES, SIGNS AND TRAFFIC HANDLING	PORTABLE CHANGEABLE MESSAGE SIGN	TMA (STATIONARY)*
	LS	MO	EA	DAY
DETOUR PLAN	1	4	2	5
PROJECT TOTALS	1	4	2	5

* TMA WILL ONLY BE PAID FOR ON AN AS-NEEDED BASIS. THE USE OF TMA SHALL BE APPROVED BY THE ENGINEER.

SUMMARY OF REMOVAL QUANTITIES

LOCATION	0100 6002	0105 6015	0496 6004
	PREPARING ROW	REMOVING STAB BASE & ASPH PAV (8"-10")	REMOV STR (SET)
	STA	SY	EA
REMOVAL LAYOUT	4	815	1
PROJECT TOTALS	4	815	1

SUMMARY OF SHANE LANE
EARTHWORK QUANTITIES

STATION	0110 6001	0132 6003
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY B)
	(CY)	(CY)
101+61	0	0
101+75	0	2
102+00	7	8
102+25	8	5
102+50	2	0
102+75	2	0
103+00	1	0
103+10	15	0
103+25	43	1
103+50	72	12
103+75	75	10
104+00	74	0
104+25	75	1
104+50	90	2
104+54	17	0
104+75	77	5

SUMMARY OF SHANE LANE
EARTHWORK QUANTITIES CON'T

STATION	0110 6001	0132 6003
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY B)
	(CY)	(CY)
105+00	82	6
105+25	89	2
105+37	46	0
105+50	52	0
105+56	25	0
105+75	80	0
105+94	85	0
106+00	29	0
106+25	115	0
106+50	101	0
106+75	86	0
106+80	15	0
TOTAL	1,363	54

SUMMARY OF SIDEWALK
EARTHWORK QUANTITIES

STATION	0110 6001	0132 6003
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY B)
	(CY)	(CY)
10+00	0	0
10+25	75	3
10+50	34	3
10+75	1	1
11+00	1	0
11+25	1	0
11+39	1	0
TOTAL	113	7

SUMMARY OF CULVERT 01
DITCH GRADING EARTHWORK QUANTITIES

STATION	0110 6001	0132 6003
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY B)
	(CY)	(CY)
10+81	0	0
11+00	11	0
11+25	7	0
11+50	4	0
11+75	1	0
11+92	0	0
TOTAL	23	0

SUMMARY OF ROADWAY QUANTITIES

LOCATION	0110 6001	0132 6003	0247 6053	0260 6002	0260 6073	0432 6045	0464 6005	0465 6560	0467 6390	0529 6038	0530 6004	0531 6002	0540 6001	0544 6001	3076 6072	5001 6002
	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TY B)	FL BS (CMP IN PLC) (TYD GR1-2) (FNAL POS)	LIME (HYDRATED LIME (SLURRY))	LIME TRT (SUBGRADE) (8")	RIPRAP (MOW STRIP) (4 IN)	RC PIPE (CL III) (24 IN)	INL (CMP) (PAZ D-CZ) (FG) (4F TX4FT-4FTX4F T)	SET (TY II) (24 IN) (RCP) (4:1) (C)	CONC CURB (RIBBON)	DRIVEWAYS (CONC)	CONC SIDEWALKS (5")	MTL W-BEAM GD FEN (TIM POST)	GUARDRAIL END TREATMENT (INSTALL)	D-GR HMA TY-D PG 76-22 (EXEMPT)	GEOGRID BASE REINFORCEME NT (TY II)
	CY	CY	CY	TON	SY	CY	LF	EA	EA	EA	LF	SY	SY	LF	EA	TON
ROADWAY PLAN AND PROFILE																
SHEET 1 OF 2	640	52	106	11	519	10	41	1	-	183	-	79	150	1	46	519
SHEET 2 OF 2	723	2	110	12	546	9	135	1	-	207	-	-	100	1	44	546
DRIVEWAY AND SIDEWALK PLAN AND PROFILE	113	7	-	-	-	-	-	-	-	-	45	72	-	-	-	-
CULVERT 01 LAYOUT	23	-	-	-	-	-	29	-	1	-	-	-	-	-	-	-
PROJECT TOTALS	1,499	61	216	23	1,065	19	205	2	1	390	45	151	250	2	90	1,065

** REFER TO ABOVE TABLE FOR STATION BREAK OUT.

SUMMARY OF SW3P QUANTITIES

LOCATION	0160 6003	0164 6007	0164 6071	0166 6002	0168 6001	0432 6002	0506 6002	0506 6011	0506 6020	0506 6024	0506 6038	0506 6039
	FURNISHING AND PLACING TOPSOIL (4")	BROADCAST SEED (PERM) (URBAN) (CLAY)	BROADCAST SEED (TEMP) (WARM OR COOL)	FERTILIZER	VEGETATIVE WATERING	RIPRAP (CONC) (5 IN)	ROCK FILTER DAMS (INSTALL) (TY 2)	ROCK FILTER DAMS (REMOVE)	CONSTRUCTION EXITS (INSTALL) (TY 1)	CONSTRUCTION EXITS (REMOVE)	TEMP SEDMT CONT FENCE (INSTALL)	TEMP SEDMT CONT FENCE (REMOVE)
	SY	SY	SY	TON	MG	CY	LF	LF	SY	SY	LF	LF
SW3P LAYOUT												
SHEET 1 OF 2	1,760	1,760	1,760	0.1	18	8	70	70	78	78	1,164	1,164
SHEET 2 OF 2	73	73	73	0.1	1	-	-	-	-	-	130	130
PROJECT TOTALS	1,833	1,833	1,833	0.2	19	8	70	70	78	78	1,294	1,294

** FOR CONTRACTOR INFORMATION ONLY, SUBSIDIARY TO PAY ITEM 164.



SUMMARY OF SIGNING AND PAVEMENT MARKING QUANTITIES

LOCATION	0658 6016
	INSTL DEL ASSM (D-SW) SZ (BRF) GF1 (B1)
	EA
SIGNING AND PAVEMENT MARKING PLAN	6
PROJECT TOTALS	6

PENTABLE: 10338078.tbl
SCALE: 1:1

DATE: 10/04/2023 TIME: 8:13:51 AM

PLOT DRIVER: TXDOT_PDF_BW.plt
USER: LGOMEZGONZ
FILE: Roger Hanks Parkway - Summary of Quantities

NO.	DATE	REVISION	APPROVED
 HDR Firm Registration No. F-754 710 Heesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900			 THE CITY OF DRIPPING SPRINGS TEXAS © 2023
ROGER HANKS SUMMARY OF QUANTITIES			
SHEET 1 OF 1			
DESIGN SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS KB	STATE	DISTRICT	RH SHEET NO.
CHECK JC	TEXAS	AUS	HAYS
CHECK JC	CONTROL	SECTION	JOB 11


TRAFFIC CONTROL PLAN GENERAL NOTES:

1. INSTALL ALL SIGNS, BARRICADES, AND TRAFFIC CONTROL DEVICES AS SHOWN AND IN ACCORDANCE WITH THE STANDARD BC SHEETS AND AS DIRECTED. SIGNS MAY BE ADJUSTED DUE TO FIELD CONDITIONS AND SAFETY TO THE TRAVELING PUBLIC.
2. ALL TRAFFIC CONTROL DEVICES SHALL CONFORM WITH THE LATEST EDITION OF THE TEXAS "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" (TMUTCD), AND SHALL BE MAINTAINED AS DIRECTED BY THE ENGINEER. ADDITIONAL GUIDELINES FOR TRAFFIC CONTROL DEVICES MAY BE FOUND IN THE TMUTCD.
3. ADDITIONAL SIGNS, BARRICADES, OR TRAFFIC CONTROL DEVICES OTHER THAN THOSE SPECIFIED MAY BE REQUIRED FOR THE SAFE MOVEMENT OF TRAFFIC THROUGH THE PROJECT. PAYMENT FOR ALL SUCH SIGNS, BARRICADES, OR TRAFFIC CONTROL DEVICES WILL BE CONSIDERED SUBSIDIARY TO THE ITEM 502, "BARRICADES, SIGNS AND TRAFFIC HANDLING".
4. WORK SITES WILL BE CAREFULLY MONITORED TO ENSURE THAT TRAFFIC CONTROL MEASURES ARE OPERATING EFFECTIVELY AND THAT ALL DEVICES USED ARE CLEARLY VISIBLE, CLEAN, AND IN GOOD REPAIR.
5. ACCESS TO ALL PRIVATE PROPERTY SHOULD TO THE GREATEST EXTENT POSSIBLE BE MAINTAINED AT ALL TIMES AND ALL WEATHER CONDITIONS AT THE SOLE EXPENSE OF THE CONTRACTOR. CONTACT THE PROPERTY OWNER AT LEAST 5 DAYS IN ADVANCE OF DRIVEWAY CONSTRUCTION. IF THE PROPERTY OWNER HAS MORE THAN ONE DRIVEWAY, CONSTRUCTION WILL ONLY BE PERMITTED ON ONE DRIVEWAY AT A TIME. DRIVEWAY GRADES DURING CONSTRUCTION SHOULD NOT EXCEED 15%. ADJUST CONSTRUCTION ACTIVITIES ACCORDINGLY TO NOT EXCEED MAXIMUM GRADE LIMITS. PROVIDE ADEQUATE TEMPORARY SURFACING FOR TRANSITIONS BETWEEN PAVEMENT ELEVATIONS FOR ALL DRIVEWAYS.
6. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED SCHEDULE OF WORK TO THE PROJECT ENGINEER PRIOR TO THE BEGINNING OF CONSTRUCTION WHICH GENERALLY CONFORMS TO THE SEQUENCE SHOWN ON THE TCP SEQUENCE OF OPERATION.
7. COMPLETE ALL WORK ON THE PROJECT AS SHOWN ON THE VARIOUS PLAN SHEETS AND IN COMPLIANCE WITH THE GENERAL NOTES OF THIS CONTRACT.
8. ANY REQUEST TO ALTER THE SEQUENCE OF OPERATION OR TRAFFIC CONTROL PLAN WILL BE SUBMITTED TO THE ENGINEER FOR HIS WRITTEN APPROVAL.
9. NO EQUIPMENT OR MATERIALS SHALL BE STORED WITHIN THE CLEAR ZONE UNLESS OTHERWISE APPROVED.

SEQUENCE OF OPERATION

1. SET PROJECT BARRICADES AND DETOUR SIGNAGE.
2. INSTALL REQUIRED TEMPORARY EROSION CONTROL DEVICES, AS DIRECTED.
3. CONSTRUCT NEW DRAINAGE AND ROADWAY.
4. PLACE PERMANENT DELINEATORS.
5. COMPLETE ALL OTHER WORK AS SHOWN ON THE PLANS.
6. CLEAN UP PROJECT AND REMOVE TEMPORARY EROSION CONTROL DEVICES, PROJECT BARRICADES, AND DETOUR SIGNAGE.


PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Sequence of Construction
 PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:13:53 AM
 SCALE: 1:1



NO.	DATE	REVISION	APPROVED

HDR

HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900



**THE CITY OF
DRIPPING SPRINGS
TEXAS**
© 2023



ROGER HANKS

**TRAFFIC CONTROL AND
SEQUENCE OF CONSTRUCTION**

SHEET 1 OF 1

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
SJ				RH
GRAPHICS				
KB	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	AUS	HAYS	12
JC	CONTROL	SECTION	JOB	
JC				

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Detour Plan
 PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:35:55 AM
 SCALE: 1:500



- NOTES:**
1. DETOUR WILL REMAIN IN PLACE THROUGHOUT THE DURATION OF CONSTRUCTION.
 2. SEE BARRICADE AND CONSTRUCTION STANDARDS FOR SIGN SPACING, DETAILS, AND ADDITIONAL SIGNING NOT SHOWN. SIGNS MAY BE ADJUSTED TO FIELD CONDITIONS.
 3. SEE WORK ZONE ROAD CLOSURE DETAILS FOR ADDITIONAL SIGNING NOT SHOWN. SIGNS MAY BE ADJUSTED TO FIELD CONDITIONS.
 4. ACCESS TO EXISTING DRIVEWAYS WILL BE MAINTAINED AT ALL TIMES THROUGHOUT CONSTRUCTION.
 5. CONTRACTOR WILL CORRDINATE TRAFFIC CONTROL, DETOUR SIGNAGE WITH THE ADJACENT ROGER HANKS PARKWAY IMPROVEMENTS PROJECT CONTRACTOR PRIOR TO PLACING DETOUR SIGNAGE.

Felipe S. Tutud

NO.	DATE	REVISION	APPROVED
<p>HDR Firm Registration No. F-754 710 Heisters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900</p>			
<p>THE CITY OF DRIPPING SPRINGS TEXAS © 2023</p>			
<p>ROGER HANKS</p> <p>DETOUR PLAN</p>			
SHEET 1 OF 1			
DESIGN SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS KB	STATE	DISTRICT	COUNTY
CHECK JC	TEXAS	AUS	HAYS
CHECK JC	CONTROL	SECTION	JOB
			13

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:13:56 AM
 FILE: \$FILES\$

BARRICADE AND CONSTRUCTION (BC) STANDARD SHEETS GENERAL NOTES:

1. The Barricade and Construction Standard Sheets (BC sheets) are intended to show typical examples for placement of temporary traffic control devices, construction pavement markings, and typical work zone signs. The information contained in these sheets meet or exceed the requirements shown in the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. The development and design of the Traffic Control Plan (TCP) is the responsibility of the Engineer.
3. The Contractor may propose changes to the TCP that are signed and sealed by a licensed professional engineer for approval. The Engineer may develop, sign and seal Contractor proposed changes.
4. The Contractor is responsible for installing and maintaining the traffic control devices as shown in the plans. The Contractor may not move or change the approximate location of any device without the approval of the Engineer.
5. Geometric design of lane shifts and detours should, when possible, meet the applicable design criteria contained in manuals such as the American Association of State Highway and Transportation Officials (AASHTO), "A Policy on Geometric Design of Highways and Streets," the TxDOT "Roadway Design Manual" or engineering judgment.
6. When projects abut, the Engineer(s) may omit the END ROAD WORK, TRAFFIC FINES DOUBLE, and other advance warning signs if the signing would be redundant and the work areas appear continuous to the motorists. If the adjacent project is completed first, the Contractor shall erect the necessary warning signs as shown on these sheets, the TCP sheets or as directed by the Engineer. The BEGIN ROAD WORK NEXT X MILES sign shall be revised to show appropriate work zone distance.
7. The Engineer may require duplicate warning signs on the median side of divided highways where median width will permit and traffic volumes justify the signing.
8. All signs shall be constructed in accordance with the details found in the "Standard Highway Sign Designs for Texas," latest edition. Sign details not shown in this manual shall be shown in the plans or the Engineer shall provide a detail to the Contractor before the sign is manufactured.
9. The temporary traffic control devices shown in the illustrations of the BC sheets are examples. As necessary, the Engineer will determine the most appropriate traffic control devices to be used.
10. Where highway construction or maintenance work is being undertaken, other than mobile operations as defined by the Texas Manual on Uniform Traffic Control Devices, CSJ limit signs are required. CSJ limit signs are shown on BC(2). The OBEY WARNING SIGNS STATE LAW sign, STAY ALERT TALK OR TEXT LATER and the WORK ZONE TRAFFIC FINES DOUBLE sign with plaque shall be erected in advance of the CSJ limits. The BEGIN ROAD WORK NEXT X MILES, CONTRACTOR and END ROAD WORK signs shall be erected at or near the CSJ limits. For mobile operations, CSJ limit signs are not required.
11. Traffic control devices should be in place only while work is actually in progress or a definite need exists.
12. The Engineer has the final decision on the location of all traffic control devices.
13. Inactive equipment and work vehicles, including workers' private vehicles must be parked away from travel lanes. They should be as close to the right-of-way line as possible, or located behind a barrier or guardrail, or as approved by the Engineer.

WORKER SAFETY NOTES:


1. Workers on foot who are exposed to traffic or to construction equipment within the right-of-way shall wear high-visibility safety apparel meeting the requirements of ISEA "American National Standard for High-Visibility Apparel," or equivalent revisions, and labeled as ANSI 107-2004 standard performance for Class 2 or 3 risk exposure. Class 3 garments should be considered for high traffic volume work areas or night time work.
2. Except in emergency situations, flagger stations shall be illuminated when flagging is used at night.

COMPLIANT WORKZONE TRAFFIC CONTROL DEVICES

1. Only pre-qualified products shall be used. The "Compliant Work Zone Traffic Control Devices List" (CWZTCD) describes pre-qualified products and their sources.
2. Work zone traffic control devices shall be compliant with the Manual for Assessing safety Hardware (MASH).


<p>THE DOCUMENTS BELOW CAN BE FOUND ON-LINE AT http://www.txdot.gov</p>
COMPLIANT WORK ZONE TRAFFIC CONTROL DEVICES LIST (CWZTCD)
DEPARTMENTAL MATERIAL SPECIFICATIONS (DMS)
MATERIAL PRODUCER LIST (MPL)
ROADWAY DESIGN MANUAL - SEE "MANUALS (ONLINE MANUALS) "
STANDARD HIGHWAY SIGN DESIGNS FOR TEXAS (SHSD)
TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)
TRAFFIC ENGINEERING STANDARD SHEETS

SHEET 1 OF 12

		Texas Department of Transportation <i>Traffic Safety Division Standard</i>
<p>BARRICADE AND CONSTRUCTION GENERAL NOTES AND REQUIREMENTS</p> <p>BC (1) -21</p>		
FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT
4-03 7-13	JOB	HIGHWAY
9-07 8-14	DIST	RH
5-10 5-21	AUS	COUNTY SHEET NO.
		14


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

TYPICAL LOCATION OF CROSSROAD SIGNS



- ## May be mounted on back of "ROAD WORK AHEAD" (CW20-1D) sign with approval of Engineer. (See note 2 below)
- The typical minimum signing on a crossroad approach should be a "ROAD WORK AHEAD" (CW20-1D) sign and a (G20-2) "END ROAD WORK" sign, unless noted otherwise in plans.
 - The Engineer may use the reduced size 36" x 36" ROAD WORK AHEAD (CW20-1D) sign mounted back to back with the reduced size 36" x 18" "END ROAD WORK" (G20-2) sign on low volume crossroads (see Note 4 under "Typical Construction Warning Sign Size and Spacing"). See the "Standard Highway Sign Designs for Texas" manual for sign details. The Engineer may omit the advance warning signs on low volume crossroads. The Engineer will determine whether a road is low volume as per TMUTCD Part 5. This information shall be shown in the plans.
 - Based on existing field conditions, the Engineer/Inspector may require additional signs such as FLAGGER AHEAD, LOOSE GRAVEL, or other appropriate signs. When additional signs are required, these signs will be considered part of the minimum requirements. The Engineer/Inspector will determine the proper location and spacing of any sign not shown on the BC sheets, Traffic Control Plan sheets or the Work Zone Standard Sheets.
 - The "ROAD WORK NEXT X MILES" (G20-1aT) sign shall be required at high volume crossroads to advise motorists of the length of construction in either direction from the intersection. The Engineer will determine whether a roadway is considered high volume.
 - Additional traffic control devices may be shown elsewhere in the plans for higher volume crossroads.
 - When work occurs in the intersection area, appropriate traffic control devices, as shown elsewhere in the plans or as determined by the Engineer/Inspector, shall be in place.

T-INTERSECTION



CSJ LIMITS AT T-INTERSECTION

- The Engineer will determine the types and location of any additional traffic control devices, such as a flagger and accompanying signs, or other signs, that should be used when work is being performed at or near an intersection.
- If construction closes the road at a T-intersection, the Contractor shall place the "CONTRACTOR NAME" (G20-6T) sign behind the Type 3 Barricades for the road closure (see BC(10) also). The "ROAD WORK NEXT X MILES" left arrow (G20-1bTL) and "ROAD WORK NEXT X MILES" right arrow (G20-1bTR) signs shall be replaced by the detour signing called for in the plans.

TYPICAL CONSTRUCTION WARNING SIGN SIZE AND SPACING^{1,5,6}

Sign Number or Series	SIZE		SPACING	
	Conventional Road	Expressway/Freeway	Posted Speed MPH	Sign Spacing "X" Feet (Apprx.)
CW20 ⁴	48" x 48"	48" x 48"	30	120
CW21			35	160
CW22			40	240
CW23			45	320
CW1, CW2, CW7, CW8, CW9, CW11, CW14	36" x 36"	48" x 48"	50	400
CW3, CW4, CW5, CW6, CW8-3, CW10, CW12	48" x 48"	48" x 48"	60	600 ²
			65	700 ²
			70	800 ²
			80	1000 ²
*			*	* ³


* For typical sign spacings on divided highways, expressways and freeways, see Part 6 of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) typical application diagrams or TCP Standard Sheets.

△ Minimum distance from work area to first Advance Warning sign nearest the work area and/or distance between each additional sign.

GENERAL NOTES


- Special or larger size signs may be used as necessary.
- Distance between signs should be increased as required to have 1500 feet advance warning.
- Distance between signs should be increased as required to have 1/2 mile or more advance warning.
- 36" x 36" "ROAD WORK AHEAD" (CW20-1D) signs may be used on low volume crossroads at the discretion of the Engineer as per TMUTCD Part 5. See Note 2 under "Typical Location of Crossroad Signs".
- Only diamond shaped warning sign sizes are indicated.
- See sign size listing in "TMUTCD", Sign Appendix or the "Standard Highway Sign Designs for Texas" manual for complete list of available sign design sizes.

WORK AREAS IN MULTIPLE LOCATIONS WITHIN CSJ LIMITS



When extended distances occur between minimal work spaces, the Engineer/Inspector should ensure additional "ROAD WORK AHEAD" (CW20-1D) signs are placed in advance of these work areas to remind drivers they are still within the project limits. See the applicable TCP sheets for exact location and spacing of signs and channelizing devices.

SAMPLE LAYOUT OF SIGNING FOR WORK BEGINNING DOWNSTREAM OF THE CSJ LIMITS



NOTES

- The Contractor shall determine the appropriate distance to be placed on the G20-1 series signs and "BEGIN ROAD WORK NEXT X MILES" (G20-5T) sign for each specific project. This distance shall replace the "X" and shall be rounded to the nearest whole mile with the approval of the Engineer. No decimals shall be used.
- The "BEGIN WORK ZONE" (G20-9TP) and "END WORK ZONE" (G20-2bT) shall be used as shown on the sample layout when advance signs are required outside the CSJ Limits. They inform the motorist of entering or leaving a part of the work zone lying outside the CSJ Limits where traffic fines may double if workers are present.
 - ** CSJ limit signing is required for highway construction and maintenance work, with the exception of mobile operations.
 - ◇ Area for placement of "ROAD WORK AHEAD" (CW20-1D) sign and other signs or devices as called for on the Traffic Control Plan.
 - ◇◇ Contractor will install a regulatory speed limit sign at the end of the work zone.

LEGEND	
—	Type 3 Barricade
○ ○ ○	Channelizing Devices
■	Sign
X	See Typical Construction Warning Sign Size and Spacing chart or the TMUTCD for sign spacing requirements.

SHEET 2 OF 12



BARRICADE AND CONSTRUCTION PROJECT LIMIT

BC(2)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS				RH
9-07 8-14	DIST	COUNTY		SHEET NO.
7-13 5-21	AUS	HAYS		15

DATE: 10/4/2023 8:13:57 AM
 FILE: \$FILES\$

TYPICAL APPLICATION OF WORK ZONE SPEED LIMIT SIGNS

Work zone speed limits shall be regulatory, established in accordance with the "Procedures for Establishing Speed Zones," and approved by the Texas Transportation Commission, or by City Ordinance when within Incorporated City Limits.

Reduced speeds should only be posted in the vicinity of work activity and not throughout the entire project. Regulatory work zone speed signs (R2-1) shall be removed or covered during periods when they are not needed.



GUIDANCE FOR USE:

LONG/INTERMEDIATE TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit should be included on the design of the traffic control plans when restricted geometrics with a lower design speed are present in the work zone and modification of the geometrics to a higher design speed is not feasible.

Long/Intermediate Term Work Zone Speed Limit signs, when approved as described above, should be posted and visible to the motorist when work activity is present. Work activity may also be defined as a change in the roadway that requires a reduced speed for motorists to safely negotiate the work area, including:

- rough road or damaged pavement surface
- substantial alteration of roadway geometrics (diversions)
- construction detours
- grade
- width
- other conditions readily apparent to the driver

As long as any of these conditions exist, the work zone speed limit signs should remain in place.

SHORT TERM WORK ZONE SPEED LIMITS

This type of work zone speed limit may be included on the design of the traffic control plans when workers or equipment are not behind concrete barrier, when work activity is within 10 feet of the traveled way or actually in the traveled way.

Short Term Work Zone Speed Limit signs should be posted and visible to the motorists only when work activity is present. When work activity is not present, signs shall be removed or covered. (See Removing or Covering on BC(4)).

GENERAL NOTES

- Regulatory work zone speed limits should be used only for sections of construction projects where speed control is of major importance.
- Regulatory work zone speed limit signs shall be placed on supports at a 7 foot minimum mounting height.
- Speed zone signs are illustrated for one direction of travel and are normally posted for each direction of travel.
- Frequency of work zone speed limit signs should be:

40 mph and greater	0.2 to 2 miles
35 mph and less	0.2 to 1 mile
- Regulatory speed limit signs shall have black legend and border on a white reflective background (See "Reflective Sheeting" on BC(4)).
- Fabrication, erection and maintenance of the "ADVANCE SPEED LIMIT" (CW3-5) sign, "WORK ZONE" (G20-5aP) plaque and the "SPEED LIMIT" (R2-1) signs shall not be paid for directly, but shall be considered subsidiary to Item 502.
- Turning signs from view, laying signs over or down will not be allowed, unless as otherwise noted under "REMOVING OR COVERING" on BC(4).
- Techniques that may help reduce traffic speeds include but are not limited to:
 - Law enforcement.
 - Flagger stationed next to sign.
 - Portable changeable message sign (PCMS).
 - Low-power (drone) radar transmitter.
 - Speed monitor trailers or signs.
- Speeds shown on details above are for illustration only. Work Zone Speed Limits should only be posted as approved for each project.
- For more specific guidance concerning the type of work, work zone conditions and factors impacting allowable regulatory construction speed zone reduction see TxDOT form #1204 in the TxDOT e-form system.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:13:59 AM
FILE: \$FILES

SHEET 3 OF 12




BARRICADE AND CONSTRUCTION WORK ZONE SPEED LIMIT

BC (3) -21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY		RH		
REVISIONS		DIST		COUNTY		SHEET NO.			
9-07	8-14	AUS	HAYS			16			
7-13	5-21								

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPICAL MINIMUM CLEARANCES FOR LONG TERM AND INTERMEDIATE TERM SIGNS




* When placing skid supports on unlevel ground, the leg post lengths must be adjusted so the sign appears straight and plumb. Objects shall NOT be placed under skids as a means of leveling.

** When plaques are placed on dual-leg supports, they should be attached to the upright nearest the travel lane. Supplemental plaques (advisory or distance) should not cover the surface of the parent sign.

ATTACHMENT FOR SIGN SUPPORTS



Attachment to wooden supports will be by bolts and nuts or screws. Use TxDOT's or manufacturer's recommended procedures for attaching sign substrates to other types of sign supports



Nails shall NOT be allowed.
Each sign shall be attached directly to the sign support. Multiple signs shall not be joined or spliced by any means. Wood supports shall not be extended or repaired by splicing or other means.

Splicing embedded perforated square metal tubing in order to extend post height will only be allowed when the splice is made using four bolts, two above and two below the splice point. Splice must be located entirely behind the sign substrate, not near the base of the support. Splice insert lengths should be at least 5 times nominal post size, centered on the splice and of at least the same gauge material.

GENERAL NOTES FOR WORK ZONE SIGNS

- Contractor shall install and maintain signs in a straight and plumb condition and/or as directed by the Engineer.
- Wooden sign posts shall be painted white.
- Barricades shall NOT be used as sign supports.
- All signs shall be installed in accordance with the plans or as directed by the Engineer. Signs shall be used to regulate, warn, and guide the traveling public safely through the work zone.
- The Contractor may furnish either the sign design shown in the plans or in the "Standard Highway Sign Designs for Texas" (SHSD). The Engineer/Inspector may require the Contractor to furnish other work zone signs that are shown in the TMUTCD but may have been omitted from the plans. Any variation in the plans shall be documented by written agreement between the Engineer and the Contractor's Responsible Person. All changes must be documented in writing before being implemented. This can include documenting the changes in the Inspector's TxDOT diary and having both the Inspector and Contractor initial and date the agreed upon changes.
- The Contractor shall furnish sign supports listed in the "Compliant Work Zone Traffic Control Device List" (CWZTCD) for small roadside signs. Supports for temporary large roadside signs shall meet the requirements detailed on the Temporary Large Roadside Signs (TLRS) standard sheets. The Contractor shall install the sign support in accordance with the manufacturer's recommendations. If there is a question regarding installation procedures, the Contractor shall furnish the Engineer a copy of the manufacturer's installation recommendations so the Engineer can verify the correct procedures are being followed.
- The Contractor is responsible for installing signs on approved supports and replacing signs with damaged or cracked substrates and/or damaged or marred reflective sheeting as directed by the Engineer/Inspector.
- Identification markings may be shown only on the back of the sign substrate. The maximum height of letters and/or company logos used for identification shall be 1 inch.
- The Contractor shall replace damaged wood posts. New or damaged wood sign posts shall not be spliced.

DURATION OF WORK (as defined by the "Texas Manual on Uniform Traffic Control Devices" Part 6)

- The types of sign supports, sign mounting height, the size of signs, and the type of sign substrates can vary based on the type of work being performed. The Engineer is responsible for selecting the appropriate size sign for the type of work being performed. The Contractor is responsible for ensuring the sign support, sign mounting height and substrate meets manufacturer's recommendations in regard to crashworthiness and duration of work requirements.
 - Long-term stationary - work that occupies a location more than 3 days.
 - Intermediate-term stationary - work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than one hour.
 - Short-term stationary - daytime work that occupies a location for more than 1 hour in a single daylight period.
 - Short, duration - work that occupies a location up to 1 hour.
 - Mobile - work that moves continuously or intermittently (stopping for up to approximately 15 minutes.)

SIGN MOUNTING HEIGHT

- The bottom of Long-term/Intermediate-term signs shall be at least 7 feet, but not more than 9 feet, above the paved surface, except as shown for supplemental plaques mounted below other signs.
- The bottom of Short-term/Short Duration signs shall be a minimum of 1 foot above the pavement surface but no more than 2 feet above the ground.
- Long-term/Intermediate-term Signs may be used in lieu of Short-term/Short Duration signing.
- Short-term/Short Duration signs shall be used only during daylight and shall be removed at the end of the workday or raised to appropriate Long-term/Intermediate sign height.
- Regulatory signs shall be mounted at least 7 feet, but not more than 9 feet, above the paved surface regardless of work duration.

SIZE OF SIGNS

- The Contractor shall furnish the sign sizes shown on BC (2) unless otherwise shown in the plans or as directed by the Engineer.

SIGN SUBSTRATES

- The Contractor shall ensure the sign substrate is installed in accordance with the manufacturer's recommendations for the type of sign support that is being used. The CWZTCD lists each substrate that can be used on the different types and models of sign supports.
- "Mesh" type materials are NOT an approved sign substrate, regardless of the tightness of the weave.
- All wooden individual sign panels fabricated from 2 or more pieces shall have one or more plywood cleat, 1/2" thick by 6" wide, fastened to the back of the sign and extending fully across the sign. The cleat shall be attached to the back of the sign using wood screws that do not penetrate the face of the sign panel. The screws shall be placed on both sides of the splice and spaced at 6" centers. The Engineer may approve other methods of splicing the sign face.

REFLECTIVE SHEETING

- All signs shall be retroreflective and constructed of sheeting meeting the color and retro-reflectivity requirements of DMS-8300 for rigid signs or DMS-8310 for roll-up signs. The web address for DMS specifications is shown on BC(1).
- White sheeting, meeting the requirements of DMS-8300 Type A, shall be used for signs with a white background.
- Orange sheeting, meeting the requirements of DMS-8300 Type B_{FL} or Type C_{FL}, shall be used for rigid signs with orange backgrounds.

SIGN LETTERS

- All sign letters and numbers shall be clear, and open rounded type uppercase alphabet letters as approved by the Federal Highway Administration (FHWA) and as published in the "Standard Highway Sign Design for Texas" manual. Signs, letters and numbers shall be of first class workmanship in accordance with Department Standards and Specifications.

REMOVING OR COVERING

- When sign messages may be confusing or do not apply, the signs shall be removed or completely covered.
- Long-term stationary or intermediate stationary signs installed on square metal tubing may be turned away from traffic 90 degrees when the sign message is not applicable. This technique may not be used for signs installed in the median of divided highways or near any intersections where the sign may be seen from approaching traffic.
- Signs installed on wooden skids shall not be turned at 90 degree angles to the roadway. These signs should be removed or completely covered when not required.
- When signs are covered, the material used shall be opaque, such as heavy mil black plastic, or other materials which will cover the entire sign face and maintain their opaque properties under automobile headlights at night, without damaging the sign sheeting.
- Burlap shall NOT be used to cover signs.
- Duct tape or other adhesive material shall NOT be affixed to a sign face.
- Signs and anchor stubs shall be removed and holes backfilled upon completion of work.

SIGN SUPPORT WEIGHTS


- Where sign supports require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand should be used.
- The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight.
- Rock, concrete, iron, steel or other solid objects shall not be permitted for use as sign support weights.
- Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs.
- Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall NOT be used.
- Rubber ballasts designed for channelizing devices should not be used for ballast on portable sign supports. Sign supports designed and manufactured with rubber bases may be used when shown on the CWZTCD list.
- Sandbags shall only be placed along or laid over the base supports of the traffic control device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners. Sandbags shall be placed along the length of the skids to weigh down the sign support.
- Sandbags shall NOT be placed under the skid and shall not be used to level sign supports placed on slopes.

FLAGS ON SIGNS

- Flags may be used to draw attention to warning signs. When used, the flag shall be 16 inches square or larger and shall be orange or fluorescent red-orange in color. Flags shall not be allowed to cover any portion of the sign face.

STOP/SLOW PADDLES

- STOP/SLOW paddles are the primary method to control traffic by flaggers. The STOP/SLOW paddle size should be 24" x 24".
- STOP/SLOW paddles shall be retroreflectorized when used at night.
- STOP/SLOW paddles may be attached to a staff with a minimum length of 6' to the bottom of the sign.
- Any lights incorporated into the STOP or SLOW paddle faces shall only be as specifically described in Section 6E.03 Hand Signaling Devices in the TMUTCD.



SHEETING REQUIREMENTS (WHEN USED AT NIGHT)		
USAGE	COLOR	SIGN FACE MATERIAL
BACKGROUND	RED	TYPE B OR C SHEETING
BACKGROUND	ORANGE	TYPE B _{FL} OR C _{FL} SHEETING
LEGEND & BORDER	WHITE	TYPE B OR C SHEETING
LEGEND & BORDER	BLACK	ACRYLIC NON-REFLECTIVE FILM

CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS

- Permanent signs are used to give notice of traffic laws or regulations, call attention to conditions that are potentially hazardous to traffic operations, show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, specific service (LOGO), or cultural information. Drivers proceeding through a work zone need the same, if not better route guidance as normally installed on a roadway without construction.
- When permanent regulatory or warning signs conflict with work zone conditions, remove or cover the permanent signs until the permanent sign message matches the roadway condition. For details for covering large guide signs see the TS-CD standard.
- When existing permanent signs are moved and relocated due to construction purposes, they shall be visible to motorists at all times.
- If existing signs are to be relocated on their original supports, they shall be installed on crashworthy bases as shown on the SMD Standard sheets. The signs shall meet the required mounting heights shown on the BC Sheets or the SMD Standards. This work should be paid for under the appropriate pay item for relocating existing signs.
- If permanent signs are to be removed and relocated using temporary supports, the Contractor shall use crashworthy supports as shown on the BC standard sheets, TLRS standard sheets or the CWZTCD list. The signs shall meet the required mounting heights shown on the BC, or the SMD standard sheets during construction. This work should be paid for under the appropriate pay item for relocating existing signs.
- Any sign or traffic control device that is struck or damaged by the Contractor or his/her construction equipment shall be replaced as soon as possible by the Contractor to ensure proper guidance for the motorists. This will be subsidiary to Item 502.





BARRICADE AND CONSTRUCTION TEMPORARY SIGN NOTES

BC(4)-21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	OW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY				
REVISIONS				RH					
9-07	8-14	DIST	COUNTY		SHEET NO.				
7-13	5-21	AUS	HAYS		17				


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:14:01 AM
FILE: \$FILES\$





SKID MOUNTED WOOD SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS



GROUND MOUNTED SIGN SUPPORTS

Refer to the CWZTCD and the manufacturer's installation procedure for each type sign support. The maximum sign square footage shall adhere to the manufacturer's recommendation. Two post installations can be used for larger signs.



SKID MOUNTED PERFORATED SQUARE STEEL TUBING SIGN SUPPORTS

* LONG/INTERMEDIATE TERM STATIONARY - PORTABLE SKID MOUNTED SIGN SUPPORTS

WEDGE ANCHORS
Both steel and plastic Wedge Anchor Systems as shown on the SMD Standard Sheets may be used as temporary sign supports for signs up to 10 square feet of sign face. They may be set in concrete or in sturdy soils if approved by the Engineer. (See web address for "Traffic Engineering Standard Sheets" on BC(1)).

OTHER DESIGNS
MORE DETAILS OF APPROVED LONG/INTERMEDIATE AND SHORT TERM SUPPORTS CAN BE FOUND ON THE CWZTCD LIST. SEE BC(1) FOR WEBSITE LOCATION.

- GENERAL NOTES**
- Nails may be used in the assembly of wooden sign supports, but 3/8" bolts with nuts or 3/8" x 3 1/2" lag screws must be used on every joint for final connection.
 - No more than 2 sign posts shall be placed within a 7 ft. circle, except for specific materials noted on the CWZTCD List.
 - When project is completed, all sign supports and foundations shall be removed from the project site. This will be considered subsidiary to Item 502.
- * See BC(4) for definition of "Work Duration."
 - ** Wood sign posts MUST be one piece. Splicing will NOT be allowed. Posts shall be painted white.
 - See the CWZTCD for the type of sign substrate that can be used for each approved sign support.


BARRICADE AND CONSTRUCTION TYPICAL SIGN SUPPORT

BC(5)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS				
9-07 8-14				RH
7-13 5-21				
	DIST	COUNTY	SHEET NO.	
	AUS	HAYS	18	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

- Barrier Reflectors shall be pre-qualified, and conform to the color and reflectivity requirements of DMS-8600. A list of prequalified Barrier Reflectors can be found at the Material Producer List web address shown on BC(1).
- Color of Barrier Reflectors shall be as specified in the TMUTCD. The cost of the reflectors shall be considered subsidiary to Item 512.




CONCRETE TRAFFIC BARRIER (CTB)

- Where traffic is on one side of the CTB, two (2) Barrier Reflectors shall be mounted in approximately the midsection of each section of CTB. An alternate mounting location is uniformly spaced at one end of each CTB. This will allow for attachment of a barrier grapple without damaging the reflector. The Barrier Reflector mounted on the side of the CTB shall be located directly below the reflector mounted on top of the barrier, as shown in the detail above.
- Where CTB separates two-way traffic, three barrier reflectors shall be mounted on each section of CTB. The reflector unit on top shall have two yellow reflective faces (Bi-Directional) while the reflectors on each side of the barrier shall have one yellow reflective face, as shown in the detail above.
- When CTB separates traffic traveling in the same direction, no barrier reflectors will be required on top of the CTB.
- Barrier Reflector units shall be yellow or white in color to match the edgeline being supplemented.
- Maximum spacing of Barrier Reflectors is forty (40) feet.
- Pavement markers or temporary flexible-reflective roadway marker tabs shall NOT be used as CTB delineation.
- Attachment of Barrier Reflectors to CTB shall be per manufacturer's recommendations.
- Missing or damaged Barrier Reflectors shall be replaced as directed by the Engineer.
- Single slope barriers shall be delineated as shown on the above detail.



LOW PROFILE CONCRETE BARRIER (LPCB) USED IN WORK ZONES
 LPCB is approved for use in work zone locations, where the posted speed is 45mph, or less. See Roadway Standard Sheet LPCB.

LOW PROFILE CONCRETE BARRIER (LPCB)



DELINEATION OF END TREATMENTS

END TREATMENTS FOR CTB'S USED IN WORK ZONES
 End treatments used on CTB's in work zones shall meet the appropriate crashworthy standards as defined in the Manual for Assessing Safety Hardware (MASH). Refer to the CWZTCD List for approved end treatments and manufacturers.

BARRIER REFLECTORS FOR CONCRETE TRAFFIC BARRIER AND ATTENUATORS

WARNING LIGHTS


- Warning lights shall meet the requirements of the TMUTCD.
- Warning lights shall NOT be installed on barricades.
- Type A-Low Intensity Flashing Warning Lights are commonly used with drums. They are intended to warn of or mark a potentially hazardous area. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "FL". The Type A Warning Lights shall not be used with signs manufactured with Type B_{FL} or C_{FL} Sheeting meeting the requirements of Departmental Material Specification DMS-8300.
- Type-C and Type D 360 degree Steady Burn Lights are intended to be used in a series for delineation to supplement other traffic control devices. Their use shall be as indicated on this sheet and/or other sheets of the plans by the designation "SB".
- The Engineer/Inspector or the plans shall specify the location and type of warning lights to be installed on the traffic control devices.
- When required by the Engineer, the Contractor shall furnish a copy of the warning lights certification. The warning light manufacturer will certify the warning lights meet the requirements of the latest ITE Purchase Specifications for Flashing and Steady-Burn Warning Lights.
- When used to delineate curves, Type-C and Type D Steady Burn Lights should only be placed on the outside of the curve, not the inside.
- The location of warning lights and warning reflectors on drums shall be as shown elsewhere in the plans.

WARNING LIGHTS MOUNTED ON PLASTIC DRUMS


- Type A flashing warning lights are intended to warn drivers that they are approaching or are in a potentially hazardous area.
- Type A random flashing warning lights are not intended for delineation and shall not be used in a series.
- A series of sequential flashing warning lights placed on channelizing devices to form a merging taper may be used for delineation. If used, the successive flashing of the sequential warning lights should occur from the beginning of the taper to the end of the merging taper in order to identify the desired vehicle path. The rate of flashing for each light shall be 65 flashes per minute, plus or minus 10 flashes.
- Type C and D steady-burn warning lights are intended to be used in a series to delineate the edge of the travel lane on detours, on lane changes, on lane closures, and on other similar conditions.
- Type A, Type C and Type D warning lights shall be installed at locations as detailed on other sheets in the plans.
- Warning lights shall not be installed on a drum that has a sign, chevron or vertical panel.
- The maximum spacing for warning lights on drums should be identical to the channelizing device spacing.

WARNING REFLECTORS MOUNTED ON PLASTIC DRUMS AS A SUBSTITUTE FOR TYPE C (STEADY BURN) WARNING LIGHTS

- A warning reflector or approved substitute may be mounted on a plastic drum as a substitute for a Type C, steady burn warning light at the discretion of the Contractor unless otherwise noted in the plans.
- The warning reflector shall be yellow in color and shall be manufactured using a sign substrate approved for use with plastic drums listed on the CWZTCD.
- The warning reflector shall have a minimum retroreflective surface area (one-side) of 30 square inches.
- Round reflectors shall be fully reflectorized, including the area where attached to the drum.
- Square substrates must have a minimum of 30 square inches of reflectorized sheeting. They do not have to be reflectorized where it attaches to the drum.
- The side of the warning reflector facing approaching traffic shall have sheeting meeting the color and retroreflectivity requirements for DMS 8300-Type B or Type C.
- When used near two-way traffic, both sides of the warning reflector shall be reflectorized.
- The warning reflector should be mounted on the side of the handle nearest approaching traffic.
- The maximum spacing for warning reflectors should be identical to the channelizing device spacing requirements.




Type C Warning Light or approved substitute mounted on a drum adjacent to the travel way.



Warning reflector may be round or square. Must have a yellow reflective surface area of at least 30 square inches

Arrow Boards may be located behind channelizing devices in place for a shoulder taper or merging taper, otherwise they shall be delineated with four (4) channelizing devices placed perpendicular to traffic on the upstream side of traffic.

- The Flashing Arrow Board should be used for all lane closures on multi-lane roadways, or slow moving maintenance or construction activities on the travel lanes.
- Flashing Arrow Boards should not be used on two-lane, two-way roadways, detours, diversions or work on shoulders unless the "CAUTION" display (see detail below) is used.
- The Engineer/Inspector shall choose all appropriate signs, barricades and/or other traffic control devices that should be used in conjunction with the Flashing Arrow Board.
- The Flashing Arrow Board should be able to display the following symbols:



- The "CAUTION" display consists of four corner lamps flashing simultaneously, or the Alternating Diamond Caution mode as shown.
- The straight line caution display is NOT ALLOWED.
- The Flashing Arrow Board shall be capable of minimum 50 percent dimming from rated lamp voltage. The flashing rate of the lamps shall not be less than 25 nor more than 40 flashes per minute.
- Minimum lamp "on time" shall be approximately 50 percent for the flashing arrow and equal intervals of 25 percent for each sequential phase of the flashing chevron.
- The sequential arrow display is NOT ALLOWED.
- The flashing arrow display is the TxDOT standard; however, the sequential chevron display may be used during daylight operations.
- The Flashing Arrow Board shall be mounted on a vehicle, trailer or other suitable support.
- A Flashing Arrow Board SHALL NOT BE USED to laterally shift traffic.
- A full matrix PCMS may be used to simulate a Flashing Arrow Board provided it meets visibility, flash rate and dimming requirements on this sheet for the same size arrow.
- Minimum mounting height of trailer mounted Arrow Boards should be 7 feet from roadway to bottom of panel.

REQUIREMENTS			
TYPE	MINIMUM SIZE	MINIMUM NUMBER OF PANEL LAMPS	MINIMUM VISIBILITY DISTANCE
B	30 x 60	13	3/4 mile
C	48 x 96	15	1 mile

ATTENTION
 Flashing Arrow Boards shall be equipped with automatic dimming devices.

WHEN NOT IN USE, REMOVE THE ARROW BOARD FROM THE RIGHT-OF-WAY OR PLACE THE ARROW BOARD BEHIND CONCRETE TRAFFIC BARRIER OR GUARDRAIL.

FLASHING ARROW BOARDS

SHEET 7 OF 12

TRUCK-MOUNTED ATTENUATORS

- Truck-mounted attenuators (TMA) used on TxDOT facilities must meet the requirements outlined in the Manual for Assessing Safety Hardware (MASH).
- Refer to the CWZTCD for the requirements of Level 2 or Level 3 TMAs.
- Refer to the CWZTCD for a list of approved TMAs.
- TMAs are required on freeways unless otherwise noted in the plans.
- A TMA should be used anytime that it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the work performance.
- The only reason a TMA should not be required is when a work area is spread down the roadway and the work crew is an extended distance from the TMA.



BARRICADE AND CONSTRUCTION ARROW PANEL, REFLECTORS, WARNING LIGHTS & ATTENUATOR

BC (7) -21

FILE:	bc-21.dgn	DN:	TxDOT	CK:	TxDOT	DW:	TxDOT	CK:	TxDOT
© TxDOT	November 2002	CONT	SECT	JOB	HIGHWAY		RH		
REVISIONS		DIST		COUNTY		SHEET NO.			
9-07	8-14								
7-13	5-21	AUS	HAYS						19

DATE: 10/4/2023 8:14:02 AM
 FILE: \$FILES\$

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:14:03 AM
 FILE: \$FILES\$

GENERAL NOTES

- For long term stationary work zones on freeways, drums shall be used as the primary channelizing device.
- For intermediate term stationary work zones on freeways, drums should be used as the primary channelizing device but may be replaced in tangent sections by vertical panels, or 42" two-piece cones. In tangent sections, one-piece cones may be used with the approval of the Engineer but only if personnel are present on the project at all times to maintain the cones in proper position and location.
- For short term stationary work zones on freeways, drums are the preferred channelizing device but may be replaced in tapers, transitions and tangent sections by vertical panels, two-piece cones or one-piece cones as approved by the Engineer.
- Drums and all related items shall comply with the requirements of the current version of the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD) and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
- Drums, bases, and related materials shall exhibit good workmanship and shall be free from objectionable marks or defects that would adversely affect their appearance or serviceability.
- The Contractor shall have a maximum of 24 hours to replace any plastic drums identified for replacement by the Engineer/Inspector. The replacement device must be an approved device.

GENERAL DESIGN REQUIREMENTS

Pre-qualified plastic drums shall meet the following requirements:




- Plastic drums shall be a two-piece design; the "body" of the drum shall be the top portion and the "base" shall be the bottom.
- The body and base shall lock together in such a manner that the body separates from the base when impacted by a vehicle traveling at a speed of 20 MPH or greater but prevents accidental separation due to normal handling and/or air turbulence created by passing vehicles.
- Plastic drums shall be constructed of lightweight flexible, and deformable materials. The Contractor shall NOT use metal drums or single piece plastic drums as channelization devices or sign supports.
- Drums shall present a profile that is a minimum of 18 inches in width at the 36 inch height when viewed from any direction. The height of drum unit (body installed on base) shall be a minimum of 36 inches and a maximum of 42 inches.
- The top of the drum shall have a built-in handle for easy pickup and shall be designed to drain water and not collect debris. The handle shall have a minimum of two widely spaced 9/16 inch diameter holes to allow attachment of a warning light, warning reflector unit or approved compliant sign.
- The exterior of the drum body shall have a minimum of four alternating orange and white retroreflective circumferential stripes not less than 4 inches nor greater than 8 inches in width. Any non-reflectORIZED space between any two adjacent stripes shall not exceed 2 inches in width.
- Bases shall have a maximum width of 36 inches, a maximum height of 4 inches, and a minimum of two footholds of sufficient size to allow base to be held down while separating the drum body from the base.
- Plastic drums shall be constructed of ultra-violet stabilized, orange, high-density polyethylene (HDPE) or other approved material.
- Drum body shall have a maximum unballasted weight of 11 lbs.
- Drum and base shall be marked with manufacturer's name and model number.

RETROREFLECTIVE SHEETING

- The stripes used on drums shall be constructed of sheeting meeting the color and retroreflectivity requirements of Departmental Materials Specification DMS-8300, "Sign Face Materials." Type A or Type B reflective sheeting shall be supplied unless otherwise specified in the plans.
- The sheeting shall be suitable for use on and shall adhere to the drum surface such that, upon vehicular impact, the sheeting shall remain adhered in-place and exhibit no delaminating, cracking, or loss of retroreflectivity other than that loss due to abrasion of the sheeting surface.


BALLAST

- Unballasted bases shall be large enough to hold up to 50 lbs. of sand. This base, when filled with the ballast material, should weigh between 35 lbs (minimum) and 50 lbs (maximum). The ballast may be sand in one to three sandbags separate from the base, sand in a sand-filled plastic base, or other ballasting devices as approved by the Engineer. Stacking of sandbags will be allowed, however height of sandbags above pavement surface may not exceed 12 inches.
- Bases with built-in ballast shall weigh between 40 lbs. and 50 lbs. Built-in ballast can be constructed of an integral crumb rubber base or a solid rubber base.
- Recycled truck tire sidewalls may be used for ballast on drums approved for this type of ballast on the CWZTCD list.
- The ballast shall not be heavy objects, water, or any material that would become hazardous to motorists, pedestrians, or workers when the drum is struck by a vehicle.
- When used in regions susceptible to freezing, drums shall have drainage holes in the bottoms so that water will not collect and freeze becoming a hazard when struck by a vehicle.
- Ballast shall not be placed on top of drums.
- Adhesives may be used to secure base of drums to pavement.



DETECTABLE PEDESTRIAN BARRICADES

- When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility. Refer to WZ(BTS-2) for Pedestrian Control requirements for Sidewalk Diversions, Sidewalk Detours and Crosswalk Closures.
- Where pedestrians with visual disabilities normally use the closed sidewalk, a Detectable Pedestrian Barricade shall be placed across the full width of the closed sidewalk instead of a Type 3 Barricade.
- Detectable pedestrian barricades similar to the one pictured above, longitudinal channelizing devices, some concrete barriers, and wood or chain link fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.
- Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the "Americans with Disabilities Act Accessibility Guidelines (ADAAG)" and should not be used as a control for pedestrian movements.
- Warning lights shall not be attached to detectable pedestrian barricades.
- Detectable pedestrian barricades should use 8" nominal barricade rails as shown on BC(10) provided that the top rail provides a smooth continuous rail suitable for hand trailing with no splinters, burrs, or sharp edges.



18" x 24" Sign (Maximum Sign Dimension)
 Chevron CW1-8, Opposing Traffic Lane Divider, Driveway sign D70a, Keep Right R4 series or other signs as approved by Engineer
 12" x 24" Vertical Panel
 mount with diagonals sloping down towards travel way

SIGNS, CHEVRONS, AND VERTICAL PANELS MOUNTED ON PLASTIC DRUMS

- Signs used on plastic drums shall be manufactured using substrates listed on the CWZTCD.
- Chevrons and other work zone signs with an orange background shall be manufactured with Type B_{FL} or Type C_{FL} Orange sheeting meeting the color and retroreflectivity requirements of DMS-8300, "Sign Face Material," unless otherwise specified in the plans.
- Vertical Panels shall be manufactured with orange and white sheeting meeting the requirements of DMS-8300 Type A or Type B. Diagonal stripes on Vertical Panels shall slope down toward the intended traveled lane.
- Other sign messages (text or symbolic) may be used as approved by the Engineer. Sign dimensions shall not exceed 18 inches in width or 24 inches in height, except for the R9 series signs discussed in note 8 below.
- Signs shall be installed using a 1/2 inch bolt (nominal) and nut, two washers, and one locking washer for each connection.
- Mounting bolts and nuts shall be fully engaged and adequately torqued. Bolts should not extend more than 1/2 inch beyond nuts.
- Chevrons may be placed on drums on the outside of curves, on merging tapers or on shifting tapers. When used in these locations, they may be placed on every drum or spaced not more than on every third drum. A minimum of three (3) should be used at each location called for in the plans.
- R9-9, R9-10, R9-11 and R9-11a Sidewalk Closed signs which are 24 inches wide may be mounted on plastic drums, with approval of the Engineer.

SHEET 8 OF 12


BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(8)-21

FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS				
4-03 8-14				RH
9-07 5-21	DIST	COUNTY		SHEET NO.
7-13	AUS	HAYS		20


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:14:05 AM
FILE: \$FILES



FIXED
(Rigid or self-righting)


DRIVEABLE



PORTABLE


VERTICAL PANELS (VPs)

1. Vertical Panels (VP's) are normally used to channelize traffic or divide opposing lanes of traffic.
2. VP's may be used in daytime or nighttime situations. They may be used at the edge of shoulder drop-offs and other areas such as lane transitions where positive daytime and nighttime delineation is required. The Engineer/Inspector shall refer to the Roadway Design Manual for additional requirements on the use VP's for drop-offs.
3. VP's should be mounted back to back if used at the edge of cuts adjacent to two-way two lane roadways. Stripes are to be reflective orange and reflective white and should always slope downward toward the travel lane.
4. VP's used on expressways and freeways or other high speed roadways, may have more than 270 square inches of retroreflective area facing traffic.
5. Self-righting supports are available with portable base. See "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
6. Sheeting for the VP's shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300, unless noted otherwise.
7. Where the height of reflective material on the vertical panel is 36 inches or greater, a panel stripe of 6 inches shall be used.




OPPOSING TRAFFIC LANE DIVIDERS (OTLD)

1. Opposing Traffic Lane Dividers (OTLD) are delineation devices designed to convert a normal one-way roadway section to two-way operation. OTLD's are used on temporary centerlines. The upward and downward arrows on the sign's face indicate the direction of traffic on either side of the divider. The base is secured to the pavement with an adhesive or rubber weight to minimize movement caused by a vehicle impact or wind gust.
2. The OTLD may be used in combination with 42" cones or VPs.
3. Spacing between the OTLD shall not exceed 500 feet. 42" cones or VPs placed between the OTLD's should not exceed 100 foot spacing.
4. The OTLD shall be orange with a black non-reflective legend. Sheeting for the OTLD shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.



1. The chevron shall be a vertical rectangle with a minimum size of 12 by 18 inches.
2. Chevrons are intended to give notice of a sharp change of alignment with the direction of travel and provide additional emphasis and guidance for vehicle operators with regard to changes in horizontal alignment of the roadway.
3. Chevrons, when used, shall be erected on the outside of a sharp curve or turn, or on the far side of an intersection. They shall be in line with and at right angles to approaching traffic. Spacing should be such that the motorist always has three in view, until the change in alignment eliminates its need.
4. To be effective, the chevron should be visible for at least 500 feet.
5. Chevrons shall be orange with a black nonreflective legend. Sheeting for the chevron shall be retroreflective Type B_{FL} or Type C_{FL} conforming to Departmental Material Specification DMS-8300, unless noted otherwise. The legend shall meet the requirements of DMS-8300.
6. For Long Term Stationary use on tapers or transitions on freeways and divided highways, self-righting chevrons may be used to supplement plastic drums but not to replace plastic drums.

CHEVRONS



LONGITUDINAL CHANNELIZING DEVICES (LCD)

1. LCDs are crashworthy, lightweight, deformable devices that are highly visible, have good target value and can be connected together. They are not designed to contain or redirect a vehicle on impact.
2. LCDs may be used instead of a line of cones or drums.
3. LCDs shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. LCDs should not be used to provide positive protection for obstacles, pedestrians or workers.
5. LCDs shall be supplemented with retroreflective delineation as required for temporary barriers on BC(7) when placed roughly parallel to the travel lanes.
6. LCDs used as barricades placed perpendicular to traffic should have at least one row of reflective sheeting meeting the requirements for barricade rails as shown on BC(10). Place reflective sheeting near the top of the LCD along the full length of the device.

WATER BALLASTED SYSTEMS USED AS BARRIERS

1. Water ballasted systems used as barriers shall not be used solely to channelize road users, but also to protect the work space per the appropriate Manual for Assessing Safety Hardware (MASH) crashworthiness requirements based on roadway speed and barrier application.
2. Water ballasted systems used to channelize vehicular traffic shall be supplemented with retroreflective delineation or channelizing devices to improve daytime/nighttime visibility. They may also be supplemented with pavement markings.
3. Water ballasted systems used as barriers shall be placed in accordance to application and installation requirements specific to the device, and used only when shown on the CWZTCD list.
4. Water ballasted systems used as barriers should not be used for a merging taper except in low speed (less than 45 MPH) urban areas. When used on a taper in a low speed urban area, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.
5. When water ballasted systems used as barriers have blunt ends exposed to traffic, they should be attenuated as per manufacturer recommendations or flared to a point outside the clear zone.

If used to channelize pedestrians, longitudinal channelizing devices or water ballasted systems must have a continuous detectable bottom for users of long canes and the top of the unit shall not be less than 32 inches in height.

HOLLOW OR WATER BALLASTED SYSTEMS USED AS LONGITUDINAL CHANNELIZING DEVICES OR BARRIERS

GENERAL NOTES

1. Work Zone channelizing devices illustrated on this sheet may be installed in close proximity to traffic and are suitable for use on high or low speed roadways. The Engineer/Inspector shall ensure that spacing and placement is uniform and in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUTCD).
2. Channelizing devices shown on this sheet may have a driveable, fixed or portable base. The requirement for self-righting channelizing devices must be specified in the General Notes or other plan sheets.
3. Channelizing devices on self-righting supports should be used in work zone areas where channelizing devices are frequently impacted by errant vehicles or vehicle related wind gusts making alignment of the channelizing devices difficult to maintain. Locations of these devices shall be detailed elsewhere in the plans. These devices shall conform to the TMUTCD and the "Compliant Work Zone Traffic Control Devices List" (CWZTCD).
4. The Contractor shall maintain devices in a clean condition and replace damaged, nonreflective, faded, or broken devices and bases as required by the Engineer/Inspector. The Contractor shall be required to maintain proper device spacing and alignment.
5. Portable bases shall be fabricated from virgin and/or recycled rubber. The portable bases shall weigh a minimum of 30 lbs.
6. Pavement surfaces shall be prepared in a manner that ensures proper bonding between the adhesives, the fixed mount bases and the pavement surface. Adhesives shall be prepared and applied according to the manufacturer's recommendations.
7. The installation and removal of channelizing devices shall not cause detrimental effects to the final pavement surfaces, including pavement surface discoloration or surface integrity. Driveable bases shall not be permitted on final pavement surfaces. The Engineer/Inspector shall approve all application and removal procedures of fixed bases.

Posted Speed	Formula	Minimum Desirable Taper Lengths *X			Suggested Maximum Spacing of Channelizing Devices	
		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent
30	L = WS ² / 60	150'	165'	180'	30'	60'
35		205'	225'	245'	35'	70'
40		265'	295'	320'	40'	80'
45	L = WS	450'	495'	540'	45'	90'
50		500'	550'	600'	50'	100'
55		550'	605'	660'	55'	110'
60		600'	660'	720'	60'	120'
65		650'	715'	780'	65'	130'
70		700'	770'	840'	70'	140'
75		750'	825'	900'	75'	150'
80		800'	880'	960'	80'	160'

*X Taper lengths have been rounded off.
L=Length of Taper (FT.) W=Width of Offset (FT.)
S=Posted Speed (MPH)

SUGGESTED MAXIMUM SPACING OF CHANNELIZING DEVICES AND MINIMUM DESIRABLE TAPER LENGTHS

SHEET 9 OF 12



BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC (9) -21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS				
9-07 8-14				RH
7-13 5-21	DIST	COUNTY	SHEET NO.	
	AUS	HAYS	21	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


TYPE 3 BARRICADES

1. Refer to the Compliant Work Zone Traffic Control Devices List (CWZTCD) for details of the Type 3 Barricades and a list of all materials used in the construction of Type 3 Barricades.
2. Type 3 Barricades shall be used at each end of construction projects closed to all traffic.
3. Barricades extending across a roadway should have stripes that slope downward in the direction toward which traffic must turn in detouring. When both right and left turns are provided, the chevron striping may slope downward in both directions from the center of the barricade. Where no turns are provided at a closed road, striping should slope downward in both directions toward the center of roadway.
4. Striping of rails, for the right side of the roadway, should slope downward to the left. For the left side of the roadway, striping should slope downward to the right.
5. Identification markings may be shown only on the back of the barricade rails. The maximum height of letters and/or company logos used for identification shall be 1".
6. Barricades shall not be placed parallel to traffic unless an adequate clear zone is provided.
7. Warning lights shall NOT be installed on barricades.
8. Where barricades require the use of weights to keep from turning over, the use of sandbags with dry, cohesionless sand is recommended. The sandbags will be tied shut to keep the sand from spilling and to maintain a constant weight. Sand bags shall not be stacked in a manner that covers any portion of a barricade rails reflective sheeting. Rock, concrete, iron, steel or other solid objects will NOT be permitted. Sandbags should weigh a minimum of 35 lbs and a maximum of 50 lbs. Sandbags shall be made of a durable material that tears upon vehicular impact. Rubber (such as tire inner tubes) shall not be used for sandbags. Sandbags shall only be placed along or upon the base supports of the device and shall not be suspended above ground level or hung with rope, wire, chains or other fasteners.
9. Sheeting for barricades shall be retroreflective Type A or Type B conforming to Departmental Material Specification DMS-8300 unless otherwise noted.

Barricades shall NOT be used as a sign support.




TYPICAL STRIPING DETAIL FOR BARRICADE RAIL



TYPICAL PANEL DETAIL FOR SKID OR POST TYPE BARRICADES


Each roadway of a divided highway shall be barricaded in the same manner.



PERSPECTIVE VIEW


The three rails on Type 3 barricades shall be reflectorized orange and reflective white stripes on one side facing one-way traffic and both sides for two-way traffic. Barricade striping should slant downward in the direction of detour.

1. Signs should be mounted on independent supports at a 7 foot mounting height in center of roadway. The signs should be a minimum of 10 feet behind Type 3 Barricades.
2. Advance signing shall be as specified elsewhere in the plans.




PLAN VIEW

TYPE 3 BARRICADE (POST AND SKID) TYPICAL APPLICATION




PERSPECTIVE VIEW



PLAN VIEW

CULVERT WIDENING OR OTHER ISOLATED WORK WITHIN THE PROJECT LIMITS

LEGEND	
	Plastic drum
	Plastic drum with steady burn light or yellow warning reflector
	Steady burn warning light or yellow warning reflector




Two-Piece cones

One-Piece cones

Tubular Marker

28" Cones shall have a minimum weight of 9 1/2 lbs.
 42" 2-piece cones shall have a minimum weight of 30 lbs. including base.

1. Traffic cones and tubular markers shall be predominantly orange, and meet the height and weight requirements shown above.
2. One-piece cones have the body and base of the cone molded in one consolidated unit. Two-piece cones have a cone shaped body and a separate rubber base, or ballast, that is added to keep the device upright and in place.
3. Two-piece cones may have a handle or loop extending up to 8" above the minimum height shown, in order to aid in retrieving the device.
4. Cones or tubular markers shall have white or white and orange reflective bands as shown above. The reflective bands shall have a smooth, sealed outer surface and meet the requirements of Departmental Material Specification DMS-8300 Type A or Type B.
5. 28" cones and tubular markers are generally suitable for short duration and short-term stationary work as defined on BC(4). These should not be used for intermediate-term or long-term stationary work unless personnel is on-site to maintain them in their proper upright position.
6. 42" two-piece cones, vertical panels or drums are suitable for all work zone durations.
7. Cones or tubular markers used on each project should be of the same size and shape.



TRAFFIC CONTROL FOR MATERIAL STOCKPILES




BARRICADE AND CONSTRUCTION CHANNELIZING DEVICES

BC(10)-21


FILE: bc-21.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT November 2002	CONT	SECT	JOB	HIGHWAY
REVISIONS				
9-07 8-14				RH
7-13 5-21				
AUS	DIST	COUNTY	SHEET NO.	
	AUS	HAYS	22	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:14:08 AM
FILE: \$FILES



ROAD CLOSURE BEYOND THE INTERSECTION
Signing for a Numbered Route with an Off-Site Detour



ROAD CLOSURE AT THE INTERSECTION
Signing for an Un-numbered Route with an Off-Site Detour

LEGEND	
	Type 3 Barricade
	Sign

Posted Speed *	Minimum Sign Spacing "X" Distance
30	120'
35	160'
40	240'
45	320'
50	400'
55	500'
60	600'
65	700'
70	800'
75	900'

* Conventional Roads Only

GENERAL NOTES

1. This sheet is intended to provide details for temporary work zone road closures. For permanent road closure details see the D&OM standards.
2. Barricades used shall meet the requirements shown on Barricade and Construction Standard BC(10) and listed on the Compliant Work Zone Traffic Control Devices list (CWZTCD).
3. Stockpiled materials shall not be placed on the traffic side of barricades.
4. Barricades at the road closure should extend from pavement edge to pavement edge.
5. Detour signing shown is intended to illustrate the type of signing that is appropriate for numbered routes or un-numbered routes as labeled. It does not indicate the full extent of detour signing required. Detour routes should be signed as shown elsewhere in the plans.
6. If the road is open for a significant distance beyond the intersection or there are significant origin/destination points beyond the intersection, the signs and barricades at this location should be located at the edge of the traveled way.
7. The Street Name (M4-12T) sign is to be placed above the DETOUR (M4-9S) sign.
8. For urban areas where there is a shorter distance between the intersection and the actual closure location, the ROAD CLOSED XX MILES AHEAD (R11-3a) sign may be replaced with a ROAD CLOSED TO THRU TRAFFIC (R11-4) sign. If adequate space does not exist between the intersection and the closure a single ROAD CLOSED AHEAD (CW20-3D) sign spaced as per the table above may replace the ROAD CLOSED 1000 FT (CW20-3B) and ROAD CLOSED 500 FT (CW20-3C) signs.
9. Signs and barricades shown shall be subsidiary to Item 502. Locations where these details will be required shall be as shown elsewhere in the plans.



WORK ZONE ROAD CLOSURE DETAILS
WZ (RCD) - 13

FILE: w2rcd-13.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 1995	CONT	SECT	JOB	HIGHWAY
REVISIONS				
1-97 4-98 7-13	DIST	COUNTY	SHEET NO.	
2-98 3-03	AUS	HAYS	23	

PROPOSED SHANE LANE ALIGNMENT DATA (C SHANE)


	STATION	NORTHING	EASTING
Element: Linear			
POB ()	100+00.00	13986042.754	2251475.405
PC ()	101+02.81	13986044.685	2251578.195
Tangent Direction:	N 88° 55' 24.53" E		
Tangent Length:	102.8089		
Element: Circular			
PC ()	101+02.81	13986044.685	2251578.195
PI ()	101+69.52	13986045.938	2251644.892
CC ()	102+36.14	13984544.950	2251606.377
PT ()	102+36.14	13986041.266	2251711.437
Radius:	1500.0000		
Delta:	5° 05' 34.15" Right		
Degree of Curvature (Arc):	3° 49' 10.99"		
Length:	133.3297		
Tangent:	66.7088		
Chord:	133.2858		
Middle Ordinate:	1.4812		
External:	1.4826		
Tangent Direction:	N 88° 55' 24.53" E		
Radial Direction:	S 1° 04' 35.47" E		
Chord Direction:	S 88° 31' 48.39" E		
Radial Direction:	S 4° 00' 58.69" W		
Tangent Direction:	S 85° 59' 01.31" E		
Element: Linear			
PT ()	102+36.14	13986041.266	2251711.437
PC ()	103+57.46	13986032.768	2251832.465
Tangent Direction:	S 85° 59' 01.31" E		
Tangent Length:	121.3258		
Element: Circular			
PC ()	103+57.46	13986032.768	2251832.465
PI ()	104+93.00	13986023.276	2251967.664
CC ()	105+92.92	13986222.302	2251845.773
PT ()	105+92.92	13986148.020	2252020.651
Radius:	190.0000		
Delta:	71° 00' 08.40" Left		
Degree of Curvature (Arc):	30° 09' 20.42"		
Length:	235.4527		
Tangent:	135.5315		
Chord:	220.6734		
Middle Ordinate:	35.3203		
External:	43.3855		
Tangent Direction:	S 85° 59' 01.31" E		
Radial Direction:	S 4° 00' 58.69" W		
Chord Direction:	N 58° 30' 54.49" E		
Radial Direction:	S 66° 59' 09.71" E		
Tangent Direction:	N 23° 00' 50.29" E		
Element: Linear			
PT ()	105+92.92	13986148.020	2252020.651
POE ()	109+51.81	13986478.352	2252160.963
Tangent Direction:	N 23° 00' 50.29" E		
Tangent Length:	358.8963		

PROPOSED DRIVEWAY01 ALIGNMENT DATA (C DRWY01)

	STATION	NORTHING	EASTING
Element: Linear			
POB ()	10+00.00	13986042.178	2251697.525
POE ()	10+39.54	13986002.710	2251695.123
Tangent Direction:	S 3° 29' 01.54" W		
Tangent Length:	39.5409		

PROPOSED SIDEWALK ALIGNMENT DATA (R SDWK01)

	STATION	NORTHING	EASTING
Element: Linear			
POB ()	10+00.00	13986016.142	2251783.716
PC ()	10+04.40	13986015.834	2251788.104
Tangent Direction:	S 85° 59' 01.31" E		
Tangent Length:	4.3987		
Element: Circular			
PC ()	10+04.40	13986015.834	2251788.104
PI ()	10+34.33	13986013.737	2251817.962
CC ()	10+51.45	13985985.907	2251786.003
PT ()	10+51.45	13985983.875	2251815.934
Radius:	30.0000		
Delta:	89° 52' 04.14" Right		
Degree of Curvature (Arc):	190° 59' 09.35"		
Length:	47.0547		
Tangent:	29.9309		
Chord:	42.3774		
Middle Ordinate:	8.7623		
External:	12.3776		
Tangent Direction:	S 85° 59' 01.31" E		
Radial Direction:	S 4° 00' 58.69" W		
Chord Direction:	S 41° 02' 59.24" E		
Radial Direction:	N 86° 06' 57.17" W		
Tangent Direction:	S 3° 53' 02.83" W		
Element: Linear			
PT ()	10+51.45	13985983.875	2251815.934
PC ()	10+65.20	13985970.157	2251815.003
Tangent Direction:	S 3° 53' 02.83" W		
Tangent Length:	13.7502		
Element: Circular			
PC ()	10+65.20	13985970.157	2251815.003
PI ()	11+03.05	13985932.394	2251812.439
CC ()	11+38.60	13985961.893	2251936.723
PT ()	11+38.60	13985899.812	2251831.699
Radius:	122.0000		
Delta:	34° 28' 18.88" Left		
Degree of Curvature (Arc):	46° 57' 49.51"		
Length:	73.4011		
Tangent:	37.8492		
Chord:	72.2990		
Middle Ordinate:	5.4787		
External:	5.7363		
Tangent Direction:	S 3° 53' 02.83" W		
Radial Direction:	N 86° 06' 57.17" W		
Chord Direction:	S 13° 21' 06.61" E		
Radial Direction:	S 59° 24' 43.95" W		
Tangent Direction:	S 30° 35' 16.05" E		



NO.	DATE	REVISION	APPROVED

HDR
HDR
Firm Registration No. F-754
710 Hesters Crossing, Suite 150
Round Rock, Texas 78681
512.685.2900




ROGER HANKS

HORIZONTAL ALIGNMENT DATA

SHEET 1 OF 1

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
SJ				RH
GRAPHICS				SHEET NO.
KB	STATE	DISTRICT	COUNTY	
CHECK	TEXAS	AUS	HAYS	
JC	CONTROL	SECTION	JOB	
CHECK				24
JC				



PLOT DRIVER: TXDOT_PDF_LW.plt
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Shane Lane Removal Layout
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023
 TIME: 8:14:26 AM
 SCALE: 1:40



LEGEND

	PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
	EXISTING RIGHT OF WAY
	PROPOSED RIGHT OF WAY
	PROPOSED CONSTRUCTION BY OTHERS
	REMOVE STAB BASE AND ASPH PAV
	REMOVE CONCRETE

- NOTES:**
1. ANY ITEMS REQUIRING REMOVAL THAT ARE NOT DIRECTLY CALLED OUT SHALL BE CONSIDERED SUBSIDIARY TO PREP ROW.
 2. SAW CUTTING WILL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED SUBSIDIARY TO PERTINENT BID ITEMS.
 3. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.
 4. CONTRACTOR WILL COORDINATE REMOVAL ITEMS WITH THE ADJACENT CONTRACTOR FOR THE "ROGER HANKS IMPROVEMENTS PROJECT".



Professional Engineer Seal for Felipe S. Toldtud, State of Texas, License No. 104836, dated 10/04/2023. Includes a signature.


HDR
 HDR Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900

THE CITY OF DRIPPING SPRINGS TEXAS
 © 2023

**ROGER HANKS
 REMOVAL LAYOUT**

SHEET 1 OF 1



DESIGN	SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS	KB	STATE	DISTRICT	COUNTY	RH
CHECK	JC	TEXAS	AUS	HAYS	SHEET NO.
CHECK	JC	CONTROL	SECTION	JOB	25



LEGEND

---	PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
---	EXISTING RIGHT OF WAY
---	PROPOSED RIGHT OF WAY
→	TRAVEL LANE
---	PROPOSED CONSTRUCTION BY OTHERS

- NOTES:**
- SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ALIGNMENT INFORMATION.
 - SAW CUTTING WILL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED SUBSIDIARY TO PERTINENT BID ITEMS.
 - THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.
 - ROADWAY DIMENSIONS ARE TO THE EDGE OF PAVEMENT (EOP) UNLESS NOTED OTHERWISE.
 - STATION AND OFFSET FOR INLET ARE TO CENTER OF VAULT. INLET ELEVATIONS ARE INFALL ELEVATIONS UNLESS NOTED OTHERWISE.
 - PAZD INLET ELEVATIONS ARE TOP OF GRATE ELEVATION. DITCH ELEVATIONS TIE TO TOP OF APRON.



Felipe Tutud

NO.	DATE	REVISION	APPROVED

HDR
Firm Registration No. F-754
710 Hesters Crossing, Suite 150
Round Rock, Texas 78681
512.685.2900

THE CITY OF
DRIPPING SPRINGS
TEXAS © 2023

ROGER HANKS


**ROADWAY
PLAN AND PROFILE**

SHEET 1 OF 2

DESIGN SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS KB	STATE	DISTRICT	COUNTY
CHECK JC	TEXAS	AUS	HAYS
CHECK JC	CONTROL	SECTION	JOB

26


PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Shane Lane Plan and Profile
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023
 TIME: 8:44:31 AM
 SCALE: 1/40



LEGEND

- - - - - PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
- - - - - EXISTING RIGHT OF WAY
- - - - - PROPOSED RIGHT OF WAY
- TRAVEL LANE
- - - - - PROPOSED CONSTRUCTION BY OTHERS
- - - - - DITCH A FLOWLINE


- NOTES:**
- SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ALIGNMENT INFORMATION.
 - SAW CUTTING WILL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED SUBSIDIARY TO PERTINENT BID ITEMS.
 - THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.
 - ROADWAY DIMENSIONS ARE TO THE EDGE OF PAVEMENT (EOP) UNLESS NOTED OTHERWISE.
 - STATION AND OFFSET FOR INLET ARE TO CENTER OF VAULT. INLET ELEVATIONS ARE INFALL ELEVATIONS UNLESS NOTED OTHERWISE.
 - PAZD INLET ELEVATIONS ARE TOP OF GRATE ELEVATION. DITCH ELEVATIONS TIE TO TOP OF APRON.



DRAINAGE HYDRAULIC NOTES:

- THE 25-YEAR HGL IS UNDER THE PROPOSED GROUND SURFACE FOR ALL PIPES AS PER THE COA DCM.
- THE MINIMUM AND MAXIMUM PIPE VELOCITIES ARE 2.5 AND 20 FPS FOR THE 25-YEAR DESIGN STORM PER THE COA DCM.

Pipe ID	Storm Drain Hydraulic Data																	
	Data					25 YR					100 YR							
	FL Elevation (ft)	In	Out	Length (ft)	Slope (%)	Capacity (cfs)	HGL (ft)	In	Out	Q (cfs)	V (fps)	Depth (ft)	HGL (ft)	In	Out	Q (cfs)	V (fps)	Depth (ft)
A	1230.5	1229.75	35	2.17%	33.5	1231.57	1230.82	1230.82	18.9	10.96	1.07	1233.94	1233.39	27.9	8.88	2		
B	1229.75	1229.42	15	2.17%	33.5	1230.82	1230.5	1230.5	18.9	10.96	1.07	1232.2	1232.66	27.9	8.88	2		
C	1228.83	1228.2	126	0.50%	17.1	1230.31	1230	1230	12	3.82	2	1233.31	1232.5	17.9	5.7	2		



FELIPE S. TUDUD
104836
PROFESSIONAL ENGINEER
10/04/2023

NO.	DATE	REVISION	APPROVED

HDR
HDR
Firm Registration No. F-754
710 Hesters Crossing, Suite 150
Round Rock, Texas 78681
512.685.2900

THE CITY OF DRIPPING SPRINGS TEXAS
© 2023

ROGER HANKS


ROADWAY PLAN AND PROFILE

SHEET 2 OF 3

DESIGN	SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS	KB	STATE	DISTRICT	COUNTY
CHECK	JC	TEXAS	AUS	HAYS
CHECK	JC	CONTROL	SECTION	JOB

27

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Share Lane Plan and Profile
 SCALE: 1/40
 TIME: 8:44:35 AM
 DATE: 10/4/2023



CONCRETE DRIVEWAY

GENERAL NOTES:

PROVIDE EXPANSION 20 FT C-C FOR WIDTH OR LENGTH OVER 25FT. EXPANSION JOINT PER AUS STANDARD FOR SIDEWALK (MCP SWMD).

REINFORCEMENT WILL BE IN ACCORDANCE WITH ITEM 432.3.1 USING NO. 3 OR NO. 4 BARS.

FIBER REINFORCEMENT IS NOT ALLOWED. CLASS A CONCRETE IS ALLOWED TO USE COARSE AGGREGATE GRADES 1-8.

FURNISH BASE MEETING THE REQUIREMENTS FOR ANY TYPE OR GRADE IN ACCORDANCE WITH ITEM 247. BASE COMPRESSIVE STRENGTHS ARE WAIVED.

THE BASE UNDER THE CONCRETE MAY BE REPLACED WITH CONCRETE AT A RATIO OF 3 INCHES OF BASE EQUALS 2 INCHES OF CONCRETE.





IF ROOTS ARE ENCOUNTERED VERIFY WITH THE ENGINEER PRIOR TO ACCOMMODATING OR REMOVING 2 IN. DIAMETER OR LARGER ROOTS. ROOT REMOVAL MUST BE IN ACCORDANCE WITH ITEM 752.4.2 ROOTS MAY REMAIN IN THE BASE. FOR IMPROVEMENTS WITH 6 IN. OF A ROOT, THE CONCRETE THICKNESS MAY BE REDUCED BY 1 IN. AND THE BASE INCREASED BY 1 IN. TO MINIMIZE IMPACTS TO THE ROOTS. ADJUST BASE AND SURFACE PROFILE TO PROVIDE A 1 IN. BASE CUSHION AROUND THE ROOTS. THE SURFACE PROFILE MAY BE ADJUSTED TO THE EXTENT ALLOWED BY ADA. THIS WORK IS SUBSIDIARY TO ITEM 530.

LEGEND

	PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
	EXISTING RIGHT OF WAY
	PROPOSED RIGHT OF WAY
	TRAVEL LANE
	PROPOSED CONSTRUCTION BY OTHERS

NOTES:

- SEE "HORIZONTAL ALIGNMENT DATA" SHEET FOR ALIGNMENT INFORMATION.
- SAW CUTTING WILL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED SUBSIDIARY TO PERTINENT BID ITEMS.
- THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.
- ROADWAY DIMENSIONS ARE TO THE EDGE OF PAVEMENT (EOP) UNLESS NOTED OTHERWISE.
- STATION AND OFFSET FOR INLET ARE TO CENTER OF VAULT. INLET ELEVATIONS ARE INFALL ELEVATIONS UNLESS NOTED OTHERWISE.
- PAZD INLET ELEVATIONS ARE TOP OF GRATE ELEVATION. DITCH ELEVATIONS TIE TO TOP OF APRON.
- SLOPE SIDEWALK TO DRAIN.



NO.	DATE	REVISION	APPROVED

HR HDR
Firm Registration No. F-754
710 Hesters Crossing, Suite 150
Round Rock, Texas 78681
512.685.2900

THE CITY OF DRIPPING SPRINGS TEXAS © 2023

ROGER HANKS

DRIVEWAY AND SIDEWALK PLAN AND PROFILE

SHEET 1 OF 1


DESIGN	SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS	KB	STATE	DISTRICT	COUNTY
CHECK	JC	TEXAS	AUS	HAYS
CHECK	JC	CONTROL	SECTION	JOB

28


PENTABLE: 10338078.tbl
 DATE: 10/4/2023 TIME: 8:14:39 AM SCALE: 1:40
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Connector Plan and Profile

DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.


DATE: 10/4/2023
FILE: \$FILES\$




TYPICAL POST PLACEMENT



WOOD BLOCK TO ROUND WOOD POST




WOOD BLOCK TO RECTANGULAR WOOD POST



ROUTED WOOD BLOCK TO I-BEAM STEEL POST


- GENERAL NOTES**
1. THE TYPE OF POST (ROUND WOOD POST, RECTANGULAR WOOD POST, OR STEEL POST) WILL BE AS SHOWN IN THE PLANS. THE EXACT POSITION OF MBGF SHALL BE SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. STEEL POSTS TO BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING."
 2. RAIL ELEMENTS SHALL MEET THE REQUIREMENTS OF ITEM 540, "METAL BEAM GUARD FENCE" EXCEPT AS MODIFIED IN THE PLANS. THE CONTRACTOR MAY FURNISH RAIL ELEMENTS OF 25'-0", OR 12'-6" (NOM.) LENGTHS. RAIL ELEMENTS MAY HAVE SLOTTED HOLES AT 3'-1 1/2" C-C OR 6'-3" C-C. A SPECIAL LENGTH OF RAIL MAY BE MANUFACTURED TO ACCOMMODATE THE DOWNSTREAM ANCHOR TERMINAL (DAT) AND THE TRANSITION SECTIONS OF GUARDRAIL.
 3. BUTTON HEAD "POST BOLTS & NUTS" SHALL MEET THE REQUIREMENTS OF (ASTM A307), AND SHALL BE OF SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND 5/8" WASHER (FWC16d) AND NOT MORE THAN 1" BEYOND IT. TRIM REMAINING BOLT LENGTH TO MEET REQUIRED LENGTH.
 4. FITTINGS (BOLTS, NUTS, AND WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING." FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 5. CROWN SHALL BE WIDENED TO ACCOMMODATE THE METAL BEAM GUARD FENCE.
 6. THE LATERAL APPROACH TO THE GUARD FENCE, SHALL HAVE A MAXIMUM SLOPE OF 1V:10H.
 7. IF SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER, THE GUARD FENCE MAY BE FLARED AT A RATE OF 25:1 OR FLATTER.
 8. UNLESS OTHERWISE SHOWN IN THE PLANS, GUARD FENCE PLACED IN THE VICINITY OF CURBS SHALL BE POSITIONED SO THAT THE FACE OF CURB IS LOCATED DIRECTLY BELOW OR BEHIND THE FACE OF THE RAIL. RAIL PLACED OVER CURBS SHALL BE INSTALLED SO THAT THE POST BOLT IS LOCATED APPROXIMATELY 25 INCHES ABOVE THE GUTTER PAN OR EDGE OF SHOULDER.
 9. APPLICATIONS IN SOLID ROCK ARE ONLY ALLOWED WITH STEEL POSTS. IF SOLID ROCK IS ENCOUNTERED WITHIN 0 TO 18" OF THE FINISHED GRADE, DRILL A 24" DIA. HOLE, 24" INTO THE ROCK. IF SOLID ROCK IS ENCOUNTERED BELOW 18", DRILL A 12" DIA. HOLE, 12" INTO THE ROCK OR TO THE STANDARD EMBEDMENT DEPTH, WHICHEVER MAYBE LESS. ANY EXCESS POST LENGTH, AFTER MEETING THESE DEPTHS, MAY BE FIELD CUT TO ENSURE PROPER GUARDRAIL MOUNTING HEIGHT. BACKFILL WITH COARSE AGGREGATE MATERIAL.
 10. POSTS SHALL NOT BE SET IN CONCRETE, OF ANY DEPTH.
 11. SPECIAL FABRICATION WILL BE REQUIRED AT INSTALLATION LOCATIONS HAVING A CURVATURE OF LESS THAN 150 FT. RADIUS.
 12. UNLESS OTHERWISE SHOWN IN THE PLANS, A COMPOSITE MATERIAL BLOCK THAT MEETS THE REQUIREMENTS OF DMS-7210, "COMPOSITE MATERIAL POSTS AND BLOCKS FOR METAL BEAM GUARD FENCE" MAY BE SUBSTITUTED FOR BLOCKS OF SIMILAR DIMENSIONS. THE CONSTRUCTION DIVISION, TXDOT MAINTAINS A MATERIAL PRODUCER LIST (MPL) FOR PRODUCERS OF MATERIALS CONFORMING TO DMS-7210 ONLY PRODUCERS ON THE MPL MAY FURNISH COMPOSITE MATERIAL BLOCKS.
 13. FOR THE LOW FILL CULVERT OPTION, POSTS LOCATED PARTIALLY OR WHOLLY BETWEEN PRECAST BOX CULVERT UNITS, THE USE OF A CAST-IN-PLACE CONCRETE CLOSURE BETWEEN BOXES IS REQUIRED. THE LENGTH OF THE CAST-IN-PLACE CONCRETE CLOSURE SHALL ACCOMMODATE THE PLACEMENT OF THE LOW FILL CULVERT OPTION. SEE CONCRETE CLOSURE DETAILS ON BRIDGE STANDARD SCP-MD.
 14. GUARDRAIL HEIGHT MEASUREMENT: WHEN THE GUARDRAIL IS LOCATED ABOVE PAVEMENT, MEASURE THE HEIGHT FROM THE PAVEMENT TO THE TOP OF THE W-BEAM RAIL. WHEN THE GUARDRAIL IS LOCATED UP TO 2 FT. OFF OF THE EDGE OF PAVEMENT OR FOR A PAVEMENT OVERLAY, USE A 10-FOOT STRAIGHTEDGE TO EXTEND THE PAVEMENT/SHOULDER SLOPE TO THE BACK OF RAIL, MEASURE FROM THE BOTTOM OF STRAIGHTEDGE TO THE TOP OF RAIL. FOR GUARDRAIL LOCATED DOWN A 10:1 SLOPE, MEASURE FROM THE NOMINAL TERRAIN.

NOTE: ** "WOOD" INDICATES DIMENSIONS FOR BOTH ROUND AND RECTANGULAR WOOD POST SYSTEMS.



ELEVATION MID-SPAN RAIL SPLICE

SHOWING A 25'-0" SECTION OF W-BEAM RAIL. (SEE GENERAL NOTE 2)



ELEVATION 25'-0" (NOM.) W-BEAM SECTION

NOTES: SEE GENERAL NOTE 2 FOR ALLOWABLE RAIL TYPES. SEE RAIL SPLICE DETAIL FOR REQUIRED HARDWARE.

NOTE: FOUR TYPES OF BUTTON-HEAD GUARD RAIL BOLTS COME WITH A RECESSED NUT.

SPLICE BOLT LENGTH VARIES

FBB01 = 1 1/4"

FBB02 = 2"


POST & BLOCK LENGTH

FBB03 = 10"

FBB04 = 18"

BUTTON HEAD BOLT


NOTE: SEE GENERAL NOTE 3 FOR SPLICE & POST BOLT DETAILS.



MID-SPAN RAIL SPLICE DETAIL

NOTE: GF(31), MID-SPAN RAIL SPLICES ARE REQUIRED WITH 6'-3" POST SPACINGS.

* POST(S) MAY REQUIRE FIELD MODIFICATION TO ENSURE PROPER GUARDRAIL HEIGHT.



LOW FILL CULVERT POST

12" X 12" X 1/4" (ASTM A36) STEEL BOTTOM PLATE WITH 1" DIA. HOLES REQUIRED WITH BOLT-THROUGH INSTALLATION.

NOTE: TWO INSTALLATION OPTIONS.


1. **BOLT-THROUGH OPTION:** REQUIRES A 6" MIN. SLAB THICKNESS. 7/8" DIA (ASTM A449) HEAVY HEX BOLTS WITH TWO HARDENED WASHER EACH AND HEAVY HEX NUTS. NOTE: BOLT LENGTH = SLAB PLUS 2 1/4" MIN.
2. **EPOXY ANCHOR OPTION:** THIS OPTION MAY ONLY BE USED IF THE CULVERT SLAB IS 9" MIN. THICK. THREADED ANCHOR RODS MUST BE 7/8" DIA. ASTM A449 OR A193 GRADE B7 WITH HEAVY HEX NUT, AND ONE HARDENED WASHER EACH. EMBED ANCHOR RODS 6" WITH HILTI HIT RE 500 EPOXY ADHESIVE. OTHER TYPE III CLASS C EPOXY ADHESIVES MEETING THE REQUIREMENTS OF DMS-6100, "EPOXIES AND ADHESIVES", MAY BE USED IF IT CAN BE DEMONSTRATED THAT THEY MEET OR EXCEED THE STRENGTH OF HILTI HIT RE 500 WITH THE SAME EMBEDMENT DEPTH AND THREADED ROD DIA. FOLLOW THE MANUFACTURER'S REQUIREMENTS FOR INSTALLING EPOXIED THREADED RODS. EXTEND RODS 1/4" MIN. BEYOND NUT.

NOTE: CULVERTS OF 25 FT. OR LESS, SEE GF(31)LS STANDARD FOR "LONG SPAN" OPTION.

				Design Division Standard	
METAL BEAM GUARD FENCE TL-3 MASH COMPLIANT GF(31)-19					
FILE: gf3119.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CGL/AG	
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB	HIGHWAY	
REVISIONS					
	DIST	COUNTY	SHEET NO.		
	AUS	HAYS	29		


DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 10/4/2023
 FILE: \$FILES\$




GRADING AND MOW STRIP AT GUARDRAIL END TREATMENTS

Note: Site Condition(s)
 Site conditions may exist where grading is required for the proper installation of metal guard fence and end treatments.
 Approach grading or mow strip may be decreased or eliminated, as directed by the Engineer.




PLAN

GF(31) shown with Mow Strip
 (See GF(31) standard sheet for proper installation)



SECTION A-A


Typical



MOW STRIP DETAIL


Reinforced Concrete Mow Strip with 18" x 18" Square or 18" Dia. minimum leave-out.

- GENERAL NOTES**
1. This mow strip design is for use with metal beam guard fence, guard fence transitions, and guard fence end treatments. See applicable GF(31) MBGF or GF(31) Transition Standard sheet for additional information.
 2. Mow strips shall be reinforced concrete with (wire mesh or synthetic fiber), as shown on the plans and will be paid for under the pertinent bid item. Reinforced concrete shall be placed in accordance with Item 432, "Riprap." The use of the synthetic fiber in lieu of steel reinforcing is acceptable, provided the fiber producer is on the Department Material Producer List (MPL), maintained by TxDOT, Construction Division.
 3. The leave-out behind the post shall be a minimum of 7".
 4. Only steel (W6 x 8.5 or W6 x 9.0), or 7 1/2" Dia. round wood posts are acceptable for use in the mow strip. See GF(31) Standard for additional details.
 5. Other curb placement options may be used. Curbs are not considered part of the mow strip and will be paid for under other pertinent bid item.
 6. Thickness of the mow strip will be 4".
 7. The limits of payment for reinforced concrete will include leave-outs for the posts.
 8. The leave-outs shall be filled with a Grout mixture consisting of: 2719 pounds sand, 188 pounds Type 1 or II cement, and 550 pounds of water per cubic yard, with a 28-day compressive strength of approximately 230 psi or less. Provide grout with a consistency that will flow into and completely fill all voids. Due to auger size, larger leave-out dimensions are acceptable from both an impact performance and maintenance repair standpoint (Suggested Maximum leave-out of 20"). Payment for furnishing and placing the grout mixture will be subsidiary to the pay item of riprap mow strip.




CURB OPTION (1)

This option will increase the post embedment throughout the system.



CURB OPTION (2)

Curb shown on top of mow strip




CURB OPTION (3)

		Design Division Standard	
METAL BEAM GUARD FENCE (MOW STRIP) TL-3 MASH COMPLIANT GF (31) MS-19			
FILE: gf31ms19.dgn	DN: TXDOT	CK: KM	DW: VP
© TXDOT: NOVEMBER 2019	CONT	SECT	JOB
REVISIONS		HIGHWAY	
		RH	
DIST	COUNTY	SHEET NO.	
AUS	HAYS	30	





DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023
FILE: \$FILES




- NOTES:
- ITEM ② COMPOSITE BLOCKOUTS INSTALLED AT LINE POST (9) THRU LINE POST (2).
 - DO NOT INSTALL A BLOCKOUT AT LINE POST (1).


NOTE: SECURE THE (TSS) PANEL TO OUTSIDE OF RAIL 2 WITH THE PANEL ARROWS POINTING TOWARDS THE HEAD.



SOIL ANCHOR, POST 1 & LINE POST 2 THRU 9
SECTION VIEW A-A



- * TO BE PROVIDED BY DISTRIBUTOR OR CONTRACTOR.
- ** ALTERNATIVE ITEMS NOT SHOWN. ITEM (26) 8" WOOD-BLOCKOUTS ITEM (27) 25' GUARD FENCE PANELS



NOTE: TxDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.

APPROACH GRADING AT GUARDRAIL END TREATMENTS

NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MAX-TENSION END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

GENERAL NOTES

- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: LINDSAY TRANSPORTATION SOLUTIONS (LTS) - BARRIER SYSTEMS, INC. AT (707) 374-6800
- FOR INSTALLATION, REPAIR, & MAINTENANCE REFER TO THE: MAX-TENSION INSTALLATION INSTRUCTION MANUAL. P/N MANMAX REV D (ECN 3516).
- APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
- FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TxDOT'S LATEST ROADWAY MOW STRIP STANDARD.
- ALL STEEL COMPONENTS ARE GALVANIZED PER ASTM A123 OR EQUIVALENT UNLESS OTHERWISE STATED.
- SYSTEM SHOWN USING STEEL WIDE FLANGE POST WITH COMPOSITE BLOCKOUTS.
- COMPOSITE MATERIAL BLOCKOUT THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
- REFER TO INSTALLATION MANUAL FOR SPECIFIC PANEL LAPPING GUIDANCE.
- IF SOLID ROCK IS ENCOUNTERED SEE THE MANUFACTURER'S INSTALLATION MANUAL FOR INSTALLATION GUIDANCE.
- POSTS SHALL NOT BE SET IN CONCRETE.
- A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POST TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST.
- MAX-TENSION SYSTEM SHALL NEVER BE INSTALLED WITHIN A CURVED SECTION OF GUARDRAIL.
- IF A DELINEATION MARKER IS REQUIRED, MARKER SHALL BE IN ACCORDANCE WITH TEXAS MUTCD.
- THE SYSTEM IS SHOWN WITH 12'-6" MBGF PANELS, 25'-0" MBGF PANELS ARE ALSO ALLOWED.
- A MINIMUM OF 12'-6" OF 12GA. MBGF IS REQUIRED IMMEDIATELY DOWNSTREAM OF THE MAX-TENSION SYSTEM.

ITEM#	PART NUMBER	DESCRIPTION	QTY
1	BSI-1610060-00	SOIL ANCHOR - GALVANIZED	1
2	BSI-1610061-00	GROUND STRUT - GALVANIZED	1
3	BSI-1610062-00	MAX-TENSION IMPACT HEAD	1
4	BSI-1610063-00	W6x9 I-BEAM POST 6FT.-GALVANIZED	1
5	BSI-1610064-00	TSS PANEL - TRAFFIC SIDE SLIDER	1
6	BSI-1610065-00	ISS PANEL - INNER SIDE SLIDER	1
7	BSI-1610066-00	TOOTH - GEOMET	1
8	BSI-1610067-00	RSS PLATE - REAR SIDE SLIDER	1
9	B061058	CABLE FRICTION PLATE - HEAD UNIT	1
10	BSI-1610069-00	CABLE ASSEMBLY - MASH X-TENSION	2
11	BSI-1012078-00	X-LITE LINE POST-GALVANIZED	8
12	B090534	8" W-BEAM COMPOSITE-BLOCKOUT XT110	8
13	BSI-4004386	12'-6" W-BEAM GUARD FENCE PANELS 12GA.	4
14	BSI-1102027-00	X-LITE SQUARE WASHER	1
15	BSI-2001886	5/8" X 7" THREAD BOLT HH (GR.5)GEOMET	1
16	BSI-2001885	3/4" X 3" ALL-THREAD BOLT HH (GR.5)GEOMET	4
17	4001115	5/8" X 1 1/4" GUARD FENCE BOLTS (GR.2)MGAL	48
18	2001840	5/8" X 10" GUARD FENCE BOLTS MGAL	8
19	2001636	5/8" WASHER F436 STRUCTURAL MGAL	2
20	4001116	5/8" RECESSED GUARD FENCE NUT (GR.2)MGAL	59
21	BSI-2001888	5/8" X 2" ALL THREAD BOLT (GR.5)GEOMET	1
22	BSI-1701063-00	DELINEATION MOUNTING (BRACKET)	1
23	BSI-2001887	1/4" X 3/4" SCREW SD HH 410SS	7
24	4002051	GUARDRAIL WASHER RECT AASHTO FWRO3	1
25	SEE NOTE BELOW	HIGH INTENSITY REFLECTIVE SHEETING	1
26	4002337	8" W-BEAM TIMBER-BLOCKOUT, PDB01B	8
27	BSI-4004431	25' W-BEAM GUARDRAIL PANEL, 8-SPACE, 12GA.	2
28	MANMAX Rev- (D)	MAX-TENSION INSTALLATION INSTRUCTIONS	1

Texas Department of Transportation Design Division Standard


MAX-TENSION END TERMINAL MASH - TL-3

SGT (11S) 31-18

FILE: sg+11s3118.dgn DN: TxDOT CK: KM DW: TxDOT CK: CL
© TxDOT: FEBRUARY 2018 CONT SECT JOB HIGHWAY
REVISIONS RH
DIST COUNTY SHEET NO.
AUS HAYS 31



DISCLAIMER: THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.

DATE: 10/4/2023
 FILE: \$FILES\$




- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: ROAD SYSTEMS, INC. (432)263-2435. 3616 OLD HOWARD COUNTY AIRPORT, BIG SPRING, TX 79720
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE: MSKT END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL (PUBLICATION-062717).
 - APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" ON THE FRONT FACE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - SYSTEM SHOWN USING STEEL WIDE FLANGE POSTS WITH COMPOSITE BLOCKOUTS.
 - A COMPOSITE MATERIAL BLOCKOUTS THAT MEETS THE REQUIREMENTS OF DMS-7210, MAY BE SUBSTITUTED FOR BLOCKOUTS OF SIMILAR DIMENSIONS. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - IF SOLID ROCK IS ENCOUNTERED IN THE AREA OF (POST 1) AND / OR (POST 2) CONTACT THE MANUFACTURER, & REFER TO THE LATEST ROADWAY MBSGF STANDARD FOR INSTALLATION GUIDANCE.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - SYSTEM MUST BE ATTACHED TO STANDARD 31" MBSGF.
 - UNDER NO CIRCUMSTANCES SHALL THE GUARDRAIL WITHIN THE MSKT SYSTEM BE CURVED.
 - A FLARE RATE OF UP TO 25:1 MAY BE USED TO PREVENT THE TERMINAL HEAD FROM ENCRANCHING ON THE SHOULDER. THE FLARE MAY BE DECREASED OR ELIMINATED FOR SPECIFIC INSTALLATIONS, IF DIRECTED BY THE ENGINEER.
 - THE SYSTEM IS SHOWN WITH TWO 12'-6" MBSGF PANELS, ONE 25'-0" MBSGF PANEL IS ALSO ALLOWED IN ITS PLACE.
 - A DRIVING CAP WITH A TIMBER OR PLASTIC INSERT SHALL BE USED WHEN DRIVING POSTS 3-8 TO PREVENT DAMAGE TO THE GALVANIZING ON TOP OF THE POST. SPECIAL DRIVING CAP TO BE USED ON LOWER POSTS 1 & 2 TO PREVENT DAMAGE TO THE WELDED PLATES.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM NUMBERS
A	1	MSKT IMPACT HEAD	MS3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	SF1303
C	1	POST 1 - TOP (6" X 6" X 1/8" TUBE)	MTPHP1A
D	1	POST 1 - BOTTOM (6' W6X15)	MTPHP1B
E	1	POST 2 - ASSEMBLY TOP	UHP2A
F	1	POST 2 - ASSEMBLY BOTTOM (6' W6X9)	HP2B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770
K	1	GROUND STRUT	MS785
L	6	W6X9 OR W6X8.5 STEEL POST	P621
M	6	COMPOSITE BLOCKOUTS	CBSP-14
N	1	W-BEAM MGS RAIL SECTION (9'-4 1/2")	G12025
O	2	W-BEAM MGS RAIL SECTION (12'-6")	G1203A
P	6	WOOD BLOCKOUT 6" X 8" X 14"	P675
Q	1	W-BEAM MGS RAIL SECTION (25'-0")	G1209
SMALL HARDWARE			
a	2	5/8" x 1" HEX BOLT (GRD 5)	B5160104A
b	4	5/8" WASHER	W0516
c	2	5/8" HEX NUT	N0516
d	25	5/8" Dia. x 1 1/4" SPLICE BOLT (POST 2)	B580122
e	2	5/8" Dia. x 9" HEX BOLT (GRD A449)	B580904A
f	3	5/8" WASHER	W050
g	33	5/8" Dia. H.G.R NUT	N050
h	1	3/4" Dia. x 8 1/2" HEX BOLT (GRD A449)	B340854A
j	1	3/4" Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	1/2" x 1 1/4" A325 BOLT WITH CAPTIVE WASHER	SB12A
n	8	1/2" STRUCTURAL NUTS	N012A
o	8	1 1/8" O.D. x 3/8" I.D. STRUCTURAL WASHERS	W012A
p	1	BEARING PLATE RETAINER TIE	CT-100ST
q	6	5/8" x 10" H.G.R. BOLT	B581002
r	1	OBJECT MARKER 18" X 18"	E3151



ALTERNATIVE ITEMS NOT SHOWN. *
 * ITEM(P) 8" WOOD-BLOCKOUT
 ** ITEM(Q) 25' GUARD FENCE PANEL



NOTE: TXDOT GENERIC APPROACH GRADING LAYOUT USED FOR ALL TANGENT TYPE END TREATMENTS.


NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE MSKT END TERMINAL, IT IS NOT INTENDED TO REPLACE THE PRODUCT DESCRIPTION ASSEMBLY MANUAL.

Design Division Standard

SINGLE GUARDRAIL TERMINAL
MSKT-MASH-TL-3
SGT (12S) 31-18

FILE: sgt12s3118.dgn	DN: TXDOT	CK: KM	DW: VP	CK: CL
© TXDOT: APRIL 2018	CONT	SECT	JOB	HIGHWAY
REVISIONS				
DIST	COUNTY			RH
AUS	HAYS			SHEET NO. 32






DISCLAIMER: THE USE OF THIS STANDARD IS GOVERNED BY THE "TEXAS ENGINEERING PRACTICE ACT". NO WARRANTY OF ANY KIND IS MADE BY TXDOT FOR ANY PURPOSE WHATSOEVER. TXDOT ASSUMES NO RESPONSIBILITY FOR THE CONVERSION OF THIS STANDARD TO OTHER FORMATS OR FOR INCORRECT RESULTS OR DAMAGES RESULTING FROM ITS USE.



- GENERAL NOTES**
- FOR SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL GUIDANCE OF THE SYSTEM, CONTACT: SPIG INDUSTRY, INC. AT 1(267) 644-9510. 14675 INDUSTRIAL PARK RD; BRISTOL, VA 24202
 - FOR INSTALLATION, REPAIR AND MAINTENANCE REFER TO THE MANUFACTURER'S; SGET END TERMINAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL.
 - MANUFACTURER WILL APPLY HIGH INTENSITY REFLECTIVE SHEETING, "OBJECT MARKER" TO THE FACE PLATE OF THE DEVICE PER MANUFACTURER'S RECOMMENDATIONS. THE OBJECT MARKER SHALL CONFORM TO THE STANDARDS REQUIRED IN TEXAS MUTCD.
 - THE NOMINAL HEIGHT OF THE GUARDRAIL BEAM IS 31 INCHES WITH A TOLERANCE OF +/- ONE INCH.
 - FOR POST (LEAVE-OUT) INSTALLATION AND GUIDANCE SEE TXDOT'S LATEST ROADWAY MOW STRIP STANDARD.
 - (POST 2 THROUGH POST 8) ARE MODIFIED STEEL-YIELDING POSTS WITH YIELDING HOLES AT GROUND LEVEL. THERE ARE NO SUBSTITUTE POSTS.
 - POSTS SHALL NOT BE SET IN CONCRETE.
 - IF SOLID ROCK IS ENCOUNTERED FOR ANY OF THE POSTS IN THE SYSTEM, CONTACT THE MANUFACTURER FOR SPECIFIC INSTALLATION GUIDANCE.
 - HARDWARE (BOLTS, NUTS, & WASHERS) SHALL BE GALVANIZED IN ACCORDANCE WITH ITEM 445, "GALVANIZING". FITTINGS SHALL BE SUBSIDIARY TO THE BID ITEM.
 - A COMPOSITE MATERIAL BLOCKOUT THAT MEETS DMS-7210 REQUIREMENTS MAY BE SUBSTITUTED FOR AN APPROVED WOOD BLOCKOUT. SEE CONSTRUCTION DIVISION MATERIAL PRODUCER LIST (MPL) FOR CERTIFIED PRODUCERS.
 - THE ENTIRE SYSTEM MUST BE INSTALLED IN A STRAIGHT LINE WITHOUT ANY CURVE. HOWEVER, THE SYSTEM CAN BE OFFSET BY TWO FEET AS SHOWN ON THE APPROACH GRADING DETAIL TO HELP OFF-SET THE IMPACT HEAD FROM SHOULDER OF THE ROAD.

ITEM	QTY	MAIN SYSTEM COMPONENTS	ITEM #
A	1	SGET IMPACT HEAD	SIH1A
B	1	MODIFIED GUARDRAIL PANEL 12'-6"	126SPZGP
B2	1	MODIFIED GUARDRAIL PANEL 9'-4 1/2"	GP94
C	2	STANDARD GUARDRAIL PANEL 12'-6"	GP126
D	1	STANDARD GUARDRAIL PANEL 25'-0"	GP25
E	7	MODIFIED YIELDING I-BEAM POST W6x8.5	YP6MOD
F	6	COMPOSITE BLOCKOUT 6" X 8" X 14"	CBO8
G	6	WOOD BLOCKOUT 6" X 8" X 14"	WB08
H	1	STRUT 3" X 3" X 80" X 1/4" A36 ANGLE	STR80
I	1	FOUNDATION TUBE 6" X 8" X 72" X 3/16"	FNDT6
J	1	WOOD BREAKAWAY POST 5 1/2" X 7 1/2" X 50"	WBRK50
K	1	WOOD STRIKE BLOCK	WSBLK14
L	1	STRIKE PLATE 1/4" A36 BENT PLATE	SPLT8
M	1	REINFORCEMENT PLATE 12 GA. GR55	REPLT17
N	1	GUARDRAIL GRABBER 2 1/2" X 2 1/2" X 16 1/2"	GR17
O	1	BEARING PLATE 8" X 8 5/8" X 5/8" A36	BPLT8
P	1	PIPE SLEEVE 4 1/4" X 2 3/8" O.D. (2 1/8" I.D.)	PSLV4
Q	1	BCT CABLE 3/4" X 81" LENGTH	CBL81

ITEM	QTY	SMALL HARDWARE	ITEM #
a	1	5/8" X 12" GUARDRAIL BOLT 307A HDG	12GRBLT
b	7	5/8" X 10" GUARDRAIL BOLT 307A HDG	10GRBLT
c	33	5/8" X 1 1/4" GR SPLICE BOLTS 307A HDG	1GRBLT
d	3	5/8" FLAT WASHER F436 A325 HDG	58FW436
e	1	5/8" LOCK WASHER HDG	58LW
f	39	5/8" GUARDRAIL HEX NUT HDG	58HN563
g	2	1/2" X 2" STRUT BOLT A325 HDG	2BLT
h	6	1/2" X 1 1/4" PLATE BOLT A325 HDG	125BLT
i	16	1/2" FLAT WASHER F436 A325 HDG	12FWF436
j	8	1/2" LOCK WASHER HDG	12LW
k	8	1/2" HEX NUT A563 HDG	12HN563
l	4	3/8" X 3" HEX LAG SCREW GR5 HDG	38LS
m	4	3/8" FLAT WASHER F436 A325 HDG	38FW844
n	2	1" FLAT WASHER F436 A325 HDG	1FWF436
o	2	1" HEX NUT A563HDG	1HN563
p	1	18" TO 24" LONG ZIP TIE RATED 175-200LB	ZPT18
q	1	1 1/2" X 4" SCH-40 PVC PIPE	PSPCR4
r	1	RFID CHIP RATED MIL-STD-810F	RFID810F
s	1	IMPACT HEAD REFLECTIVE SHEETING	RS30M



NOTE: THIS STANDARD IS A BASIC REPRESENTATION OF THE SGET TERMINAL SYSTEM AND IS NOT INTENDED TO REPLACE THE MANUFACTURER'S ASSEMBLY MANUAL.

Texas Department of Transportation
Design Division Standard

SPIG INDUSTRY, LLC
SINGLE GUARDRAIL TERMINAL
SGET - TL-3 - MASH
SGT (15) 31-20

FILE: sg153120.dgn	DN: TXDOT	CK: KM	DW: VP	CK: VP
© TXDOT: APRIL 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS				
DIST	COUNTY	SHEET NO.		
AUS	HAYS			33

DATE: 10/4/2023
FILE: \$FILES

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH-EX_DRN-AREAMAP_01.dgn
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023 TIME: 8:15:00 AM SCALE: 1:200

H&H Summary Table (Existing Conditions)								
DA 1: Exist Shane Culvert	Area		Tc Min	Design Storm (yrs)				
	SQFT	AC		2	10	25	50	100
189,024	4.34	4.34	13.06	C Value				
				0.47	0.53	0.58	0.61	0.65
				Intensity (in/hr)				
				4.1	6.8	8.4	9.6	11.0
Q (cfs)								
				8.42	15.72	21.00	25.55	31.14



DA 2: Exist SET	Area		Tc Min	Design Storm (yrs)				
	SQFT	AC		2	10	25	50	100
282,281	6.48	6.48	10.65	C Value				
				0.38	0.44	0.48	0.51	0.55
				Intensity (in/hr)				
				4.14	6.77	8.37	9.64	10.97
Q (cfs)								
				10.06	19.16	25.89	31.71	39.00



LEGEND

- XX DRAINAGE AREA ID
- X.XX AC TOTAL AREA
- DRAINAGE AREA BOUNDARY
- FLOW ARROW
- -820- - EXIST CONTOURS
- 820- PROP CONTOURS
- PROPOSED CONSTRUCTION BY OTHERS

- NOTES:**
- HAYS COUNTY TECHNICAL CRITERIA AND CITY OF AUSTIN CRITERIA DRAINAGE MANUAL (DCM) WERE USED FOR ALL HYDRAULIC COMPUTATIONS
 - HY-8 WAS USED TO MODEL THE EXTENSION OF THE EXISTING SHANE LANE CROSS CULVERT. CHANGES RESULT IN A MINOR DECREASE TO THE HEADWATER ELEVATION.
 - THE DESIGN STORM FOR THIS PROJECT IS THE 25-YR STORM EVENT.



Felipe S. Tutud

NO.	DATE	REVISION	APPROVED

HDR

HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900

THE CITY OF
DRIPPING SPRINGS
 TEXAS © 2023

ROGER HANKS
 EXISTING DRAINAGE
 AREA MAP


SCALE: 1"=200'

SHEET 1 OF 2

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
				RH
GRAPHICS	STATE	DISTRICT	COUNTY	SHEET NO.
AT	TEXAS	AUS	HAYS	
CHECK	CONTROL	SECTION	JOB	
				34

PENTABLE: 10338078.tbl
 DATE: 10/04/2023 TIME: 8:15:06 AM SCALE: 1:200

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOINEZGONZ
 FILE: RH-PROP_DRN_AREAMAP_02.dgn



H&H Summary Table (Proposed Conditions)									
DA 1: Exist Shane Culvert	Area		Tc Min	Design Storm (yrs)					
	SQFT	AC		2	10	25	50	100	
189,024	4.34	4.34	13.06	C Value					
				0.47	0.53	0.58	0.61	0.65	
				Intensity (in/hr)					
				4.1	6.8	8.4	9.6	11.0	
				Q (cfs)					
				8.42	15.72	21.00	25.55	31.14	

DA 2: South PAZD	Area		Tc Min	Design Storm (yrs)					
	SQFT	AC		2	10	25	50	100	
116,004	2.66	2.66	6.95	C Value					
				0.43	0.50	0.54	0.57	0.61	
				Intensity (in/hr)					
				4.14	6.77	8.37	9.64	10.97	
				Q (cfs)					
				4.76	8.96	12.01	14.64	17.90	


DA 3: North PAZD	Area		Tc Min	Design Storm (yrs)					
	SQFT	AC		2	10	25	50	100	
166,843	3.83	3.83	9.80	C Value					
				0.43	0.49	0.53	0.56	0.61	
				Intensity (in/hr)					
				4.62	7.53	9.27	10.62	12.04	
				Q (cfs)					
				7.54	14.12	18.87	22.93	27.91	

LEGEND

- DRAINAGE AREA BOUNDARY
- FLOW ARROW
- 820- EXIST CONTOURS
- 820- PROP CONTOURS
- PROPOSED CONSTRUCTION BY OTHERS

--- DRAINAGE AREA ID
 XX
 X.XX AC --- TOTAL AREA

- NOTES:**
- HAYS COUNTY TECHNICAL CRITERIA AND CITY OF AUSTIN CRITERIA DRAINAGE MANUAL (DCM) WERE USED FOR ALL HYDRAULIC COMPUTATIONS
 - HY-8 WAS USED TO MODEL THE EXTENSION OF THE EXISTING SHANE LANE CROSS CULVERT. CHANGES RESULT IN A MINOR DECREASE TO THE HEADWATER ELEVATION.
 - THE DESIGN STORM FOR THIS PROJECT IS THE 25-YR STORM EVENT.



TSS Treatment Data	
HDR Required TSS (lbs)	115
KHA Extra TSS (lbs)	187

Impervious Cover			
Units	Existing	Proposed	Increase
SQFT	20,300	26,136	5,663
AC	0.47	0.60	0.13

WATER QUALITY NOTE:
 THIS PROJECT DOES NOT PROPOSE ANY BMPS. THE REQUIRED TSS TREATMENT FOR THE INCREASE IN IMPERVIOUS COVER WILL BE ACCOUNTED FOR IN THE ADJACENT ROGER HANKS PARKWAY EXTENSION PROJECT. THE ADJACENT PROJECT (EAPP =11003195; RN109124040) RECEIVED CZP APPROVAL ON OCTOBER 7TH, 2022, AND INCLUDES BMPS WITH MORE TREATMENT CAPACITY THAN REQUIRED ACCORDING TO THE CZP AND PLAN SET. THE EXTRA TREATMENT OF TSS FOR THE KHA PROJECT IS MORE THAN THE REQUIRED TSS FOR THIS PROJECT. A CZP EXCEPTION REQUEST STATING THIS IS TO BE SUBMITTED AT A FUTURE DATE.

NO.	DATE	REVISION	APPROVED

HDR
 HDR Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900

THE CITY OF DRIPPING SPRINGS TEXAS

ROGER HANKS




PROPOSED DRAINAGE AREA MAP

SCALE: 1"=200' SHEET 2 OF 2

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS				RH
AT	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK	TEXAS	AUS	HAYS	35
CHECK	CONTROL	SECTION	JOB	

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH-CULV01_EXTENSION.01.dgn

PENTABLE: 10338078.tbl
 DATE: 10/4/2023 TIME: 8:15:10 AM
 SCALE: 1:20



FELIPE S. TOLDT
 104836
 LICENSED PROFESSIONAL ENGINEER
 10/04/2023

NO.	DATE	REVISION	APPROVED

HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900

**THE CITY OF
 DRIPPING SPRINGS
 TEXAS**
 © 2023

ROGER HANKS

CULVERT 01 LAYOUT


SCALE: 1" = 10' - H
 1" = 5' - V

DESIGN	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS			RH
AT	STATE	DISTRICT	COUNTY
CHECK	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB


36

SHEET 1 OF 1

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOMEZGONZ
 FILE: RH-DRW-DETAIL01.dgn
 PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:22:14 AM
 SCALE: 1:1



PLAN/ELEVATION






SECTION A-A

PIPE COLLAR DETAIL
 FOR HORIZONTAL OR VERTICAL PLACEMENT
 N.T.S.

**PIPE COLLAR
 GENERAL NOTES**

1. THE CONTRACTOR SHALL TAKE STEPS TO ENSURE A SMOOTH JOINT ALONG THE INSIDE WALL OF PIPE.
2. ANY SPILLAGE OF CONCRETE THROUGH THE JOINT SHALL BE REMOVED AND THE INSIDE PIPE SURFACES SMOOTHED AS DIRECTED BY THE ENGINEER.
3. PIPE COLLARS WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED SUBSIDIARY TO ITEM 464.

 <i>Felipe Tutud</i>			
NO.	DATE	REVISION	APPROVED
			
HDR Firm Registration No. F-754 710 Hesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900			
 THE CITY OF DRIPPING SPRINGS TEXAS © 2023			
ROGER HANKS DRAINAGE DETAILS			
NTS SHEET 1 OF 1			
DESIGN FT	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.	HIGHWAY NO.
GRAPHICS LG	STATE	DISTRICT	COUNTY
CHECK	TEXAS	AUS	HAYS
CHECK	CONTROL	SECTION	JOB
			37

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:15:14 AM
 FILE: \$FILES\$

Size	MAX DEPTH = 15 ft. to top of BASE SLAB											MAX DEPTH = 25 ft. to top of BASE SLAB											Min Height (See Gen Note 3)	Max HOLE DIA (See Fab Note 2)	Max KO DIA (See Fab Note 2)
	Base Slab			Base Unit or Riser Walls			Below Grade Slab (w/PJB) Reducing Slab (w/PB)					Base Slab			Base Unit or Riser Walls			Below Grade Slab (w/PJB) Reducing Slab (w/PB)							
	Short Span Reinf. Steel Area	Long Span Reinf. Steel Area	Thickness	Short Span Reinf. Steel Area	Long Span Reinf. Steel Area	Thickness	Reduced Riser Size or ID	Short Span Reinf. Steel Area	Long Span Reinf. Steel Area	Thickness	Short Span Reinf. Steel Area	Long Span Reinf. Steel Area	Thickness	Short Span Reinf. Steel Area	Long Span Reinf. Steel Area	Thickness	Reduced Riser Size or ID	Short Span Reinf. Steel Area	Long Span Reinf. Steel Area	Thickness	Reduced Riser Size or ID	Short Span Reinf. Steel Area			
X x Y	Ashort	Along	BS	Bshort	Blong	W	RWSxRWL or ID	Dshort	Dlong	TS	Ashort	Along	BS	Bshort	Blong	W	RWSxRWL or ID	Dshort	Dlong	TS	BH MIN	HOLE DIA	KO DIA		
ft.	in ² /ft	in ² /ft	in.	in ² /ft	in ² /ft	in.	ft. **	in ² /ft	in ² /ft	in.	in ² /ft	in ² /ft	in.	in ² /ft	in ² /ft	in.	ft. **	in ² /ft	in ² /ft	in.	ft.	in.	in.		
Precast Junction Box (PJB)	3x3	0.23	0.23	6	0.19	0.19	6	N/A	0.37	0.37	9	0.29	0.29	6	0.24	0.24	6	N/A	0.37	0.37	9	3.5	36	36	
	4x4	0.29	0.29	6	0.24	0.24	6	N/A	0.41	0.41	9	0.47	0.47	6	0.38	0.38	6	N/A	0.41	0.41	9	4.5	48	48	
	3x5	0.29	0.18	6	0.19	0.35	6	N/A	0.48	0.48	9	0.39	0.18	6	0.23	0.59	6	N/A	0.48	0.48	9	3.5	36/60	36/60	
	4x5	0.36	0.18	6	0.22	0.34	6	N/A	0.42	0.42	9	0.53	0.26	6	0.39	0.59	6	N/A	0.42	0.42	9	4.5	48/60	48/60	
	5x5	0.36	0.36	6	0.34	0.34	6	N/A	0.43	0.43	9	0.62	0.62	6	0.59	0.59	6	N/A	0.43	0.43	9	5.5	60	60	
	5x6	0.27	0.27	9	0.34	0.45	6	N/A	0.48	0.48	9	0.47	0.45	9	0.38	0.54	8	N/A	0.48	0.48	9	5.5	60/72	60/72	
	6x6	0.27	0.27	9	0.45	0.45	6	N/A	0.56	0.56	9	0.52	0.52	9	0.54	0.54	8	N/A	0.56	0.56	9	6.5	72	72	
	8x8	0.46	0.46	9	0.51	0.51	8	N/A	0.45	0.45	12	0.87	0.87	9	0.59	0.59	10	N/A	0.45	0.45	12	8.5	96	72	
Precast Base (PB)	3x3	0.23	0.23	6	0.19	0.19	6	N/A	N/A	N/A	N/A	0.29	0.29	6	0.24	0.24	6	N/A	N/A	N/A	N/A	3.5	36	36	
	4x4	0.29	0.29	6	0.24	0.24	6	N/A	N/A	N/A	N/A	0.47	0.47	6	0.38	0.38	6	N/A	N/A	N/A	N/A	4.5	48	48	
	3x5	0.29	0.18	6	0.19	0.35	6	3x3	0.30	0.34	9	0.39	0.18	6	0.23	0.59	6	3x3	0.40	0.40	9	3.5	36/60	36/60	
	4x5	0.36	0.18	6	0.22	0.34	6	3x3	0.30	0.30	9	0.53	0.26	6	0.39	0.59	6	3x3	0.46	0.37	9	4.5	48/60	48/60	
	4x5	0.36	0.18	6	0.22	0.34	6	4x4	0.30	0.30	9	0.53	0.26	6	0.39	0.59	6	4x4	0.39	0.39	9	4.5	48/60	48/60	
	4x5	0.36	0.18	6	0.22	0.34	6	48"	0.39	0.39	9	0.53	0.26	6	0.39	0.59	6	48"	0.47	0.47	9	4.5	48/60	48/60	
	4x5	0.36	0.18	6	0.22	0.34	6	3x5	0.33	0.40	9	0.53	0.26	6	0.39	0.59	6	3x5	0.48	0.48	9	4.5	48/60	48/60	
	5x5	0.36	0.36	6	0.34	0.34	6	3x3	0.34	0.34	9	0.62	0.62	6	0.59	0.59	6	3x3	0.53	0.53	9	5.5	60	60	
	5x5	0.36	0.36	6	0.34	0.34	6	4x4	0.36	0.36	9	0.62	0.62	6	0.59	0.59	6	4x4	0.64	0.64	9	5.5	60	60	
	5x5	0.38	0.38	6	0.34	0.34	6	48"	0.36	0.36	9	0.62	0.62	6	0.59	0.59	6	48"	0.64	0.64	9	5.5	60	60	
	5x5	0.36	0.36	6	0.34	0.34	6	3x5	0.34	0.40	9	0.62	0.62	6	0.59	0.59	6	3x5	0.53	0.53	9	5.5	60	60	
	5x6	0.31	0.31	9	0.34	0.45	6	3x3	0.34	0.34	9	0.47	0.45	9	0.38	0.54	8	3x3	0.61	0.50	9	5.5	60/72	60/72	
	5x6	0.27	0.27	9	0.34	0.45	6	4x4	0.36	0.45	9	0.47	0.45	9	0.38	0.54	8	4x4	0.74	0.57	9	5.5	60/72	60/72	
	5x6	0.29	0.29	9	0.34	0.45	6	48"	0.36	0.45	9	0.47	0.45	9	0.38	0.54	8	48"	0.74	0.57	9	5.5	60/72	60/72	
	5x6	0.29	0.29	9	0.34	0.45	6	3x5	0.45	0.45	9	0.47	0.45	9	0.38	0.54	8	3x5	0.61	0.61	9	5.5	60/72	60/72	
	6x6	0.29	0.29	9	0.45	0.45	6	3x3	0.41	0.41	9	0.52	0.52	9	0.54	0.54	8	3x3	0.74	0.74	9	6.5	72	72	
	6x6	0.27	0.27	9	0.45	0.45	6	4x4	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	4x4	0.87	0.87	9	6.5	72	72	
	6x6	0.29	0.29	9	0.45	0.45	6	48"	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	48"	0.87	0.87	9	6.5	72	72	
	6x6	0.29	0.29	9	0.45	0.45	6	3x5	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	3x5	0.87	0.87	9	6.5	72	72	
	8x8	0.52	0.52	9	0.51	0.51	8	3x3	0.61	0.61	12	0.91	0.91	9	0.70	0.70	10	3x3	0.85	0.85	12	8.5	96	72	
8x8	0.52	0.52	9	0.51	0.51	8	4x4	0.70	0.70	12	0.87	0.87	9	0.70	0.70	10	4x4	1.01	1.01	12	8.5	96	72		
8x8	0.52	0.52	9	0.51	0.51	8	48"	0.70	0.70	12	0.87	0.87	9	0.70	0.70	10	48"	1.01	1.01	12	8.5	96	72		
8x8	0.52	0.52	9	0.51	0.51	8	3x5	0.70	0.85	12	0.87	0.87	9	0.70	0.70	10	3x5	1.01	1.01	12	8.5	96	72		

** Unless otherwise indicated.

FABRICATION NOTES:

- Maximum spacing of reinforcement is 8".
- At manufacturer's option, provide cast or cored holes or thin wall panels (KO) to the maximum diameter shown for each. When no penetration is required, it is acceptable to provide a wall with no sectional reduction.

GENERAL NOTES:

- Precast Junction Box consists of base slab, base unit, risers (as required), and below grade slab. See sheet PJB for details.
- Precast Base consists of base slab, base unit, risers (as required), reducing slab (as required), and reduced risers (as required). See sheet PB for details.
- Min Height shown is for stock base units. Use stock base units whenever practical. Smaller height base units can be used in special installation circumstances, when noted elsewhere in the plans. Absolute minimum height of base units is 2'-6".

HL93 LOADING








**DESIGN DATA FOR
PRECAST BASE AND
JUNCTION BOX**

PDD

FILE: prest10-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS				RH
DIST	COUNTY			SHEET NO.
AUS	HAYS			38

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:15:16 AM
FILE: \$FILES\$



FABRICATION NOTES:

1. Provide Class "H" concrete in accordance with Item 421 and having a minimum compressive strength of 5,000 psi.
2. Provide Grade 60 reinforcing steel or equivalent area of WWR.
3. Provide typical clear cover of 1 1/2" to reinforcing steel at interior or exterior walls.
4. Walls or slabs with a thickness of 8" or greater require shrinkage and temperature reinforcing steel. Provide steel area = 0.11 in²/ft each way.
5. No substitution is allowed for vertical and horizontal #4 bars in corners.
6. Manufacture base and risers to nearest 3" increment.
7. Design tongue and groove joints for full closure on both shoulders. Minimum spigot depth is 3/4".
8. Provide lifting devices in conformance with Manufacturer's recommendations.
9. See sheet PDD for sizes, dimensions, and reinforcing steel not shown.

INSTALLATION NOTES:

1. If required elsewhere. Inverts (benching) to be provided by Contractor. Concrete or mortar used for invert is subsidiary to specified inlet or manhole.
2. Seal tongue and groove joints with preformed or bulk mastic in conformance with Manufacturer's recommendations. Tongue and groove joints may be grouted no more than 1" between each section, or 1/2 the joint depth, whichever is greater.
3. Do not grout rubber gasket joints without Manufacturer's recommendation.
4. For rigid pipe, cut hole in thin wall panel (KO) 4" Max, 2" Min larger than pipe OD.
5. For flexible pipe, consult boot/seal Manufacturer's specification for placement tolerance and hole size. Center pipe in hole and install boot/seal per Manufacturer's specification.


GENERAL NOTES:

1. Precast Base consists of base slab, base unit, risers (as required), reducing slab (as required), and reduced risers (as required). See sheet PDD for sizes.
2. Designed according to ASTM C913.
3. Payment for precast base is subsidiary to the specified inlet, per Item 465, "Junction Boxes, Manholes, and Inlets."


Cover dimensions are clear dimensions, unless noted otherwise.

HL93 LOADING				 Texas Department of Transportation Bridge Division Standard
PRECAST BASE				
PB				
FILE: prest01-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
©TxDOT February 2020		CONTRACT	SECTION	HIGHWAY
REVISIONS				RH
DIST	COUNTY			SHEET NO.
AUS	HAYS			39


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PRECAST ROUND MANHOLE (PRM) WITH THROUGH-HOLE
 PRECAST BASE (PB) OR PRECAST JUNCTION BOX (PJB) WITH THIN-WALL KNOCK-OUT
TYPICAL HALF PLAN




PRECAST ROUND MANHOLE (PRM) WITH THROUGH-HOLE
 PRECAST BASE (PB) OR PRECAST JUNCTION BOX (PJB) WITH THIN-WALL KNOCK-OUT
TYPICAL HALF PLAN



PRECAST ROUND MANHOLE (PRM) WITH THROUGH-HOLE
 PRECAST BASE (PB) OR PRECAST JUNCTION BOX (PJB) WITH THIN-WALL KNOCK-OUT
TYPICAL HALF ELEVATION



PRECAST ROUND MANHOLE (PRM) WITH THROUGH-HOLE
 PRECAST BASE (PB) OR PRECAST JUNCTION BOX (PJB) WITH THIN-WALL KNOCK-OUT
TYPICAL HALF ELEVATION



TYPICAL PARTIAL ELEVATION OF PRECAST SAFETY END TREATMENTS
 Showing square PSET for parallel drainage, cross drainage shown similar.

① Completely fill the void between the precast structure and the connecting pipe or box with cementitious grouts and mortars in accordance with DMS-4675 "Cementitious Grouts and Mortars for Miscellaneous Application".

CONSTRUCTION NOTES:
 Do not grout rubber gasket joints without Manufacturer's recommendations.
 Do not use bricks, masonry blocks, native stone, or similar materials in conjunction with grouted connections when filling void spaces around pipes or box culverts.

MATERIAL NOTES:
 Provide grouted connections in accordance with DMS-4675 "Cementitious Grouts and Mortars for Miscellaneous Application".


GENERAL NOTES:
 See applicable standards for notes and details not shown:
 Precast Base (PB)
 Precast Junction Box (PJB)
 Precast Round Manhole (PRM)
 Precast Safety End Treatments C/D Square (PSET-SC)
 Precast Safety End Treatments P/D Square (PSET-SP)
 Provide Concrete Box Culverts in accordance with Item 462 "Concrete Box Culverts and Drains".
 Provide Reinforced Concrete Pipe (RCP) in accordance with Item 464 "Reinforced Concrete Pipe".
 Provide Thermoplastic Pipe (TP) in accordance with Special Specification Thermoplastic Pipe.
 Payment for grouted connections is considered subsidiary to other bid items.

DATE: 10/4/2023 8:15:22 AM
 FILE: \$FILES\$


				Bridge Division Standard	
PIPE AND BOX GROUTED CONNECTIONS FOR PRECAST STRUCTURES					
PBGC					
FILE: pbgstd1-20.dgn	DN: TxDOT	CK: TAR	DW: JTR	CK: TAR	
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY	
REVISIONS					RH
DIST	COUNTY			SHEET NO.	
AUS	HAYS				40

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:15:24 AM
FILE: \$FILES




PLAN VIEW ~ STYLE 'FG'




ELEVATION VIEW WITHOUT FORMED SIDE




ELEVATION VIEW WITH FORMED SIDE




SECTION A-A ~ BS1




SECTION A-A ~ BS2



SECTION A-A ~ BS3



TYPICAL CORNER REINFORCING PLAN DETAIL
Showing BS2 other beam sections similar.



BARS U (#3)
Showing one complete bar.

- ① Matches inside face of wall of precast base or riser below inlet.
- ② Construct cast-in-place reinforced concrete with or without formed side. Place formed side/sides as directed elsewhere in the plans. Formed sides may only be used on sides parallel to traffic. Use Class "C" concrete. Apron and formed side reinforcing not shown for clarity. Apron and formed side are subsidiary to PAZD-CZ. Apron is 2'-0" width around precast zone drain, unless an optional formed side is used. For apron and formed side, provide (#4) reinforcing at 12" O.C.
- ③ Top slab reinforcing not shown for clarity.
- ④ Top slab reinforcing and post reinforcing not shown for clarity.

FABRICATION NOTES:

1. Provide Class "H" concrete in accordance with Item 421 and having a minimum compressive strength of 5,000 psi.
2. Provide Grade 60 reinforcing steel or equivalent area of WWR.
3. Provide clear cover of 3/4" to reinforcing from bottom of slab and 2" to reinforcing from top of slab for structural reinforcement.
4. Provide 1 1/2" end cover on (#5) reinforcing.
5. Design tongue and groove joints for full closure on both shoulders. Minimum spigot depth is 3/4".
6. Provide lifting devices in conformance with Manufacturer's recommendations.

INSTALLATION NOTES:

1. Precast Area Zone Drain within Clear Zone (PAZD-CZ) is for use in ditches and medians outside and inside of the horizontal clearance (clear zone). PAZD-CZ is never placed in the roadway.
2. Seal tongue and groove joints with preformed or bulk mastic in conformance with Manufacturer's recommendations. Tongue and groove joints may be grouted no more than 1" between each section, or 1/2 the joint depth, whichever is greater.
3. Do not grout rubber gasket joints without Manufacturer's recommendation.

GENERAL NOTES:

1. Designed according to ASTM C913.
2. Payment for inlet is per Item 465, "Junction Boxes, Manholes, and Inlets" by type, style, size, and opening size (when applicable).

Cover dimensions are clear dimensions, unless noted otherwise.
Reinforcing bar dimensions shown are out-to-out of bar.

Style	Size (X x Y)	A x A *	B x B	Beam Section
FG	3'x3'	3'x3'	1.5'x1.5'	BS1
FG	4'x4'	3'x3'	2'x2'	BS2
FG	4'x4'	4'x4'	2'x2'	BS1
FG	5'x5'	3'x3'	2.5'x2.5'	BS3
FG	5'x5'	4'x4'	2.5'x2.5'	BS2


*Nominal frame/grate size.

HL93 LOADING

		Bridge Division Standard	
<h2>PRECAST AREA ZONE DRAIN WITHIN CLEAR ZONE</h2>			
<h3>PAZD-CZ</h3>			
FILE: prest015-20.dgn	DN: SDC	CK: TAR	DW: JTR
©TxDOT February 2020	CONTRACT	SECTION	JOB
REVISIONS			HIGHWAY
			RH
DIST	COUNTY	SHEET NO.	
AUS	HAYS	41	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:15:26 AM
 FILE: \$FILES\$



NOTE: All pipe runners, calculations, and dimensions are based on the pipe culverts mitered as shown in this detail. Alternate styles of mitered ends will require that appropriate adjustments be made to the values presented on this standard.


SIDE ELEVATION OF TYPICAL PIPE CULVERT MITER

(Showing corrugated metal pipe (CMP) culvert. Details of reinforced concrete pipe (RCP) culvert are similar.)



SIDE ELEVATION OF CAST-IN-PLACE CONCRETE

(Showing reinforced concrete pipe (RCP) culvert. Details of corrugated metal pipe (CMP) culvert are similar. Pipe runners not shown for clarity)



ISOMETRIC VIEW OF TYPICAL INSTALLATION

(Showing installation with no skew.)

CROSS PIPE LENGTHS AND PIPE RUNNER LENGTHS ① ②

Nominal Culvert I.D.	Pipe Culvert Spa ~ G	Cross Pipe Length	Pipe Runner Length											
			3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
			0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
24"	1' - 7"	3' - 5"	N/A	N/A	N/A	5' - 10"	N/A	N/A	N/A	8' - 1"	N/A	N/A	N/A	12' - 9"
27"	1' - 8"	3' - 8"	N/A	N/A	5' - 5"	6' - 11"	N/A	N/A	N/A	7' - 7"	N/A	N/A	11' - 11"	14' - 11"
30"	1' - 10"	3' - 11"	N/A	N/A	6' - 4"	8' - 0"	N/A	N/A	N/A	8' - 9"	N/A	N/A	13' - 8"	17' - 0"
33"	1' - 11"	4' - 2"	6' - 2"	6' - 5"	7' - 3"	9' - 1"	8' - 6"	8' - 10"	10' - 0"	12' - 5"	13' - 3"	13' - 9"	15' - 5"	19' - 2"
36"	2' - 1"	4' - 5"	6' - 11"	7' - 3"	8' - 2"	10' - 2"	9' - 6"	9' - 11"	11' - 2"	13' - 10"	14' - 9"	15' - 3"	17' - 2"	21' - 3"
42"	2' - 4"	4' - 11"	8' - 6"	8' - 10"	9' - 11"	12' - 4"	11' - 7"	12' - 0"	13' - 6"	16' - 8"	17' - 9"	18' - 5"	20' - 8"	25' - 7"
48"	2' - 7"	5' - 5"	10' - 1"	10' - 5"	11' - 9"	N/A	13' - 7"	14' - 2"	15' - 10"	N/A	20' - 9"	21' - 6"	24' - 2"	N/A
54"	3' - 0"	5' - 11"	11' - 8"	12' - 1"	N/A	N/A	15' - 8"	16' - 3"	N/A	N/A	23' - 10"	24' - 8"	N/A	N/A
60"	3' - 3"	6' - 5"	13' - 3"	N/A	N/A	N/A	17' - 9"	N/A	N/A	N/A	26' - 10"	N/A	N/A	N/A

TYPICAL PIPE CULVERT MITERS ③

Side Slope	0° Skew	15° Skew	30° Skew	45° Skew
3:1	3:1	3.106:1	3.464:1	4.243:1
4:1	4:1	4.141:1	4.619:1	5.657:1
6:1	6:1	6.212:1	6.928:1	8.485:1

CONDITIONS WHERE PIPE RUNNERS ARE NOT REQUIRED ②

Nominal Culvert I.D.	Single Pipe Culvert	Multiple Pipe Culverts
12" thru 21"	Skews thru 45°	Skews thru 45°
24"	Skews thru 45°	Skews thru 30°
27"	Skews thru 30°	Skews thru 15°
30"	Skews thru 15°	Skews thru 15°
33"	Skews thru 15°	Always required
36"	Normal (no skew)	Always required
42" thru 60"	Always required	Always required

STANDARD PIPE SIZES AND MAX PIPE RUNNER LENGTHS ①

Pipe Size	Pipe O.D.	Pipe I.D.	Max Pipe Runner Length
2" STD	2.375"	2.067"	N/A
3" STD	3.500"	3.068"	10' - 0"
4" STD	4.500"	4.026"	19' - 8"
5" STD	5.563"	5.047"	34' - 2"

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY) ⑤

Nominal Culvert I.D.	3:1 Side Slope				4:1 Side Slope				6:1 Side Slope			
	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew	0° Skew	15° Skew	30° Skew	45° Skew
12"	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.6	0.7	0.7	0.7	0.8
15"	0.5	0.5	0.5	0.6	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9
18"	0.5	0.5	0.6	0.6	0.6	0.7	0.7	0.8	0.8	0.8	0.9	1.0
21"	0.6	0.6	0.6	0.7	0.7	0.7	0.8	0.9	0.9	0.9	1.0	1.2
24"	0.6	0.7	0.7	0.8	0.8	0.8	0.8	1.0	1.0	1.0	1.1	1.3
27"	0.7	0.7	0.8	0.9	0.8	0.9	0.9	1.1	1.1	1.1	1.2	1.4
30"	0.8	0.8	0.8	0.9	0.9	0.9	1.0	1.2	1.2	1.2	1.3	1.6
33"	0.8	0.8	0.9	1.0	1.0	1.0	1.1	1.3	1.3	1.4	1.5	1.7
36"	0.9	0.9	0.9	1.1	1.1	1.1	1.2	1.4	1.4	1.5	1.6	1.8
42"	1.0	1.0	1.1	1.3	1.2	1.3	1.3	1.6	1.6	1.7	1.8	2.1
48"	1.1	1.1	1.2	N/A	1.4	1.4	1.5	N/A	1.9	1.9	2.1	N/A
54"	1.3	1.3	N/A	N/A	1.6	1.6	N/A	N/A	2.1	2.1	N/A	N/A
60"	1.4	N/A	N/A	N/A	1.7	N/A	N/A	N/A	2.3	N/A	N/A	N/A

① Provide pipe runner of the size shown in the tables. Provide cross pipe of the same size as the pipe runner. Provide cross pipe stub out and bottom anchor pipe of the next smaller size pipe as shown in the Standard Pipe Sizes and Max Pipe Runner Lengths table.

② This standard allows for the placement of only one pipe runner across each culvert pipe opening. In order to limit the clear opening to be traversed by an errant vehicle, the following conditions must be met:

For 60" culvert pipes, the skew must not exceed 0°.
 For 54" culvert pipes, the skew must not exceed 15°.
 For 48" culvert pipes, the skew must not exceed 30°.
 For all culvert pipe sizes 42" and less, the skew must not exceed 45°.

If the above conditions cannot be met, the designer should consider using a safety end treatment with flared wings. For further information, refer to the TxDOT Roadway Design Manual.

③ Miter = slope of mitered end of pipe culvert.

④ Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".

⑤ Quantities shown are for one end of one reinforced concrete pipe (RCP) culvert. For multiple pipe culverts or for corrugated metal pipe (CMP) culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only.

SHEET 1 OF 2




SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE

SETP-CD


FILE: setpcdse-20.dgn	DN: GAF	CK: CAT	DW: JRP	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS				RH
	DIST	COUNTY		SHEET NO.
	AUS	HAYS		42

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:15:27 AM
FILE: \$FILES




OPTION A1 **OPTION A2**
CROSS PIPE AND CONNECTIONS DETAILS



SIDE ELEVATION OF SAFETY END TREATMENT INSTALLATION
(Showing pipe runner with Cross Pipe Connection Option A1 and Anchor Pipe Option B2 on corrugated metal pipe (CMP) culvert. Reinforced concrete pipe culvert (RCP) details are similar. Riprap not shown for clarity.)




PLAN OF SKEWED INSTALLATION




NOTE: The separate pipe runner shown is required when Cross Pipe Connection Option A1 is used.

PIPE RUNNER DETAILS




OPTION B1 **OPTION B2**
BOTTOM ANCHOR PIPE DETAILS (10)




OPTION B1 **OPTION B2**
BOTTOM ANCHOR TOEWALL DETAILS

(Culvert and riprap not shown for clarity.)



SHOWING CROSS PIPE AND ANCHOR TOEWALL



SHOWING TYPICAL PIPE CULVERT AND RIPRAP

SECTION A-A

- (4) Riprap placed beyond the limits shown will be paid for as concrete riprap in accordance with Item 432, "Riprap".
- (6) Recommended values of side slope are 3:1, 4:1, and 6:1. All quantities, calculations, and dimensions shown herein are based on these recommended values. Slope of 3:1 or flatter is required for vehicle safety.
- (7) Note that actual slope of pipe runner may vary slightly from side slope of riprap and trimmed culvert pipe edge.
- (8) Ensure that riprap concrete does not flow into the cross pipe so as to permit disassembly of the bolted connection to allow cleanout access.
- (9) After installation, inspect the 1/2 inch hole to ensure that the lap of the pipe runner with the bottom anchor pipe is adequate.
- (10) At fabricator's option, a heat bend to a smooth 5 inch radius or a manufactured elbow (of the same material as the runner) may be substituted for the mitered and welded joint in the bottom anchor pipe.

MATERIAL NOTES:
Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
Provide pipe runners, cross pipes, and anchor pipes conforming to the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.
Provide ASTM A307 bolts and nuts.
Galvanize all steel components, except concrete reinforcing, after fabrication.
Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:
Pipe runners are designed for a traversing load of 1,800 pounds at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.
Safety end treatments (SET) shown herein are intended for use in those installations where out of control vehicles are likely to traverse the openings approximately perpendicular to the pipe runners.
Payment for riprap and toewall is included in the price bid for each safety end treatment.
Construct concrete riprap and all necessary inverts in accordance with the requirements of Item 432, "Riprap".

SHEET 2 OF 2

		Bridge Division Standard	
SAFETY END TREATMENT FOR 12" DIA TO 60" DIA PIPE CULVERTS TYPE II ~ CROSS DRAINAGE			
SETP-CD			
FILE: setpcdse-20.dgn	DN: GAF	CK: CAT	DW: JRP
©TxDOT February 2020	CON: SECT	JOB	HIGHWAY
REVISIONS			RH
DIST	COUNTY	SHEET NO.	
AUS	HAYS	43	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:15:29 AM
 FILE: \$FILES\$

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	RCP Wall "B" Thickness	TP Wall Thickness (8)	"D" (1)	Slope	Min Length of Unit	Single Pipe		Multiple Pipes	
						Skew	Pipe Runners Required	Skew	Pipe Runners Required
12"	2"	1.15"	17.00"	3:1	2' - 11"	≤ 45°	No	≤ 45°	No
				4:1	3' - 6"				
				6:1	4' - 9"				
15"	2 1/4"	1.30"	20.50"	3:1	3' - 8"	≤ 45°	No	≤ 45°	No
				4:1	4' - 7"				
				6:1	6' - 5"				
18"	2 1/2"	1.60"	24.00"	3:1	4' - 6"	≤ 45°	No	≤ 45°	No
				4:1	5' - 8"				
				6:1	8' - 0"				
24"	3"	1.95"	31.00"	3:1	6' - 2"	≤ 45°	No	= 30°	No
				4:1	7' - 10"				
				6:1	11' - 3"				
30"	3 1/2"	2.65"	38.50"	3:1	7' - 10"	= 15°	No	= 15°	No
				4:1	10' - 1"				
				6:1	14' - 8"				
36"	4"	2.75"	45.50"	3:1	9' - 5"	= 0°	No	= 0°	Yes
				4:1	12' - 3"				
				6:1	17' - 11"				
42"	4 1/2"	2.7"	52.50"	3:1	11' - 1"	≥ 0°	Yes	≥ 0°	Yes
				4:1	14' - 5"				
				6:1	21' - 2"				


SAFETY PIPE RUNNER DIMENSIONS

Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"




PLAN

(Showing bell end connection.)




LONGITUDINAL ELEVATION

(Showing bell end connection.)




END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS

(If required)



OPTIONAL JOINT FOR RCP

(Showing joint between RCP and precast safety end treatment)




OPTION A


DETAIL A

(If required)

OPTION B




MULTIPLE PIPE INSTALLATION




OPTION WITH SQUARE BOTTOM

SECTION A-A



OPTION WITH INVERT BOTTOM



INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS

(If required)

- 1 Dimension "D" is based on reinforced concrete pipe (RCP) meeting the requirements of ASTM C-76, Class III, (RCP Wall "B" thickness). Adjust "D" for any other wall thickness used. For thermoplastic pipe (TP) take into account the annular space requirements for grouted connections.
- 2 Slope as shown elsewhere in plans. Slope of 3:1 or flatter is required for vehicle safety.
- 3 Toewall to be used only when dimension is shown elsewhere in the plans.
- 4 Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap is considered subsidiary to the Item 467, "Safety End Treatment".
- 5 Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.
- 6 Measured along slope.
- 7 Provide cement stabilized bedding and backfill in accordance with the Item 400, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item 467, "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- 8 Thermoplastic pipe wall thickness may vary. Adjust accordingly. Thermoplastic pipe requires the safety end treatments to have a bell end for grouted connections.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (RCP), and thermoplastic pipe (TP) may be used for TYPE II end treatment as specified in Item "Safety End Treatment".

When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.

Manufacture this product in accordance with Item 467, "Safety End Treatment" except as noted below:

- A. Provide minimum reinforcing of #4 at 6" (Grade 40) or #4 at 9" (Grade 60) each way or 6"x6" - D12 x D12 or 5"x5" - D10 x D10 welded wire reinforcement (WWR).
- B. For precast (steel formed) sections, provide Class "C" concrete (f'c = 3,600 psi).

At the option and expense of the Contractor, the next larger size of safety end treatment may be furnished as long as the "D" dimension cast is that of the required size of pipe.

Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.

Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Grade B), ASTM A500 (Grade B), or API 5LX52.

Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

Connect RCP using the Optional Joint for RCP detail shown or in accordance with Item 464 "Reinforced Concrete Pipe". Connect TP by grouting. See Pipe and Box Grouted Connections (PBG) standard for grouted connections with TP and precast safety end treatment.


PRECAST SAFETY END TREATMENT TYPE II ~ CROSS DRAINAGE

PSET-SC


FILE: psetscss-21.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONV	SECT	JOB	HIGHWAY
REVISIONS				RH
12-21: Added 42" TP				
DIST	COUNTY			SHEET NO.
AUS	HAYS			44

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:15:32 AM
FILE: \$FILES




PLAN VIEW
(Showing spigot end connection.)




LONGITUDINAL ELEVATION
(Showing spigot end connection.)




END DETAIL FOR INSTALLATION OF SAFETY PIPE RUNNERS
(If required)




INSTALLATION DETAIL FOR SAFETY PIPE RUNNERS
(If required)




OPTION A



OPTION B



SECTION A-A



MULTIPLE PIPE INSTALLATION

MAX SAFETY PIPE RUNNER LENGTHS AND REQUIRED SAFETY PIPE RUNNER SIZES

Max Safety Pipe Runner Length	Required Pipe Runner Size		
	Pipe Size	Pipe O.D.	Pipe I.D.
11' - 2"	3" STD	3.500"	3.068"
15' - 6"	3 1/2" STD	4.000"	3.548"
20' - 10"	4" STD	4.500"	4.026"
35' - 4"	5" STD	5.563"	5.047"

- Slope as shown elsewhere in the plans. Slope of 3:1 or flatter is required for vehicle safety.
- Provide cement stabilized bedding and backfill in accordance with the Item, "Excavation and Backfill for Structures". Bedding and backfill is considered subsidiary to the Item "Safety End Treatment". When concrete riprap is specified around the safety end treatment, backfill as directed by Engineer.
- Fill the top 4" of void between precast end treatments with concrete riprap. Concrete riprap be considered subsidiary to the Item "Safety End Treatment".
- Adjust clear distance between pipes to provide for the minimum distance between safety end treatments.

REQUIREMENTS FOR CULVERT PIPES AND SAFETY PIPE RUNNERS

Pipe I.D.	Min Wall Thickness	Min O.D.	Min O.D. at Tapered End	Min Reinf Requirements (sq. in. / ft. of pipe)	Slope	Minimum Length of Unit	Single Pipe		Multiple Pipe		
							Skew	Pipe Runners Required	Skew	Pipe Runners Required	
12"	2"	16"	16"	0.07 Circ.	3:1	2' - 0"	≤ 45°	No	≤ 45°	No	
						4:1					2' - 8"
						6:1					4' - 0"
15"	2 1/4"	19 1/2"	19"	0.07 Circ.	3:1	2' - 10"	≤ 45°	No	≤ 45°	No	
						4:1					3' - 9"
						6:1					5' - 8"
18"	2 1/2"	23"	21 1/2"	0.07 Circ.	3:1	3' - 8"	≤ 45°	No	≤ 45°	No	
						4:1					4' - 10"
						6:1					7' - 3"
24"	3"	30"	27"	0.07 Circ.	3:1	5' - 3"	≤ 45°	No	≤ 30°	No	
						4:1			7' - 0"	> 30°	Yes
						6:1			10' - 6"		
30"	3 1/2"	37"	31"	0.18 Circ.	3:1	6' - 3"	≤ 15°	No	≤ 15°	No	
						4:1			8' - 2"	> 15°	Yes
						6:1			12' - 1"		
36"	4"	44"	36"	0.19 Ellip.	3:1	7' - 10"	= 0°	No	≥ 0°	No	
						4:1			10' - 4"	> 0°	Yes
						6:1			15' - 4"		
42"	4 1/2"	51"	41 1/2"	0.23 Ellip.	3:1	9' - 6"	≥ 0°	Yes	≥ 0°	Yes	
						4:1			12' - 6"		
						6:1			18' - 7"		

MATERIAL NOTES:

Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise.
Provide safety pipe runners, cross pipes, pipe support posts, and pipe stubs meeting the requirements of ASTM A53 (Type E or S, Gr B), ASTM A500 Gr B, or API 5LX52.
Galvanize all steel components except reinforcing steel after fabrication. Repair galvanizing damaged during transport or construction in accordance with the specifications.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe (CRP) may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".
When precast safety end treatment is used as a Contractor's alternate to mitered RCP, riprap will not be required unless noted otherwise on the plans.
Manufacture precast concrete end sections in accordance with Item 464, "Reinforced Concrete Pipe" and in accordance with ASTM Specification C-76, Class III, Wall B for circular pipe.
Provide precast concrete end sections with a spigot or bell end for compatibility to upstream or downstream end conditions with sufficient annular space to allow for grout, mortar, cold applied asphalt joint compound or pre-formed plastic gasket material.
Methods of lifting shall be provided by the manufacturer for ease of loading, unloading, and installation.
Pipe runners are designed for a traversing load of 1,800 Lbs at yield as recommended by Research Report 280-1, "Safety Treatment of Roadside Cross-Drainage Structures", Texas Transportation Institute, March 1981.


PRECAST SAFETY END TREATMENT TYPE II ~ CROSS DRAINAGE

PSET-RC


FILE: psetrcss-20.dgn	DN: RLW	CK: KLR	DW: JTR	CK: GAF
©TxDOT February 2020	CONT	SECT	JOB	HIGHWAY
REVISIONS				RH
	DIST	COUNTY		SHEET NO.
	AUS	HAYS		45

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: 10/4/2023 8:15:34 AM
FILE: \$FILES




PLAN



LONGITUDINAL ELEVATION



MULTIPLE PIPE INSTALLATION



SINGLE PIPE INSTALLATION

SECTION A-A

ESTIMATED CONCRETE RIPRAP QUANTITIES (CY) ⑤

Nominal Culvert (Pipe) I.D.	PSET-SC and PSET-SP Standards					PSET-RC and PSET-RP Standards		
	Unit Width "W"	Side Slope			Unit Width "W"	Side Slope		
		3:1	4:1	6:1		3:1	4:1	6:1
12"	23.0"	0.1	0.2	0.2	16.0"	0.1	0.1	0.2
15"	26.5"	0.2	0.2	0.3	19.5"	0.1	0.2	0.2
18"	30.0"	0.2	0.2	0.3	23.0"	0.2	0.2	0.3
24"	37.0"	0.3	0.3	0.5	30.0"	0.2	0.3	0.4
30"	44.5"	0.3	0.4	0.6	37.0"	0.3	0.3	0.5
36"	51.5"	0.4	0.5	0.7	44.0"	0.3	0.4	0.6
42"	58.5"	0.5	0.6	0.8	51.0"	0.4	0.5	0.7

- ① Riprap placed beyond the limits shown will be paid as concrete riprap in accordance with Item 432, "Riprap". When riprap is cast integrally with the precast safety end treatment, this dimension is 1'-0" minimum.
- ② 1#2" Dia ASTM A307 Gr A threaded anchor rod with 2 nuts and 2 washers. Galvanize all components in accordance with Item 445, "Galvanizing". Repair galvanizing that is damaged during transport or construction in accordance with the specifications.
- ③ 3#4" through holes in walls of safety end treatment for riprap anchor rods may be drilled with rotary (coring or masonry) type drilling equipment or may be formed. Do not use percussive (star) type drilling equipment. If holes are drilled, patch spalls in the inside face of the wall exceeding 1#2" from the holes.
- ④ Provide riprap toe wall when dimension is shown elsewhere in the plans or when field conditions require a toe wall.
- ⑤ Quantities shown are for one end of one reinforced concrete pipe culvert. For multiple pipe culverts, quantities will need to be adjusted. Riprap quantities are for Contractor's information only. Quantities are based on the minimum unit lengths shown on the Precast Safety End Treatment (SET) standard sheets.

MATERIAL NOTES:

Provide Class "B" riprap in accordance with Item 432, "Riprap".
Synthetic fibers listed on the "Fibers for Concrete" Material Producer List (MPL) may be used in lieu of steel reinforcing in riprap concrete unless noted otherwise. The anchor rods shown are always required.

GENERAL NOTES:

Precast safety end treatment for reinforced concrete pipe may be used for TYPE II end treatment as specified in Item 467, "Safety End Treatment".
Refer to PSET-SC or PSET-SP standard sheets for details of square safety end treatments not shown. Refer to PSET-RC or PSET-RP standard sheets for details of round safety end treatments not shown.
For precast units with integrally cast riprap, substitute reinforcing steel in the amount on 0.26 in./ft. minimum for the threaded anchor rods shown. When requested, submit sealed engineering drawings for approval prior to construction. Shop drawings will not be required. Note that a proprietary precast unit with integral riprap is available from L&R Precast Concrete Works, Inc. (956) 583-6293 or www.lrpccast.com.
Payment for riprap and toewalls is included in the price bid for each safety end treatment.

These riprap details are only applicable when notes that require placement of riprap with precast safety end treatments are shown elsewhere in the plans.
Precast units with integrally cast riprap are permitted unless noted otherwise on the plans.

Texas Department of Transportation Bridge Division Standard

PRECAST SAFETY END TREATMENT TYPE II RIPRAP DETAILS PSET-RR

FILE: psetrrse-20.dgn	DN: GAF	CK: TxDOT	DW: JRP	CK: GAF
©TxDOT February 2020	CONTRACT	SECTION	JOB	HIGHWAY
REVISIONS				RH
	DIST	COUNTY		SHEET NO.
	AUS	HAYS		46


PLOT DRIVER: TXDOT_PDF_BW.pltctg
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - Connector Signing and Pavement Marking Plan

PENTABLE: 10338078.tbl

DATE: 10/4/2023


TIME: 8:15:45 AM

SCALE: 1:40





LEGEND

	PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
	EXISTING RIGHT OF WAY
	PROPOSED RIGHT OF WAY
	PROPOSED CONSTRUCTION BY OTHERS
	INSTL DEL ASSM (D-SW)SZ (BRF)GF1 (BI)



NOTES:
 1. ALL DELINEATORS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD).



NO.	DATE	REVISION	APPROVED

HDR
 HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900



ROGER HANKS
SIGNING AND PAVEMENT MARKING PLAN

SHEET 1 OF 1

DESIGN SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO. RH
GRAPHICS KB	STATE	DISTRICT	COUNTY	SHEET NO.
CHECK JC	TEXAS	AUS	HAYS	47
CHECK JC	CONTROL	SECTION	JOB	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:15:47 AM
 FILE: \$FILES\$

REFLECTOR UNIT SIZES FOR DELINEATORS AND OBJECT MARKERS				DELINEATORS				D & OM DESCRIPTIVE CODES		
DEVICE	SIZE 1	SIZE 2	SIZE 3	SIZE 4	SINGLE		DOUBLE		INSTL DEL ASSM (D-XX)SZ X (XXXX)XXX (XX) NUMBER OF REFLECTORS S = Single D = Double COLOR OF REFLECTORS W = White Y = Yellow R = Red REFLECTOR UNIT SIZE 1 or 2 TYPE OF POST OR DELINEATOR WC = Wing Channel Post YFLX = Yellow Flexible Post WFLX = White Flexible Post BRFL = Barrier Reflector TYPE OF MOUNT GND = Embedded (drivable or set in concrete) CTB = Concrete Barrier Mount GF1 or GF2 = Guard Fence Attachment SRF = Surface Mount DIRECTION If Required BI = Bi-Directional BR = Bi-Directional with red on back	
SHEETING	Yellow, White or Red Type B or C reflective sheeting				Yellow, White or Red Type B or C Reflective Sheeting					
NOTE	1. Size 1 and 4 - Direct applied reflective sheeting for use on flexible post (flx). 2. Size 2 and 3 - For use on wing channel (wc) post only. Use approved metal, plastic or fiberglass backplate with 17/64" mounting holes.				POST TYPE	WC	YFLX, WFLX	WC	YFLX, WFLX	INSTL OM ASSM (OM-XX) (XXXX)XXX (XX) TYPE OF OBJECT MARKER 1, 2, 3, or 4 NUMBER OF REFLECTORS OR DIRECTION X = 3-Size 2 reflector unit (Type 2 only) Y = 1-Size 3 reflector unit (Type 2 only) Z = 3-Size 1 or 1-Size 4 reflector unit(s) (Type 2 only) L = Left Side (Type 3 Object Marker only) R = Right Side (Type 3 Object Marker only) C = Center (Type 3 Object Marker only) TYPE OF POST WC = Wing Channel Post WFLX = White Flexible Post TWT = Thin Walled Tubing TYPE OF MOUNT GND = Embedded (drivable) SRF = Surface Mount WAS = Wedge Anchor Steel WAP = Wedge Anchor Plastic DIRECTION If Required BI = Bi-Directional
					MOUNT TYPE	GND	GND, SRF	GND	GND, SRF	

OBJECT MARKERS										
DEVICE	Type 1 (OM-1)		Type 2 (OM-2)			Type 3 (OM-3)			Type 4 (OM-4)	
	OM-1	OM-2X	OM-2Y	OM-2Z	OM-3L	OM-3R	OM-3C	OM-4		
	Yellow-Type B _{FL} or C _{FL} Sheeting		Yellow - Type B or C Sheeting			Alternating acrylic black and retroreflective yellow - Type B _{FL} or C _{FL} Sheeting			Red -Type B _{FL} or C _{FL} Sheeting	
SHEETING	TWT		WC	WC	WFLX	TWT			TWT	
POST TYPE	WAS, WAP		GND	GND	GND, SRF	WAS, WAP			WAS, WAP	
MOUNT TYPE										











DEPARTMENTAL MATERIAL SPECIFICATIONS	
FLEXIBLE DELINEATOR & OBJECT MARKER POSTS (EMBEDDED & SURFACE MOUNT TYPES)	DMS-4400
SIGN FACE MATERIALS	DMS-8300
DELINEATORS, OBJECT MARKERS AND BARRIER REFLECTORS	DMS-8600


BARRIER REFLECTORS (BRF)			CHEVRONS				ONE DIRECTION LARGE ARROW		NOTE: Delineator and object marker substrates and sign substrates shall be 0.080" Aluminum sign blank to conform to ASTM B-209 Alloy 6061-T6 or approved alternative.	
DEVICE	GF1	GF2	CTB	W1-8				W1-6		
	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: www.txdot.gov.				1. CHEVRON (W1-8) signs and ONE DIRECTION LARGE ARROW (W1-6) Signs shall be installed per Sign Mounting Details (SMD) Standard Sheets and paid under Item 644 (Small Roadside Sign Assemblies). 2. When there is a need to increase conspicuity, the Texas version of the ONE DIRECTION LARGE ARROW sign (W1-9T) may be used instead of the ONE DIRECTION LARGE ARROW (W1-6).				 Texas Department of Transportation Traffic Safety Division Standard	
SHEETING	Yellow, White, Red			SIZE (W x L)	18" x 24" (Conventional)	24" x 30" (Conventional Oversize)	30" x 36" (Expressway)	36" x 48" (Freeway)		48" x 24" (Conventional)
NOTE	1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.			MOUNTING HEIGHT	4'-0" or 7'-0"		7'-0" Only		7'-0"	
				NOTE						

FILE: dom1-20.dgn	DN: TXDOT	CK: TXDOT	DW: TXDOT	CK: TXDOT
© TXDOT August 2004	CONT	SECT	JOB	HIGHWAY
10-09 3-15	REVISIONS		RH	
4-10 7-20	DIST	COUNTY	SHEET NO.	
	AUS	HAYS	48	

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:15:48 AM
 FILE: \$FILES\$

POST TYPE AND SUPPORT FOUNDATION DETAILS				TYPE OF BARRIER MOUNTS		
WING CHANNEL (WC)	FLEXIBLE POSTS (YFLX, WFLX)		WEDGE ANCHOR SYSTEMS		GUARD FENCE ATTACHMENT	
GND	GND	SRF	WAS	WAP	GF1	
						
	EMBEDDED	SURFACE MOUNT	STEEL	PLASTIC	CONCRETE TRAFFIC BARRIER (CTB)	
NOTES 1. Embedded Wing Channel (WC) post option may be used for Type 2 Object Markers and Delineators only. 2. 1.12 lbs/ft steel per ASTM A 1011 SS Gr. 50, or ASTM A499.			NOTE 1. Install per manufacturer's recommendations.		GENERAL NOTES 1. Place delineators on a section of roadway at a consistent distance from the edge of pavement. 2. Where a restriction prevents consistent placement from the pavement edge, place the affected object markers in line with the innermost edge of the obstruction. 3. When Type 2 object markers and delineators are more than 8'-0" from the edge of the pavement, it may not be possible to maintain a height of approximately 4'-0". If this is the case, place the object marker or delineator as close to the desired height as possible. 4. Install all delineators, object markers and barrier reflectors in accordance with the manufacturer's recommendation. 5. Barrier reflectors should be installed a minimum of 18 inches above the edge of the pavement surface. 6. Diagonal stripes on Type 3 object markers shall slope down toward the intended travel lane.	
NOTES 1. See "Flexible Delineator and Object Marker Posts" Material Producer List for approved devices. 2. Install per manufacturer's recommendations. 3. Post length may vary to meet field conditions. 4. When using yellow delineators with flexible posts to separate opposing direction of travel, such as centerline or median use, the flexible posts shall be yellow.						
TYPES 1,3, AND 4 OBJECT MARKERS AND CHEVRONS		CHEVRONS AND ONE DIRECTION LARGE ARROW SIGN		DELINEATORS AND TYPE 2 OBJECT MARKERS		
						
NOTE Mounting at 4 feet to the bottom of the chevron is permitted for chevrons that will not exceed a height of 6'-6" to the top of the chevron (sizes 24" x 30" and smaller)		NOTE Chevrons 30" x 36" and larger shall be mounted at a height of 7' to the bottom of the chevron. Chevron sign and ONE DIRECTION LARGE ARROW sign (W1-9T) shall be installed per SMD standard sheets and paid under item 644.		See general notes 1, 2 and 3.		



Texas Department of Transportation

Traffic Safety Division Standard

DELINEATOR & OBJECT MARKER INSTALLATION

D & OM(2)-20

FILE: dom2-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS				
10-09 3-15	DIST	COUNTY	SHEET NO.	
4-10 7-20	AUS	HAYS	49	


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:15:55 AM
 FILE: \$FILES\$

MINIMUM WARNING DEVICES AT CURVES WITH ADVISORY SPEEDS

Amount by which Advisory Speed is less than Posted Speed	Curve Advisory Speed	
	Turn (30 MPH or less)	Curve (35 MPH or more)
5 MPH & 10 MPH	• RPMs	• RPMs
15 MPH & 20 MPH	• RPMs and One Direction Large Arrow sign	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons.
25 MPH & more	• RPMs and Chevrons; or • RPMs and One Direction Large Arrow sign where geometric conditions or roadside obstacles prevent the installation of chevrons	• RPMs and Chevrons


SUGGESTED SPACING FOR DELINEATORS ON HORIZONTAL CURVES



NOTE

ONE DIRECTION LARGE ARROW (W1-6) sign should be located at approximately and perpendicular to the extension of the centerline of the tangent section of approach lane.

SUGGESTED SPACING FOR CHEVRONS ON HORIZONTAL CURVES



NOTE

At least one chevron pair is installed beyond the point of tangent in tangent section.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS KNOWN				
Degree of Curve	FEET			
	Radius of Curve	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
		A	2A	B
1	5730	225	450	—
2	2865	160	320	—
3	1910	130	260	200
4	1433	110	220	160
5	1146	100	200	160
6	955	90	180	160
7	819	85	170	160
8	716	75	150	160
9	637	75	150	120
10	573	70	140	120
11	521	65	130	120
12	478	60	120	120
13	441	60	120	120
14	409	55	110	80
15	382	55	110	80
16	358	55	110	80
19	302	50	100	80
23	249	40	80	80
29	198	35	70	40
38	151	30	60	40
57	101	20	40	40

Curve delineator approach and departure spacing should include 3 delineators spaced at 2A. This spacing should be used during design preparation or when the degree of curve is known.

DELINEATOR AND CHEVRON SPACING

WHEN DEGREE OF CURVE OR RADIUS IS NOT KNOWN			
Advisory Speed (MPH)	Spacing in Curve	Spacing in Straightaway	Chevron Spacing in Curve
	A	2xA	B
65	130	260	200
60	110	220	160
55	100	200	160
50	85	170	160
45	75	150	120
40	70	140	120
35	60	120	120
30	55	110	80
25	50	100	80
20	40	80	80
15	35	70	40

If the degree of curve is not known, delineator spacing may be determined based on the Advisory Speed of the curve. Use the delineator curve spacing for each Advisory Speed (MPH).

DELINEATOR AND OBJECT MARKER APPLICATION AND SPACING

CONDITION	REQUIRED TREATMENT	MINIMUM SPACING
Frwy./Exp. Tangent	RPMs	See PM-series and FPM-series standard sheets
Frwy./Exp. Curve	Single delineators on right side	See delineator spacing table
Frwy/Exp. Ramp	Single delineators on at least one side of ramp (should be on outside of curves) (see Detail 3 on D&OM(4))	100 feet on ramp tangents Use delineator spacing table for ramp curves ("straightway spacing" does not apply to ramp curves)
Acceleration/Deceleration Lane	Double delineators (see Detail 3 on D&OM(4))	100 feet (See Detail 3 on D & OM (4))
Truck Escape Ramp	Single red delineators on both sides	50 feet
Bridge Rail (steel or concrete) and Metal Beam Guard Fence	Bi-Directional Delineators when undivided with one lane each direction Single Delineators when multiple lanes each direction	Equal spacing (100' max) but not less than 3 delineators
Concrete Traffic Barrier (CTB) or Steel Traffic Barrier	Barrier reflectors matching the color of the edge line	Equal spacing 100' max
Cable Barrier	Reflectors matching the color of the edge line	Every 5th cable barrier post (up to 100' max)
Guard Rail Terminus/Impact Head	Divided highway - Object marker on approach end Undivided 2-lane highways - Object marker on approach and departure end	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5) and D & OM (6)
Bridges with no Approach Rail	Type 3 Object Marker (OM-3) at end of rail and 3 single delineators approaching rail	See D & OM(5)
Reduced Width Approaches to Bridge Rail	Type 2 and Type 3 Object Markers (OM-3) and 3 single delineators approaching bridge	Requires reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end See D & OM (5)
Culverts without MBGF	Type 2 Object Markers	See Detail 2 on D & OM(4)
Crossovers	Double yellow delineators and RPMs	See Detail 1 on D & OM (4)
Pavement Narrowing (lane merge) on Freeways/Expressway	Single delineators adjacent to affected lane for full length of transition	100 feet

NOTES

- Unless indicated otherwise, the delineator or barrier reflector color shall conform to the color of the pavement edge line on the side of the road where the delineators or barrier reflectors are placed.
- Barrier reflectors may be used to replace required delineators.
- Single red delineators may be mounted on the back side of delineator posts for wrong way driver applications

LEGEND	
	Bi-directional Delineator
	Delineator
	Sign

Texas Department of Transportation
Traffic Safety Division Standard


DELINEATOR & OBJECT MARKER PLACEMENT DETAILS

D & OM(3)-20

FILE: dom3-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2004	CONT	SECT	JOB	HIGHWAY
REVISIONS				
3-15 8-15	DIST	COUNTY	SHEET NO.	
8-15 7-20	AUS	HAYS	50	

20C


**TWO-WAY, TWO LANE ROADWAY
WITH REDUCED WIDTH APPROACH RAIL**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.


**TWO-WAY, TWO LANE ROADWAY
WITH METAL BEAM GUARD FENCE (MBGF)**



NOTE:

1. Terminal ends require reflective sheeting provided by manufacturer per D & OM (VIA) or a Type 3 Object Marker (OM-3) in front of the terminal end.

**TWO-WAY, TWO LANE ROADWAY
BRIDGE WITH NO APPROACH RAIL**



LEGEND

	Bidirectional Delineator
	Delineator
	OM-3
	OM-2
	Terminal End
	Traffic Flow



**DELINEATOR &
OBJECT MARKER
PLACEMENT DETAILS**





D & OM(5)-20

FILE: dom5-20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT	CK: TxDOT
© TxDOT August 2015	CONT	SECT	JOB	HIGHWAY
REVISIONS				RH
7-20	DIST	COUNTY	SHEET NO.	
	AUS	HAYS	51	




DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023 8:15:57 AM
FILE: \$FILES\$


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.





Object marker installed per manufacturer's recommendations.



* Adjust to fit attenuator per manufacturer's recommendation, or as directed by the Engineer



OBJECT MARKERS SMALLER THAN 3 FT²




NOTES

- Object Markers shall conform to the Texas MUTCD and meet the color and reflectivity requirement of Department Material Specification DMS 8300. Background shall be yellow reflective sheeting (Type B or C) and Chevron shall be black.
- Object Markers may be fabricated from adhesive backed reflective sheeting applied directly to guardrail end treatment, or applied directly to an "end cap" as per the manufacturer's recommendation. Direct applied sheeting shall provide a smooth surface and have no wrinkles, air bubbles, cuts or tears. A radius at the corners is not required for direct applied sheeting.
- Object Marker size may be reduced to fit smaller devices. Width of alternating black and yellow stripes are typically 6". Object Markers smaller than 3ft may have reduced width stripes of a minimum of 2 1/4".
- Pop rivets, screws, or nuts and bolts may be used to attach object markers and reflectors. Holes, slots or other openings may be cut or drilled through object markers to allow cable or other attachments.
- Object Marker at nose of attenuator is subsidiary to the attenuator.
- See D & OM (1-4) for required barrier reflectors.

NOTES

- Spacing should be adjusted to attach through centerline of drum, per attenuator manufacturer's recommendation, or as directed by the Engineer.
- Mounting should be flush with top of attenuator. Minimum size 96" x 24".



DATE: 10/4/2023 8:15:59 AM
FILE: \$FILES

<p>DELINEATOR & OBJECT MARKER FOR VEHICLE IMPACT ATTENUATORS</p> <p>D & OM(VIA)-20</p>			
FILE: domvia20.dgn	DN: TxDOT	CK: TxDOT	DW: TxDOT
© TxDOT December 1989	CONT	SECT	JOB
REVISIONS			HIGHWAY
4-92 8-04			RH
8-95 3-15			
4-98 7-20			
DIST	COUNTY	SHEET NO.	
AUS	HAYS	52	
20G			

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023
FILE: \$FILE\$

I. STORMWATER POLLUTION PREVENTION-CLEAN WATER ACT SECTION 402

TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for projects with 1 or more acres disturbed soil. Projects with any disturbed soil must protect for erosion and sedimentation in accordance with Item 506.

List MS4 Operator(s) that may receive discharges from this project. They may need to be notified prior to construction activities.

1.
2.
 No Action Required Required Action

Action No.

- Prevent stormwater pollution by controlling erosion and sedimentation in accordance with TPDES Permit TXR 150000
- Comply with the SW3P and revise when necessary to control pollution or required by the Engineer.
- Post Construction Site Notice (CSN) with SW3P information on or near the site, accessible to the public and TCEQ, EPA or other inspectors.
- When Contractor project specific locations (PSL's) increase disturbed soil area to 5 acres or more, submit NOI to TCEQ and the Engineer.

II. WORK IN OR NEAR STREAMS, WATERBODIES AND WETLANDS CLEAN WATER ACT SECTIONS 401 AND 404

USACE Permit required for filling, dredging, excavating or other work in any water bodies, rivers, creeks, streams, wetlands or wet areas.

The Contractor must adhere to all of the terms and conditions associated with the following permit(s):

- No Permit Required
 Nationwide Permit 14 - PCN not Required (less than 1/10th acre waters or wetlands affected)
 Nationwide Permit 14 - PCN Required (1/10 to <1/2 acre, 1/3 in tidal waters)
 Individual 404 Permit Required
 Other Nationwide Permit Required: NWP# _____

Required Actions: List waters of the US permit applies to, location in project and check Best Management Practices planned to control erosion, sedimentation and post-project TSS.

1.
2.
3.
4.

The elevation of the ordinary high water marks of any areas requiring work to be performed in the waters of the US requiring the use of a nationwide permit can be found on the Bridge Layouts.

Best Management Practices:

Erosion	Sedimentation	Post-Construction TSS
<input checked="" type="checkbox"/> Temporary Vegetation	<input checked="" type="checkbox"/> Silt Fence	<input type="checkbox"/> Vegetative Filter Strips
<input type="checkbox"/> Blankets/Matting	<input checked="" type="checkbox"/> Rock Berm	<input type="checkbox"/> Retention/Irrigation Systems
<input type="checkbox"/> Mulch	<input type="checkbox"/> Triangular Filter Dike	<input type="checkbox"/> Extended Detention Basin
<input type="checkbox"/> Sodding	<input type="checkbox"/> Sand Bag Berm	<input type="checkbox"/> Constructed Wetlands
<input type="checkbox"/> Interceptor Swale	<input type="checkbox"/> Straw Bale Dike	<input type="checkbox"/> Wet Basin
<input type="checkbox"/> Diversion Dike	<input type="checkbox"/> Brush Berms	<input type="checkbox"/> Erosion Control Compost
<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Erosion Control Compost	<input type="checkbox"/> Mulch Filter Berm and Socks
<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Mulch Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks
<input type="checkbox"/> Compost Filter Berm and Socks	<input type="checkbox"/> Compost Filter Berm and Socks	<input checked="" type="checkbox"/> Vegetation Lined Ditches
	<input type="checkbox"/> Stone Outlet Sediment Traps	<input type="checkbox"/> Sand Filter Systems
	<input type="checkbox"/> Sediment Basins	<input type="checkbox"/> Grassy Swales

III. CULTURAL RESOURCES

Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease work in the immediate area and contact the Engineer immediately.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

IV. VEGETATION RESOURCES

Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162, 164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

V. FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES, CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.

- No Action Required Required Action

Action No.

1.
2.
3.
4.

If any of the listed species are observed, cease work in the immediate area, do not disturb species or habitat and contact the Engineer immediately. The work may not remove active nests from bridges and other structures during nesting season of the birds associated with the nests. If caves or sinkholes are discovered, cease work in the immediate area, and contact the Engineer immediately.

LIST OF ABBREVIATIONS

BMP: Best Management Practice	SPCC: Spill Prevention Control and Countermeasure
CGP: Construction General Permit	SW3P: Storm Water Pollution Prevention Plan
DSHS: Texas Department of State Health Services	PCN: Pre-Construction Notification
FHWA: Federal Highway Administration	PSL: Project Specific Location
MOA: Memorandum of Agreement	TCEQ: Texas Commission on Environmental Quality
MOU: Memorandum of Understanding	TPDES: Texas Pollutant Discharge Elimination System
MS4: Municipal Separate Stormwater Sewer System	TPWD: Texas Parks and Wildlife Department
MBTA: Migratory Bird Treaty Act	TxDOT: Texas Department of Transportation
NOT: Notice of Termination	T&E: Threatened and Endangered Species
NWP: Nationwide Permit	USACE: U.S. Army Corps of Engineers
NOI: Notice of Intent	USFWS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

General (applies to all projects):

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

Contact the Engineer if any of the following are detected:

- * Dead or distressed vegetation (not identified as normal)
- * Trash piles, drums, canister, barrels, etc.
- * Undesirable smells or odors
- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

- Yes No

If "No", then no further action is required.

If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

- Yes No

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatement activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered on site. Hazardous Materials or Contamination Issues Specific to this Project:

- No Action Required Required Action

Action No.

1.
2.
3.

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

- No Action Required Required Action

Action No.

1.
2.
3.



		HDR Firm Registration No. F-754 710 Hesters Crossing, Suite 150 Round Rock, Texas 78681 512.685.2900	
		Design Division Standard	
ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS			
EPIC			
FILE: epic.dgn	DN: TxDOT	CK: RG	DW: VP
©TxDOT: February 2015	CONT	SECT	JOB
12-12-2011 (05) REVISIONS			RH
05-07-14 ADDED NOTE SECTION IV.	DIST	COUNTY	SHEET NO.
01-23-2015 SECTION I (CHANGED ITEM 1122 TO ITEM 506, ADDED GRASSY SWALES.	AUS	HAYS	53

A. GENERAL SITE DATA

- PROJECT LIMITS:**
SHANE LN/GOLDEN EAGLE DR AT ROGER HANKS PARKWAY
PROJECT LENGTH = 519.00 FT. = 0.098 MILES

- PROJECT LOCATION:**
BEG LATITUDE: +30° 12' 10.57" N BEG LONGITUDE: -98° 06' 14.03" W
END LATITUDE: +30° 12' 13.06" N END LONGITUDE: -98° 06' 08.23" W

- PROJECT SITE MAPS:**
* PROJECT LOCATION MAP: SEE TITLE SHEET
* DRAINAGE PATTERNS: SEE DRAINAGE AREA MAP
* SLOPES ANTICIPATED AFTER MAJOR GRADINGS OR AREAS OF SOIL DISTURBANCE: SEE TYPICAL SECTIONS
* LOCATION OF EROSION AND SEDIMENT CONTROLS: SEE SW3P LAYOUT
* SURFACE WATERS AND DISCHARGE LOCATIONS: SEE DRAINAGE AREA MAP
* PROJECT SPECIFIC LOCATIONS: TO BE SPECIFIED BY THE PROJECT FIELD OFFICE DURING CONSTRUCTION AND LOCATED IN THE PROJECT SW3P FILE. REFERENCE ITEM #10 BELOW

- PROJECT DESCRIPTION:** RECONSTRUCTING OF THE ROADWAY AND OPERATIONAL IMPROVEMENTS

- MAJOR SOIL DISTURBING ACTIVITIES:**
SOIL DISTURBING ACTIVITIES WILL INCLUDE PREPARING THE RIGHT OF WAY, GRADING, EROSION CONTROLS, AND TOPSOIL WORK FOR FINAL SEEDING.

- EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:**

EXISTING SOILS CONSIST OF CLAY LOAM
EXISTING VEGETATIVE COVER PATCHY GRASS APPROX 60%

- TOTAL PROJECT AREA:** 0.92 ACRES

- TOTAL AREA TO BE DISTURBED:** 0.99 ACRES

- WEIGHTED RUNOFF COEFFICIENT**
BEFORE CONSTRUCTION: 0.52
AFTER CONSTRUCTION: 0.55

- NAME OF RECEIVING WATERS:** (SEGMENT NUMBER OF RECEIVING WATERS)
ONION CREEK (SEGMENT NUMBER 1427)

- PROJECT SW3P FILE:** FOR PROJECTS DISTURBING ONE ACRE OR MORE, TXDOT WILL MAINTAIN AN SW3P FILE WITH ALL PERTINENT ENVIRONMENTAL DOCUMENTS, CORRESPONDENCE, ETC. AT THE PROJECT FIELD OFFICE. IF NO FIELD OFFICE IS AVAILABLE THEN THE SW3P FILE SHALL BE KEPT IN THE INSPECTOR'S TRUCK.

B. EROSION AND SEDIMENT CONTROLS

- SOIL STABILIZATION PRACTICES:**
 TEMPORARY SEEDING
 PERMANENT PLANTING, SODDING, OR SEEDING
 MULCHING
 SOIL RETENTION BLANKET
 BUFFER ZONES
 PRESERVATION OF NATURAL RESOURCES

OTHER:

- STRUCTURAL PRACTICES:**
 SILT FENCES
 ROCK FILTER DAMS
 DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
 DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
 DIVERSION DIKE AND SWALE COMBINATIONS
 PIPE SLOPE DRAINS
 PAVED FLUMES
 ROCK BEDDING AT CONSTRUCTION EXIT
 TIMBER MATTING AT CONSTRUCTION EXIT
 CHANNEL LINERS
 SEDIMENT TRAPS
 SEDIMENT BASINS
 STORM INLET SEDIMENT TRAP
 STONE OUTLET STRUCTURES
 CURBS AND GUTTERS
 STORM SEWERS
 VELOCITY CONTROL DEVICES

OTHER:

- STORM WATER MANAGEMENT:**
STORM WATER DRAINAGE WILL BE PROVIDED BY EXISTING AND PROPOSED OPEN DITCHES THIS SYSTEM WILL CARRY THE DRAINAGE WITHIN THE RIGHT-OF-WAY TO EXISTING CHANNELS AND STORM SEWER SYSTEM

- STORM WATER MANAGEMENT ACTIVITIES: (SEQUENCE OF CONSTRUCTION)**
1. EXTEND EXISTING PIPE AND INSTALL AREA INLET.
2. RECONSTRUCT SHANE LN/GOLDEN EAGLE FROM BEGIN TO END.
3. CONSTRUCT CONNECTOR FROM SHANE LN TO ROGER HANKS PARKWAY.

- NON-STORM WATER DISCHARGES:**
FILTER NON-STORM WATER DISCHARGES, OR HOLD RETENTION BASINS, BEFORE BEING ALLOWED TO MIX WITH STORM WATER. THESE DISCHARGES CONSIST OF NON-POLLUTED GROUND WATER, SPRING WATER, FOUNDATION AND/OR FOOTING DRAIN WATER; AND WATER USED FOR DUST CONTROL, PAVEMENT WASHING AND VEHICLE WASHWATER CONTAINING NO DETERGENTS.

C. OTHER REQUIREMENTS & PRACTICES

- MAINTENANCE:**
MAINTENANCE WILL BE PERFORMED AS INDICATED ON FIELD INSPECTION AND MAINTENANCE REPORT FORM 2118.

 - INSPECTION:**
INSPECTION WILL BE PERFORMED AS INDICATED ON FIELD INSPECTION AND MAINTENANCE REPORT FORM 2118.


 - WASTE MATERIALS:**
ALL WASTE MATERIALS WILL BE COLLECTED, STORED AND DISPOSED OF IN A LEGAL AND PROPER MANNER. NO CONSTRUCTION WASTE MATERIAL WILL BE BURIED ON SITE.

 - HAZARDOUS WASTE (INCLUDING SPILL REPORTING):**
AT A MINIMUM, ANY PRODUCTS IN THE FOLLOWING CATEGORIES ARE CONSIDERED TO BE HAZARDOUS. PAINTS, ACIDS FOR CLEANING MASONRY SURFACES, CLEANING SOLVENTS, ASPHALT PRODUCTS, CHEMICAL ADDITIVES FOR SOIL STABILIZATION, OR CONCRETE CURING COMPOUNDS AND ADDITIVES. IN THE EVENT A SPILL WHICH MAY BE HAZARDOUS, THE SPILL COORDINATOR MUST BE CONTACTED IMMEDIATELY.

 - SANITARY WASTE:**
ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NECESSARY OR AS REQUIRED BY LOCAL REGULATION BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.
- OFFSITE VEHICLE TRACKING:
- HAUL ROADS DAMPENED FOR DUST CONTROL
 LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
 EXCESS DIRT ON ROAD REMOVED DAILY
 STABILIZED CONSTRUCTION ENTRANCE
- OTHER:

REMARKS: DISPOSAL AREAS, STOCKPILES AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL SEDIMENT FROM ENTERING RECEIVING WATERS. DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WATERBODY OR STREAMBED.

CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED TO MINIMIZE THE RUNOFF OF POLLUTANTS.



NO.	DATE	REVISION	APPROVED

HDR
HDR
Firm Registration No. F-754
710 Hesters Crossing, Suite 150
Round Rock, Texas 78681
512.685.2900



ROGER HANKS

SW3P NARRATIVE

SHEET 1 OF 1





DESIGN SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS KB	STATE	DISTRICT	COUNTY	RH SHEET NO.
CHECK JC	TEXAS	AUS	HAYS	54
CHECK JC	CONTROL	SECTION	JOB	

PLOT DRIVER: TXDOT_PDF_LW.pltcf9
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - SW3P Narrative
 PENTABLE: 10338078.tbl
 DATE: 10/4/2023
 TIME: 8:16:03 AM
 SCALE: 1:1

LEGEND

---	PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
- - - -	EXISTING RIGHT OF WAY
---	PROPOSED RIGHT OF WAY
---	PROPOSED CONSTRUCTION BY OTHERS
(RFD2)	ROCK FILTER DAM (TY 2)
(SCP)	SEDIMENT CONTROL FENCE
↓ ↓ ↓ ↓	SEEDING AND TOPSOIL

- NOTES:**
- CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF BMPs SHOWN AND ALTER LOCATIONS AS NEEDED TO ACHIEVE INTENDED PURPOSE AS APPROVED BY THE ENGINEER.
 - PERIMETER CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCING ANY SOIL DISTURBING ACTIVITIES. PERIMETER DEVICES TO BE PLACED AT ROW OR EASEMENT UNLESS OTHERWISE NOTED.
 - CONSTRUCTION EXIT LOCATIONS ARE TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
 - CONTRACTOR IS RESPONSIBLE TO VEGETATE ANY ADDITIONAL DISTURBED AREAS NOT CALLED OUT IN PLANS. PROVIDE SEEDING AND TOPSOIL FOR THESE AREAS. SUBSIDIARY TO PERTINENT ITEMS.



NO.	DATE	REVISION	APPROVED

HDR
 HDR
 Firm Registration No. F-754
 710 Hesters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900



ROGER HANKS
SW3P LAYOUT


SHEET 1 OF 2

DESIGN	SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS	KB	STATE	DISTRICT	COUNTY	RH
CHECK	JC	TEXAS	AUS	HAYS	SHEET NO.
CHECK	JC	CONTROL	SECTION	JOB	55

PLOT DRIVER: TXDOT_PDF_BW.plt
 USER: LGOINEZGONZ
 FILE: Roger Hanks Parkway - SW3P Layout
 PENTABLE: 10338078.tbl
 DATE: 10/04/2023
 TIME: 8:16:14 AM
 SCALE: 1/40

PLOT DRIVER: TXDOT_PDF_BW.pltctg
 USER: LGOMEZGONZ
 FILE: Roger Hanks Parkway - SW3P Layout


PENTABLE: 10338078.tbl
 DATE: 10/04/2023 TIME: 8:16:19 AM
 SCALE: 1:40



LEGEND

	PROPERTY LINE (HAYS CENTRAL APPRAISAL DISTRICT)
	EXISTING RIGHT OF WAY
	PROPOSED RIGHT OF WAY
	PROPOSED CONSTRUCTION BY OTHERS
	ROCK FILTER DAM (TY 2)
	SEDIMENT CONTROL FENCE
	SEEDING AND TOPSOIL

- NOTES:**
- CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF BMPs SHOWN AND ALTER LOCATIONS AS NEEDED TO ACHIEVE INTENDED PURPOSE AS APPROVED BY THE ENGINEER.
 - PERIMETER CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCING ANY SOIL DISTURBING ACTIVITIES. PERIMETER DEVICES TO BE PLACED AT ROW OR EASEMENT UNLESS OTHERWISE NOTED.
 - CONSTRUCTION EXIT LOCATIONS ARE TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
 - CONTRACTOR IS RESPONSIBLE TO VEGETATE ANY ADDITIONAL DISTURBED AREAS NOT CALLED OUT IN PLANS. PROVIDE SEEDING AND TOPSOIL FOR THESE AREAS. SUBSIDIARY TO PERTINENT ITEMS.



STATE OF TEXAS
 FELIPE S. TUTTUD
 104836
 LICENSED PROFESSIONAL ENGINEER
 10/04/2023
Felipe Tuttud

NO.	DATE	REVISION	APPROVED

HDR
 HDR
 Firm Registration No. F-754
 710 Heisters Crossing, Suite 150
 Round Rock, Texas 78681
 512.685.2900

THE CITY OF
DRIPPING SPRINGS
 TEXAS © 2023


ROGER HANKS
SW3P LAYOUT

SHEET 2 OF 2

DESIGN SJ	FED. RD. DIV. NO.	FEDERAL AID PROJECT NO.		HIGHWAY NO.
GRAPHICS KB	STATE	DISTRICT	COUNTY	RH SHEET NO.
CHECK JC	TEXAS	AUS	HAYS	56
CHECK JC	CONTROL	SECTION	JOB	


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

10/14/2023
\$FILE\$



TEMPORARY SEDIMENT CONTROL FENCE

SCF



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA. SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


LEGEND

Sediment Control Fence

SCF

GENERAL NOTES

1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
2. Perform vertical tracking on slopes to temporarily stabilize soil.
3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
4. Do not exceed 12" between track impressions.
5. Install continuous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING

TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING EC(1)-16

FILE: ec116	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY
REVISIONS				RH
DIST	COUNTY		SHEET NO.	
AUS	HAYS		57	


DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023
FILE: \$FILES\$




FILTER DAM AT TOE OF SLOPE


(RFD1)




PLAN VIEW



"V" SHAPE PLAN VIEW




SECTION B-B




TYPE 4 (SACK GABIONS)

(RFD4)




SECTION A-A




FILTER DAM AT SEDIMENT TRAP

(RFD2) OR (RFD1)



PROFILE



SECTION C-C

ROCK FILTER DAM USAGE GUIDELINES

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 GPM/FT² of cross sectional area. A 2 year storm frequency may be used to calculate the flow rate.


Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximately 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

Type 2 (18" high with wire mesh) (3" to 6" aggregate): Type 2 may be used in ditches and at dike or swale outlets.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

Type 4 (Sack gabions) (3" to 6" aggregate): Type 4 May be used in ditches and smaller channels to form an erosion control dam.

Type 5: Provide rock filter dams as shown on plans.



FILTER DAM AT CHANNEL SECTIONS

(RFD3) OR (RFD2) OR (RFD1)

GENERAL NOTES

1. If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
2. Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
3. The rock filter dam dimensions shall be as indicated on the SW3P plans.
4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
6. Filter dams should be embedded a minimum of 4" into existing ground.
7. The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
8. Rock filter dam types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
9. Sack Gabions should be staked down with 3/4" dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 1/2" x 3 1/4".
10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
11. The guidelines shown hereon are suggestions only and may be modified by the Engineer.


PLAN SHEET LEGEND

- Type 1 Rock Filter Dam (RFD1)
- Type 2 Rock Filter Dam (RFD2)
- Type 3 Rock Filter Dam (RFD3)
- Type 4 Rock Filter Dam (RFD4)


		Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES ROCK FILTER DAMS EC (2) - 16			
FILE: ec216	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2016	CONT	SECT	JOB
REVISIONS		HIGHWAY	
		RH	
DIST	COUNTY	SHEET NO.	
AUS	HAYS	58	

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: 10/4/2023
FILE: \$FILES\$



PLAN VIEW




ELEVATION VIEW


**CONSTRUCTION EXIT (TYPE 1)
ROCK CONSTRUCTION (LONG TERM)**

GENERAL NOTES (TYPE 1)

- The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
- The coarse aggregate should be open graded with a size of 4" to 8".
- The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other materials approved by the Engineer.
- The construction exit shall be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




ELEVATION VIEW


**CONSTRUCTION EXIT (TYPE 2)
TIMBER CONSTRUCTION (LONG TERM)**

GENERAL NOTES (TYPE 2)

- The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50'.
- The treated timber planks shall be attached to the railroad ties with 1/2" x 6" min. lag bolts. Other fasteners may be used as approved by the Engineer.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The approach transitions shall be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- The construction exit should be graded to allow drainage to a sediment trapping device.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW



**SECTION A-A
CONSTRUCTION EXIT (TYPE 3)
SHORT TERM**

GENERAL NOTES (TYPE 3)

- The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
- The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
- The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.

				Design Division Standard	
TEMPORARY EROSION, SEDIMENT AND WATER POLLUTION CONTROL MEASURES CONSTRUCTION EXITS EC(3)-16					
FILE: ec316	DN: TxDOT	CK: KM	DW: VP	DN/CK: LS	
© TxDOT: JULY 2016	CONT	SECT	JOB	HIGHWAY	
REVISIONS					
	DIST	COUNTY	SHEET NO.		
	AUS	HAYS			59