


**TOWN OF DUNDEE
PRICE QUOTE SHEET**



DATE: 1/17/2026

DEPARTMENT: Public Works Stormwater

NAME OF PERSON SECURING THE QUOTE: Johnathon Vice

GENERAL DESCRIPTION OF ITEM: Construct a stormwater swell to direct water to existing drain with pipe and drians to be place near existing driveways on MLK and Betty Ave to prevent future flooding

Vendor Selected:

VENDOR #1

COMPANY NAME: ODOM CONTRACTING

CONTACT NUMBER: 863-337-6499

NAME OF REPRESENTATIVE: Kevin Odom

PRICE: \$29,880.00

SHIPPING: N/A

COMMENTS: Construct a stormwater swell to direct water to existing drain

Vendor Selected:

VENDOR #2

COMPANY NAME: ADEC CONSTRUCTION

CONTACT NUMBER: 954-274-7117

NAME OF REPRESENTATIVE: JUAN/ STEVEN

PRICE: \$35,915.00

SHIPPING: N/A

COMMENTS: Construct a stormwater swell to direct water to existing drain

Vendor Selected:

VENDOR #3

COMPANY NAME: JCR CONSTRUCTION AND SERVICES LLC

CONTACT NUMBER: 863-660-4704

NAME OF REPRESENTATIVE: Jarold

PRICE: \$86,900.00

SHIPPING: N/A

COMMENTS: Construct a stormwater swell to direct water to existing drain

DEPARTMENT DIRECTOR/SUPERVISOR: Johnathon Vice

DATE: 1/17/26

FINANCE DIRECTOR APPROVAL: VACANT

DATE: 1/23/26

TOWN MANAGER APPROVAL: Kurt A. Cook

DATE: 1/26/26

ADDITIONAL COMMENTS: _____

SOLE SOURCE JUSTIFICATION: _____



P.O. BOX 92019
LAKELAND, FL. 33804
863-337-6499 Office
863-337-5402 Fax

Town of Dundee
105 Center St
Dundee, FL
(863) 514-6636
E-MAIL: jvice@townofdundee.com

DATE: 11/19/2025

Revised 12/3/2025

ATTN: John Vice

RE: Betty Ave Drainage

<u>DESCRIPTION</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
GENERAL CONDITIONS				
Mobilization	1	EA		
Silt Fence	540	LF		
TOTAL GENERAL CONDITIONS				\$2,540.00
STORM				
Type C Inlet	2	EA		
Connect to Exist Inlet	1	EA		
6" PVC SDR-26	140	LF		
Grade Swale	1	LS		
Sod as Needed	1	LS		
6" Concrete Drive Apron (Patch)	1	LS		
Test	1	LS		
TOTAL STORM				\$27,340.00
TOTAL PROJECT				\$29,880.00

NOTES & CONDITIONS:

- ADDITIONAL MATERIAL COST SHALL BE ADDED BASED ON PRICE IN EFFECT AT TIME OF SHIPMENT.
- PER DRAWINGS DESIGN & PERMITTING BY OTHERS.
- SPECIFICALLY EXCLUDED IS THE HANDLING OR REMOVAL OF ANY HAZARDOUS MATERIAL OR UNSUITABLE MATERIALS FOUND ON THIS SITE.
- OWNER TO FURNISH ALL PERMITS, APPROVED PLANS, CONSTRUCTION EASEMENTS AND BONDS.
- THIS PROPOSAL MAY BE WITHDRAWN IF NOT ACCEPTED WITHIN 30 CALENDAR DAYS.

EXCLUSIONS:

LAY OUT, SOIL TESTING, DEWATERING, CONFLICTS, ASBUILTS, E.P.A. POLLUTION PLAN, RELOCATING EXISTING UTILITIES, IRRIGATION, METERS & METER BOXES FOR POTABLE WATER, REMOVAL OR REPLACEMENT OF TREES AND LANDSCAPING (INCLUDING SOD, SEED, MULCH), REPAIR OF ROAD, M.O.T., ROOF DRAIN TIE-INS, POLE HOLDING, ELECTRIC FOR LIFT STATION & RESTORATION OF ANY KIND.

KEVIN ODOM

ODOM CONTRACTING LLC



QUOTE/PURCHASE ORDER

"Real professionals on your side"

DATE	PO No.
12/8/2025	PODTD05

Bill to: Town of Dundee 1500 Race Road, Dundee, Fl	PROJECT: Betty Avenue
	P. O. NUMBER: PODTD05

CONTAC PERSON	JOB	PAYMENT TERMS	DUE DATE
John Vice	Stormwater Betty Avenue	45-Net	


QTY.	DESCRIPTION	RATE	AMOUNT
1.00	Mobilization	5,350.00	5,350.00
1.00	Maintenance of Traffic	950.00	950.00
1.00	Clearing & Grubbing	2,400.00	2,400.00
600.00	Silt Fence	1.00	600.00
1.00	Inlet Protection System	45.00	45.00
2.00	Catch Basin	4,000.00	8,000.00
1.00	Existing Catch Basin	650.00	650.00
148.00	Proposed 6" PVC Pipe	40.00	5,920.00
1.00	Regradin Swale	4,500.00	4,500.00
3,000.00	Bahia Sod Placement	2.50	7,500.00
		TOTAL DUE	35,915.00

Thank you for your business!

ADEC CONSTRUCTION INC.
 2200 N Commerce Pkwy Suite 200
 Weston, Fl. 33326
 Broward: **954 274 7117**
www.adeconstructioninc.com

JCR CONSTRUCTION & SERVICES LLC

3804 Block Prine Rd
FL 33810 USA
jcrconstructionservices@gmail.com



ADDRESS

Town Of Dundee
Betty ave project

ESTIMATE # 4624

DATE 12/18/2025

ACTIVITY	QUANTITY	RATE	AMOUNT
Service GENERAL CONDITIONS.	1	5,300.00	5,300.00
Service Description	1	70,500.00	70,500.00
Mob Porta Potty Service Silt Fence Driveway removal Type C Inlet Box with grate Inlet and 6" line install Grading Export Concrete Driveway replacement Sod			
Price reflects equipment, labor and supervision, for drainage and grading. ditch will be regraded for drainge to new installed boxes If any dirt must be removed it will be a charge of 275 Shop Drawings for boxes are included with Install Price.			
EXCLUSIONS			
NO ASPHALT No soil testing, mot. Utility relocations, Paving, Curb work, Or anything not listed in the line items above.Price is valid for 30 days A 50% Deposit is required to start work			
Overhead 15% of overhead	1	11,100.00	11,100.00

TOTAL

\$86,900.00