Tucker Paving $1,454,638.20				EZ Paving $1,554,010.94					
Item Discription	Price	QTY	Units	Item Discription	Price	QTY	Units	Difference in prices	Contractor with higher price
Mobilization	$ 226,500.00	1	LS	Mobilization/Demobilization	$ 60,000.00	1	LS	$ 166,500.00	Tucker Paving
Maintance of Traffic	$ 125,805.73	1	LS	Maintanance of Traffice	$ 11,000.00	1	LS	$ 114,805.73	Tucker Paving
Not Listed in Bid	-	-	-	Surveys/ As Builts	$ 121,000.00	1	EA	N/A	NOT ENOUGH INFO
Silt Fence (Sediment Barrier)	$ 9,550.00	9,550	LF	Silt Fence	$ 47,223.00	9,900	LF	$ 37,673.00	EZ Paving
Single sing post (relocate)	$ 1,005.00	5	EA	Relocate No Traspassing sign	$ 310.00	4	EA	$ 695.00	Tucker Paving
Relocated of power pole	not included	-	-	Relocate Power Pole	$ 61,600.00	8	EA	N/A	NOT ENOUGH INFO
Not Listed in Bid	-	-	-	Adjust Exsiting Valve	$ 178.50	2	EA	N/A	NOT ENOUGH INFO
included in item 28 price amount	-	-	-	Remove Exsiting wood post	$ 65.85	1	EA	N/A	NOT ENOUGH INFO
Not Listed in Bid	-	-	-	Saw Cut	$ 2,416.50	150	LF	N/A	NOT ENOUGH INFO
Not Listed in Bid	-	-	-	Export Materials	$ 41,364.00	11,490	CY	N/A	NOT ENOUGH INFO
Performace Turf (Bahia Sod)	$ 68,860.00	17,215	SY	Bahia Sod	$ 68,194.50	20,665	SY	$ 665.50	Tucker Paving
Embankment (grading)	$ 15,312.00	638	CY	Grading (Ditch, swell, slop etc)	$ 18,000.00	1	LS	$ 2,688.00	EZ Paving
Pipe Culvert RCP Round 18"	$ 44,352.00	616	LF	18" RCP Pipe	$ 50,703.84	776	LF	$ 6,351.84	EZ Paving
Mitered End Section (cross drain round)	$ 27,536.00	16	EA	18" RCP MES	$ 84,790.80	16	EA	$ 57,254.80	EZ Paving
Rip Rap Rubble Ditch Lining	$ 5,400.00	60	TN	Rip Rap	$ 33,332.89	735	SF	$ 27,932.89	EZ Paving
Super pave Asphalt TIC Traffic C 9.5	$ 296,676.00	1809	TN	2" SP-9.5 Asphalt	$ 326,370.00	14,835	SY	$ 29,694.00	EZ Paving
Optional Base 10" Lime Rock	$ 440,328.00	15726	SY	10" crushed concrete road base	$ 252,936.75	14,835	SY	$ 187,391.25	Tucker Paving
Not Listed in Bid	-	-	-	12" compacted subgrade	$ 24,477.75	14,835	SY	N/A	NOT ENOUGH INFO
Called out Item #18 not listed twice	-	-	-	2" SP-9.5 Asphalt (bella vista)	$ 2,200.00	100	SY	N/A	NOT ENOUGH INFO
Called out Item #19 not listed twice	-	-	-	8" crushed concrete road base (bella vista)	$ 5,373.50	100	SY	N/A	NOT ENOUGH INFO
Not Listed in Bid	-	-	-	12" stabilzed subgrade road base (bella vista)	$ 14,080.00	100	SY	N/A	NOT ENOUGH INFO
Concrete Curb/ Gutter (TYPE MIAMI CURB)	$ 740.00	20	LF	3" valley curb	$ 9,042.00	120	LF	$ 8,302.00	EZ Paving
Not Listed in Bid				6" concrete driveway w/fiber 3000psi	$ 224,812.50	8,175	SF	N/A	NOT ENOUGH INFO
12" Compacted subgrade	$ 15,726.00	15,726	SY	12" compacted subgrade	$ 3,651.50	908	SY	$ 12,074.50	Tucker Paving
concrete spillway 4" reinforced	$ 3,339.00	63	SY	concrete spill way	$ 15,537.50	565	SF	$ 12,198.50	EZ Paving
sinage and striping (paint only) see Bid notes	$ 99,679.47	1	LS	Signage/striping (PAINT ONLY) SEE BID NOTES	$ 75,350.00	1	LS	$ 24,329.47	Tucker Paving
Nuclear Density Test	$ 23.00	1	EA	Not Listed in Bid	-	-	-	N/A	NOT ENOUGH INFO
Proctor T-180 or T-99	$ 86.00	1	EA	Not Listed in Bid	-	-	-	N/A	NOT ENOUGH INFO
Clearing and Grubbing	$ 55,560.00	1	LS	Not Listed in Bid	-	-	-	N/A	NOT ENOUGH INFO
Regular Excavation	$ 18,160.00	9080	CY	Not Listed in Bid	-	-	-	N/A	NOT ENOUGH INFO
Required Permits (SWPPP) AND FEE'S	not included	-	-	Required Permits (SWPPP) AND FEE'S	not included	-	-	N/A	NOT ENOUGH INFO

Engineering Estimated Project Cost	$2,045,841.02
Linclon Ave Extension PROBALE COST	
Items	Price
Pavement	$ 324,208.36
Storm Water System	$ 49,457.02
Signage and Striping	$ 9,276.34
Earthwork	$ 19,035.36
20% Contingency	$ 80,395.42
CAMP ENDEAVOR PROBALE COST	
Pavement	$1,031,146.79
Storm Water System	$ 185,429.20
Signage and Striping	$ 30,884.64
Earthwork	$ 55,429.80
20% Contingency	$ 260,578.09
Egineering Total Probale Cost Estimate	$2,045,841.02