

Candy Cane
Dyersville, IA
1/23/24

Quotation Price – Materials Only Delivered to Job Site

Baseball Field -	\$ 140,904.00
Installation – Payable to 3rd Party	\$ 36,000.00

Sales tax, bonding, labor, installation, and unloading of the equipment are not included.

Quote is confidential. Pricing and lead times are effective for 30 days only. Prices are subject to change if the order is not released within 60 days from the date of the purchase.

Light-Structure System™ with Total Light Control – TLC for LED™ technology

Guaranteed Lighting Performance

- Guaranteed light levels of 50 footcandles Infield and 30 footcandles Outfield
- BallTracker® technology – targeted light, optimizing visibility of the ball in play with no glare in the players typical line-of-sight

System Description

- Factory aimed and assembled luminaries, including BallTracker® luminaires
- 6 Galvanized steel poles
- 6 Pre-cast concrete bases with integrated lightning grounding
- Pole length factory assembled wire harnesses
- Factory wired and tested remote electrical component enclosures
- UL listed assemblies

Control Systems and Services

- Control-Link® control and monitoring system to provide remote on/off and dimming (high/medium/low) control and performance monitoring with 24/7 customer support

Operation and Warranty Services

- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 Team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors

Responsibilities of Buyer

- Confirm pole or luminaire locations, supply voltage and phase required for lighting system prior to production
- Provide electrical design and materials for electrical distribution system
- Provide labor and equipment for installation of electrical distribution system
- Provide labor and equipment for installation of bases and poles
- Buyer is responsible for getting electrical power to the site, coordination with the utility, and any power company fees
- The unloading and storage of the material on site is the responsibility of the buyer

Payment Terms

Final payment terms are subject to approval by Musco credit department. Final payment shall not be withheld by Buyer on account of delays beyond the control of Musco.

Delivery Timing

10 - 12 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole/luminaire locations.



Notes

Quote is based on following conditions:

- Shipment of entire project together to one location.
- Voltage and phase system requirements to be confirmed.
- Structural code and wind speed = 2015 IBC, 115 mi/h, Exposure C, Importance Factor 1.
- Due to the built-in custom light control per luminaire, pole or luminaire locations need to be confirmed prior to production. Changes to pole or luminaire locations after the product is sent to production could result in additional charges.
- Standard soil conditions – rock, bottomless, wet, or unsuitable soil may require additional engineering, special installation methods and additional cost.

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.

Jason Schillig
Sales Representative
Musco Sports Lighting, LLC
Phone: 563-260-1334
E-mail: jason.schillig@musco.com

