

PURCHASE ORDER

Effingham County Board of Commissioners

804 S LAUREL STREET
SPRINGFIELD, GA 31329
Phone: 912-754-2159
Fax: 912-754-8413

DATE:
P.O. #

3/21/2023
Q-00396-1

VENDOR

Custom Truck and Body Works, Inc.
PO Box 718
13787 White House Road
Woodbury, GA 30293
ATTN : Jimmy Gill
706-977-7095 (cell) / 706-553-9178 (office)

SHIP TO

Effingham County Board of Commissioners
804 S.Laurel Street
Springfield, GA 31329
ATTN : Alison Bruton
912-754-2159

REQUISITIONER	SHIP VIA	F.O.B.	SHIPPING TERMS
ECBOC			

ITEM #	DESCRIPTION	QTY	UNIT PRICE	TOTAL
	Type III 14' Ambulance - Chevy G4500	1	\$199,582.00	\$ 199,582.00

SUBTOTAL	\$ 199,582.00
TAX RATE	\$ -
TAX	\$ -
S & H	\$ -
OTHER	\$ -
TOTAL	\$ 199,582.00

OTHER COMMENTS OR SPECIAL INSTRUCTIONS

ECBOC is a tax exempt entity. Tax ID# is 58-6000821

Custom Truck and Body Works, Inc. agrees to furnish one (1) Type III 14' Ambulance - Chevy G4500 as described in Quote Q-00396-1. The County references the terms, conditions and specifications contained in Quote Q-00396-1.

CUSTOM TRUCK & BODY WORKS - SIGNATURE

TITLE

CUSTOM TRUCK & BODY WORKS - PRINT NAME

DATE

AUTHORIZED BY - SIGNATURE

CHAIRMAN

AUTHORIZED BY - TITLE

WESLEY CORBITT

AUTHORIZED BY - PRINT NAME

AUTHORIZED DATE



Quote #: Q-00396-1
Date: 2/28/2023 4:34 PM
Expires On: 4/30/2023

Custom Truck and Body Works, Inc.

Manufacturers of Custom Emergency Apparatuses

13787 White House Rd
Woodbury, GA 30293
United States
Main Line: 706-655-4300

SHIPPING

WANDA MCDUFFIE
Effingham County

(912) 754-2148
wmcduffie@effinghamcounty.org

BILL TO

EFFINGHAM COUNTY EMS

Name	Direct Line	E-Mail Address
Jimmy Gill	(706) 977-7095	jimmy@customtruckandbodyworks.com
Payment Terms	Delivery Method	Delivery Terms
Due on Receipt	Pickup at CTBW	150 to 180 Business Days After Receipt of Chassis

Dear WANDA MCDUFFIE,

Custom Truck and Body Works would like to thank you for the opportunity to work with your department on this project. We have prepared this quote based on the information that has been provided to us. We are certain that we can meet or exceed any needs and expectations you may have. Please review the attached documents and if there should be any questions, clarifications or any additional information please do not hesitate to contact me. We look forward to hearing from you soon.

*Sincerely,
Jimmy Gill*

TYPE III 14' AMBULANCE-CHEVY G4500

\$199,582 Each

MODULAR BODY

QTY	UOM	PRODUCT NAME	DESCRIPTION
1		Modular Body - Type III 14'	The ambulance body 169"L x 96"W x72"H shall be constructed of custom designed aluminum extrusions and aluminum plate. The ambulance body shall be designed and engineered specifically as an emergency vehicle and shall be built to meet the heavy-duty requirements of emergency service.

CHASSIS

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	Chassis - Chevy G4500 - 4x2 - Gas - 100CA	
1	Each	Chassis Add On #1	Non Standard Additional Chassis Add On
Go Industries Brush Guard			
1	Each	Chassis Add On #2	Non Standard Additional Chassis Add On
LED LIGHT BAR			

CHASSIS ADD ON

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Set	Wheel Inserts - Phoenix - Chevy G3500/ G4500 (Standard)	
1	Set	Running Boards - Driver & Passenger - Reg Cab - NFPA (Standard)	Diamond plate running boards shall be provided and installed on the cab of the module to the chassis manufacturers recommendation.
2	Set	Lights - Grille - ION Red w Clear Lens LED (Standard)	Whelen ION series Red LED warning light with clear lens and chrome flange installed on the front grill of the chassis.
2	Set	Lights - Front Intersection - ION Red w Clear Lens LED (Standard)	Whelen ION series Red LED warning light with clear lens and chrome flange installed on the fenders of the chassis.
1	Set	Speaker - Cast - Chevrolet G3500/G4500 (Standard)	Two (2) 100-watt speakers shall be installed through the front OEM bumper.
1	Each	Back Up Camera - 7" Monitor Installed On Windshield (Standard)	An exterior Back Up Camera With 7" Monitor shall be mounted on the windshield.
2	Set	Fire Extinguisher - 5Lb w/ Bracket (Standard)	5lb Fire Extinguisher shall be shipped loose.
1	Set	Mud Flaps	Set of heavy-duty, thick rubber material mud flaps shall be as wide as the dual rear wheels.
1	Each	Spare Tire	A spare tire shall be provided with the chassis.
1	Each	Alarm - Backup	An audible alarm shall be installed to activate when the vehicle is placed into reverse gear. There shall be installed on the front console and wired through the vehicle electrical system, a momentary cutoff switch to disable the alarm.
1	Set	Engine Block Heater - Wire - Shoreline	The chassis engine block heater shall be wired to shoreline power.

CHASSIS CONSOLE

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	Console - Wood - Gray (Standard)	A wood scorpion coated console with (2) cup holders and map slot shall be provided between the driver and passenger seat.
2	Each	Siren - (Standard)	A Whelen 295SLSA1 single tone siren shall be installed in the cab console.
1	Each	Spotlight - Go Light LED w Remote Control	12V LED spotlight shall be installed on the cab roof.

L1 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	L1 Compartment	Street Side Forward Compartment Dimensions: H72"x W22"x D22"
1	Each	O2 Bracket Kit - Universal Cylinder w Ratchet Straps (Standard)	There shall be a Universal Zico Cylinder Bracket QRM-V O2 bottle mount to the back wall to allow the department to utilize both "M" cylinder and "H" cylinder bottles. LOCATION=BACK WALL
1	Each	O2 Wrench	An aluminum O2 wrench provided near the O2 bracket in the Oxygen compartment.
1	Each	Oxygen Regulator - 50 PSI	50 PSI Pre-Set diaphragm regulator with nut and nipple connection for large cylinders and preset to 50 PSI.
2	Each	Portable O2 Bracket Kit - D Cylinder - Zico QR-D-2	

L2 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	L2 Compartment	Street Side Intermediate Compartment Dimensions: H40"x W45"x D20"
1	Each	Panel - L2 - Inverter - Vanner 1100	A Vanner 1100 watt Inverter with 50 amp battery charger shall be provided and installed in the streetside exterior L2 compartment.
1	Each	Inverter - Pre Wire	A pre-wire for installation of the inverter shall be provided in the L2 compartment.

L3 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	L3 Compartment (Standard)	Street Side Rear Compartment Dimensions: H40"x W37"x D20"
Double doors on compartment			
1	Each	Adjustable Shelf - L3 Compartment	A horizontal aluminum adjustable shelf/shelves shall be provided in the L3 compartment mounted on shelf track.

R3 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	R3 Compartment	Curb Side Rear Compartment Dimensions: H72"x W20"x D20"
(2) straps and buckles across the back board storage area			
2	Each	Adjustable Shelf - R3 Compartment	A horizontal aluminum adjustable shelf/shelves shall be provided in the R3 compartment mounted on shelf track.
1	Each	Backboard Divider - R3 Compartment	A vertical divider shall be mounted center of the back board compartment.

R2 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	R2 Compartment	Curb Side Intermediate Compartment Dimensions: H24"x W20"x D20"

R1 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	R1 Compartment	Curb Side Forward Compartment Dimensions: H57"x W22"x D20"
1	Each	ALS Access with Slide Out & Battery Tray	
1	Each	R1 Battery Box Compartment	Battery Box Compartment Dimensions: H13"x W22"x D20"

EMERGENCY LIGHT PACKAGE

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Set	Lights - M Series - Red & White LED Warning w Clear Lens (7 Front Wall R/W/ R/W/R/W/R) (Standard)	Whelen M9 LED warning lights shall be installed on the module in the specified configuration. (7) front wall lights, (4) side body lights, (3) rear upper, and (2) lower window level lights.
2	Each	Lights - Rear Intersection - M7 Red LED w Clear Lens - Warning Light	Whelen M7 LED warning lights shall be installed above both rear wheels on the module

NON EMERGENCY LIGHT PACKAGE

QTY	UOM	PRODUCT NAME	DESCRIPTION
2	Set	Lights - Action Area/ Telemetry - LED	3" round led lights shall be located in the action area and telemetry area.
1	Each	Lights - Compartment - Single - LED Strip Lights (Standard)	Each exterior compartment shall have one (1) strip LED light installed full height on each side of the door opening.
10	Set	Lights - Dome - Whelen LED (Standard)	Whelen 8" LED Dome patient compartment lights with dual level lighting will be located in the ceiling. *Exact location & quantity can be changed at pre-construction meeting*
6	Set	Lights - Scene - M9 LED (Standard)	Whelen M Series LED Scene Lights shall be installed (2) two on rear, (2) per side of the ambulance modular body.
2	Set	Lights - Stop/Turn/Tail - M6 Series LED (Standard)	Whelen M Series LED Brake, Back Up and Turn signals with individual bezels installed on the rear of the module.
1	Set	Lights - ICC Marker - Red & Amber LED	7 LED Red and & 7 LED Yellow ICC lights installed on the upper module perimeter to meet DOT requirements.
1	Each	Light - Stepwell - LED	LED Stepwell light installed at the entry steps of the module.
1	Each	Lights - Tag Bracket - LED	LED lighting installed at the the tag bracket to meet DOT requirements.
2	Set	Lights - Docking - 6" Oval White	6" LED lights installed at the rear bumper to provide additional back up lighting.

MODULAR EXTERIOR

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	Shoreline - 30A/120V - Auto Eject - Blue Cover	A 30 amp automatic power line disconnect system shall be furnished for the vehicle shoreline.
2	Set	Fenderette - Aluminum (Standard)	Polished aluminum fender flair shall be installed around the rear wheel well openings.
1	Each	Window - Side - Sliding - Dark Tint (Standard)	Tinted high black aluminum framed sliding window is to be centered on the side entry door.
2	Each	Window - Rear - Fixed - Dark Tint (Standard)	Tinted high black aluminum framed fixed window is to be centered on each rear entry door.
1	System	Door Locks - Power - 6 Compartments & 2 Entry Doors w Hidden Stealth Switch	Install Power Door locks on all Compartments and Patient Entry Side and Rear Doors. Lock/unlock can be initiated by key fob, remote switch or by Cab & Driver's Side electric locks.
1	Set	Compartments - Scorpion - Gray (Standard)	Scorpion coated finish on all exterior compartments.
1	Set	Drip Rails - Aluminum	

PAINT

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	Paint Type - Modular Body - 1 Color	The module shall be a single tone paint to match the OEM chassis or customer specified paint code.
1	Each	Paint Type - Chassis - OEM (Standard)	Chassis shall be painted OEM one color to match fleet.

VINYL GRAPHICS

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Set	Door Panels - Chevron (Standard)	Aluminum plate door panels on all exterior doors with 12" of reflective chevron.
1	Set	Vinyl Graphics - Star of Life Reflective Package	KKK-Spec reflective SOL package provided with the graphics package. *Exact color and location to be determined at the pre-construction meeting*
1	Set	Vinyl Graphics - Lettering & Decals	Lettering and department decals designed and printed on 3M 680CR reflective material and laminated with UV protective laminate.
1	Each	Rear Chevron - Reflective	Printed rear chevrons that meets the existing fleet/customer specifications. Printed on 3M IJ680CR reflective material. **Color to be determined at Precon**
1	Each	Vinyl Graphics - Star of Life (Large)	Large printed Star of Life, installed on the front or rear of module. Printed on 3M IJ680CR reflective material. **Color and location to be determined at Precon**
Custom swoosh and SOL to match existing units			

MODULAR INTERIOR

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	Panel - Power - Location - Interior (Standard)	A printed circuit board shall be installed in the interior electrical cabinet behind attendant seat.
2	Set	Antenna - Coax	Two [2] 10-gauge power and two [2] ground wires, two [2] RG58U coax cables, and two [2] PL259 connectors.
3	Each	Outlet - 12V	12 Volt DC 20 Amp cigar style outlets will be located in the action area and in the advanced life support cabinet. *Exact location & quantity can be changed at pre-construction meeting*

QTY	UOM	PRODUCT NAME	DESCRIPTION
6	Each	Outlet - 110V - Lighted	110 Volt AC GFI duplex lighted outlets will be located in the action area, the telemetry, as well as the advanced life support cabinet. *Exact location & quantity can be changed at pre-construction meeting*
1	Each	Outlet - Oxygen - Single	A single O2 outlet provided at the head end of the squad wall. *Exact location & quantity can be changed at pre-construction meeting*
1	Set	Outlet - Oxygen - Dual	Dual O2 outlets shall be provided in the action area. *Exact location & quantity can be changed at pre-construction meeting*
1	Each	Outlet - Vacuum	Ohio style quick disconnect vacuum outlet provided in the action area wall.
1	Each	Electrical System - RCTronics 12V (Standard)	12v RC Tronics switch panel electrical system shall be provided in the cab console and in the action area of the module.
2	Each	Pre Wire - 12V Radio	12v radio pre-wires at the front console and rear action area. *Exact location and quantity can be changed at the pre-construction meeting*
1	Each	Flooring - Gun Metal Gray - Lonplate 3" (Standard)	Lonplate heavy duty floor covering installed above the PVC sub floor, rolled up on each side 3".
1	Each	Flooring - Composite PVC Sub Flooring	PVC composite sub flooring shall be installed above the aluminum sub floor.
1	Set	Cabinets - Plywood - 1 Tone - Matte Gray (Standard)	Cabinets shall be constructed of 3/4" plywood with a high-pressure plastic matte Gray laminate finish.
1	Set	Windows - Life Defender - Fixed (Standard)	Austin Hardware Gen II Life Defender cabinets, with clear plexi and fixed sliding windows.
1	Each	Seat - CPR	
1	Each	Countertops - Gray (Standard)	Solid Surface material counter tops at the action and telemetry areas. Gray in color.
1	Each	Cabinet - Plywood - Over Rear Door	Cabinet located over the rear entry door, providing one storage section.
1	Each	Cabinet - Plywood - Squad Bench Overhead	Cabinet located over the squad bench, divided into two separate storage sections.
1	Each	Cabinet - Plywood - Glove Box	Cabinet located over the side entry door, providing storage for three glove boxes.
1	Each	Cabinet Add On #1	Non Standard Additional Cabinet Add On
Add 110V in overhead cabinet closest to curbside entry door			
1	Each	Cabinet Add On #2	Non Standard Additional Cabinet Add On
Cabinet above pass thru			
1	Each	Cabinet Add On #3	Non Standard Additional Cabinet Add On
cabinet below pass thru			
1	System	Insulation - Polyfiber (Standard)	The modular ambulance body shall be insulated with a non-flammable Polyfiber insulation.
1	Each	Defibrillator Mount for Lifepak 12/15- Ferno	A Ferno Life Pack 12/15 monitor mount shall be supplied and installed at delivery. Customer location determined during the pre-build conference.
1	Each	Heater - Aux 110 - 1500W	A 110v auxiliary heater shall be supplied and installed. Location shall be determined during the pre-build conference.
Mounted above CPR seat			
6	Each	Emergency Release Latch	Curb and Rear entry doors shall come with upper and lower emergency release latches, in the event of failure to exit the module.

MODULAR INTERIOR DETAILS

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	Each	Suction - Rico - Action Area (Standard)	A RICO RS4X disposable aspirator will be installed in the action area and connected to the vacuum inlet by a quick connect coupler.
1	Each	Vacuum Pump	Electric vacuum pump installed in the L-2 exterior compartment, plumbed to the vacuum outlet on the rear action area wall.
3	Each	Seat Belt - 6 Point Harness	All seated positions shall have a 6 point safety harness seat belt system.
1	Each	Safety Net - Yellow Angled (Standard)	A yellow safety net shall be provided and installed at the head end of the squad bench.
2	Each	Grab Rail - Ceiling - 80" Yellow (Standard)	1.25" diameter x 80" yellow grab bars shall be provided and securely fastened to the ceiling over the primary cot and over the squad bench. *Exact location & quantity can be changed at pre-construction meeting*
3	Each	Grab Handle - 18" Yellow (Standard)	1.25" diameter x 18" yellow grab bars shall be provided at each entry door. *Exact location & quantity can be changed at pre-construction meeting*
3	Each	Grab Handle - Interior V Style - Yellow (Standard)	V-Style yellow grab handles shall be provided on the side and rear entry doors.
1	Each	Timer - 15 Minute Delay	A 15-minute mechanical timer shall be provided and installed at the head of squad bench adjacent to the side entry door. Timer to control the curb side dome lights.
1	Each	Clock - Digital - Intellitec (Standard)	A digital EMS clock shall be provided at the Action Area wall.
2	Set	IV Hanger - Ceiling Mount (Standard)	IV Hangers will be recessed in the ceiling over the head and foot end of the primary cot.
1	System	Upholstery - Vinyl - Gunmetal Gray (Standard)	Seamless vacuum formed vinyl material, gun metal gray, provided on the attendant seat, squad bench cushions and CPR cushions.
1	System	Cot Fastener - Floor Plate w Power Source - Stryker	A cot fastener Floor Plate with Power Source shall be center mounted on the floor of the module.
Customer supplied floor plate and power load			
1	System	Cot Fastener Mount - Center (Standard)	The cot fastener shall be center mounted in the patient module.
1	Set	Seat - Attendant Child 3 Point Safety - Gunmetal Gray w Swivel Base - Wise (Standard)	Attendant seat with child safety seat, 3 point harness and swivel base shall be located at the head end of the primary cot.
1	System	Riser - Stainless Steel - Interior	

HVAC SYSTEM

QTY	UOM	PRODUCT NAME	DESCRIPTION
1	System	AC - 12 Volt - Ducted with Bottom Mount Condenser (Standard)	Hoseline brushless 12VDC HVAC system located on the front bulkhead and shall be ducted down the ceiling of the patient compartment.
1	Each	Exhaust Fan	The patient compartment shall be ventilated with fresh outside air via one (1) static intake vent and one (1) power exhaust vent.
2	Each	Cowl Vent	An aluminum cowl vent shall be provided on the exterior to cover the intake vent.
1	Each	Filter - Hepa	A hepa filter shall be installed in the HVAC intake.

WE LOOK FORWARD TO BUILDING THIS AMAZING VEHICLE FOR YOUR DEPARTMENT!