

100' SPLITTER ISLAND ON ALL APPROACHES

120' NON-UNIFORM CIRCULAR ROUNDABOUT WITH 20' CIRCULAR ROADWAY

TREE TO NOT BE DISTURBED


MARLOW UNITED METHODIST CHURCH

SR 17 AT MARLOW RD ALTERNATIVE SKETCH
 COUNTY: EFFINGHAM
 GDOT DISTRICT: 5

	DESIGN SPEED	FUNCTIONAL CLASSIFICATION
SR 17	45 MPH	RURAL ARTERIAL
MARLOW RD	35 MPH	RURAL COLLECTOR

NOT INTENDED FOR CONSTRUCTION, BIDDING, OR PERMIT PURPOSES.

PRELIMINARY SUBJECT TO CHANGE BASED ON FURTHER DEVELOPMENTS FROM CLIENT INPUT AND TECHNICAL REVIEW.



SHEET 1 OF 1

LEGEND

PROPOSED FULL DEPTH PAVEMENT	
PROPOSED CLASS B PAVEMENT	
PROPOSED MILL/OVERLAY CONSTR.	
PROPOSED SIDEWALK	
PROPOSED MEDIAN / C&G	
PROPOSED MOUNTABLE MEDIAN	
PROPOSED LANDSCAPING/GRASS	
ANTICIPATED DISPLACEMENT	
REMOVE EXISTING PAVEMENT & GRADE TO DRAIN	
PROPERTY AND EXISTING R/W LINE	
REQUIRED R/W LINE	
PROPOSED CONSTRUCTION C/L	

ATKINS

Member of the SNC-Lavalin Group

Atkins North America, Inc.
 1600 RiverEdge Parkway NW, Ste. 700
 Atlanta, GA 30328
 Tel: (770)933-0280

Certificate of Authorization #PEF000902
 Expiration date 06/30/2022