



**Quote #:** Q-00620-1  
**Date:** 10/10/2023 9:50 AM  
**Expires On:** 2/29/2024

**Custom Truck and Body Works, Inc.**

*Manufacturers of Custom Emergency Apparatuses*  
 13787 White House Rd  
 Woodbury, GA 30293  
 United States  
 Main Line: 706-655-4300

**SHIPPING**

Andrew Gelmini  
 Forest Park Fire Dept.  
 4539 Jonesboro Road  
 Forest Park, Georgia 30297  
 (404) 366-4720  
 agelmini@forestparkga.gov

**BILL TO**

Forest Park Fire Dept.  
 4539 Jonesboro Road  
 Forest Park, Georgia 30297

Name	Direct Line	E-Mail Address
Jimmy Gill	(706) 977-7095	jimmy@customtruckandbodyworks.com
Payment Terms	Delivery Method	Delivery Terms
Due on Receipt	Pickup at CTBW	120 to 150 Business Days After Receipt of Chassis









*Dear Andrew Gelmini,*

*Custom Truck and Body Works would like to thank you for the opportunity to work with your department on this project. We have prepared this quote based on the information that has been provided to us. We are certain that we can meet or exceed any needs and expectations you may have. Please review the attached documents and if there should be any questions, clarifications or any additional information please do not hesitate to contact me. We look forward to hearing from you soon.*


*Sincerely,  
 Jimmy Gill*



**Type III 14" Ambulance - Chevy G4500**

**\$267,518 Each**


QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
2	Each	Fire Extinguisher - 5Lb w/ Bracket (Standard)	5lb Fire Extinguisher shall be shipped loose.	
1	Set	Mirrors - Power & Heated 2020XG - Velvac		
1	Set	Mud Flaps	Set of heavy-duty, thick rubber material mud flaps shall be as wide as the dual rear wheels.	
1	Each	Spare Tire	A spare tire shall be provided with the chassis.	
1	Each	Alarm - Backup	An audible alarm shall be installed to activate when the vehicle is placed into reverse gear. There shall be installed on the front console and wired through the vehicle electrical system, a momentary cutoff switch to disable the alarm.	
1	Set	Air Horns - Buell		
1	System	Lights - Wig Wag - Chevrolet		
1	Set	Engine Block Heater - Wire - Shoreline	The chassis engine block heater shall be wired to shoreline power.	

#### CHASSIS CONSOLE




QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	Back Up Camera - 7" Monitor Installed On Console	An exterior Back Up Camera With 7" Monitor shall be mounted on the console.	





QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	Inverter - Vanner 1100 (Standard)	A Vanner 1100 watt Inverter with 50 amp battery charger shall be provided.	
1	Each	Inverter - Pre Wire	A pre-wire for installation of the inverter shall be provided in the L2 compartment.	

### L3 COMPARTMENT






QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	L3 Compartment - 3/4" Height	Street Side Rear Compartment Dimensions: H65"x W42"x D20"	<b>Photo Coming Soon</b>
1	Each	Adjustable Shelf - L3 Compartment	A horizontal aluminum adjustable shelf/shelves shall be provided in the L3 compartment mounted on shelf track.	





### R3 COMPARTMENT

QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	R3 Compartment	Curb Side Rear Compartment Dimensions: H72"x W20"x D20"	
2	Each	Adjustable Shelf - R3 Compartment	A horizontal aluminum adjustable shelf/shelves shall be provided in the R3 compartment mounted on shelf track.	
1	Each	Backboard Divider - R3 Compartment	A vertical divider shall be mounted center of the back board compartment.	





QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Set	Lights - ICC Marker - Red & Amber LED	7 LED Red and 7 LED Yellow ICC lights installed on the upper module perimeter to meet DOT requirements.	
1	Each	Light - Stepwell - LED	LED Stepwell light installed at the entry steps of the module.	
1	Each	Lights - Tag Bracket - LED	LED lighting installed at the the tag bracket to meet DOT requirements.	
2	Set	Lights - Docking - 6" Oval White	6" LED lights installed at the rear bumper to provide additional back up lighting.	






**MODULAR EXTERIOR**

QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	Shoreline - 20A/120V - Auto Eject - Yellow Cover (Standard)	A 20 amp automatic power line disconnect system shall be furnished for the vehicle shoreline.	
2	Set	Fenderette - Aluminum (Standard)	Polished aluminum fender flair shall be installed around the rear wheel well openings.	
1	System	Rub Rails - Reflective Chevron (Standard)		
1	Each	Window - Side - Sliding - Dark Tint (Standard)	Tinted high black aluminum framed sliding window is to be centered on the side entry door.	
2	Each	Window - Rear - Fixed - Dark Tint (Standard)	Tinted high black aluminum framed fixed window is to be centered on each rear entry door.	





QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Set	Vinyl Graphics - Star of Life Reflective Package	KKK-Spec reflective SOL package provided with the graphics package. ##Color, style and location to be determined at preconstruction meeting	
1	Set	Vinyl Graphics - Lettering & Decals	Lettering and department decals designed and printed on 3M 680CR reflective material and laminated with UV protective laminate.	
1	Each	Rear Chevron - Reflective	Printed rear chevron that meets the existing fleet/customer specifications. Printed on 3M IJ680CR reflective material. ##Color to be determined at preconstruction meeting	
Red / Gray				
1	Each	Vinyl Graphics - Z Stripe	Printed stripe, in the shape of a "Z", that runs the length of chassis to end of module. Printed on 3M IJ680CR reflective material. ##Color, style and location to be determined at preconstruction meeting	
Matching Gray				




**MODULAR INTERIOR**

QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	Panel - Power - Location - Interior (Standard)	A printed circuit board shall be installed in the interior electrical cabinet behind attendant seat.	
1	Each	Flooring - Gun Metal Gray - Lonplate 3" (Standard)	Lonplate heavy duty floor covering installed above the PVC sub floor, rolled up on each side 3".	
1	Each	Flooring - Composite PVC Sub Flooring	PVC composite sub flooring shall be installed above the aluminum sub floor.	
1	System	Insulation - Polyfiber (Standard)	The modular ambulance body shall be insulated with a non-flammable Polyfiber insulation.	







QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	Seat - CPR		
1	Each	Countertops - White - Soft Edge Trim	Solid Surface material counter tops with soft edge trim at the action and telemetry areas. White in color.	 Soft Edge Trim
1	Each	Cabinet - Plywood - Over Rear Door	Cabinet located over the rear entry door, providing one storage section.	
1	Each	Cabinet - Plywood - Squad Bench Overhead	Cabinet located over the squad bench, divided into two separate storage sections.	
1	Each	Cabinet - Plywood - Glove Box	Cabinet located over the side entry door, providing storage for three glove boxes.	

MODULAR INTERIOR - ELECTRICAL

QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
2	Set	Antenna - Coax	Two [2] 10-gauge power and two [2] ground wires, two [2] RG58U coax cables, and two [2] PL259 connectors.	
2	Each	Outlet - 12V	12 Volt DC 20 Amp cigar style outlets will be located in the action area and in the advanced life support cabinet. ##Exact location & quantity can be changed at pre-construction meeting	
3	Each	Outlet - 110V - Lighted	110 Volt AC GFI duplex lighted outlets will be located in the action area, the telemetry, as well as the advanced life support cabinet. ##Exact location & quantity can be changed at pre-construction meeting	
1	Each	Outlet - Oxygen - Single	A single O2 outlet provided at the head end of the squad wall. ##Exact location & quantity can be changed at pre-construction meeting	

QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
2	Each	Grab Rail - Ceiling - 80" Yellow (Standard)	1.25" diameter x 80" yellow grab bars shall be provided and securely fastened to the ceiling over the primary cot and over the squad bench. ##Exact location & quantity can be changed at pre-construction meeting	
3	Each	Grab Handle - 18" Yellow (Standard)	1.25" diameter x 18" yellow grab bars shall be provided at each entry door. ##Exact location & quantity can be changed at pre-construction meeting	
3	Each	Grab Handle - Interior V Style - Yellow (Standard)	V-Style yellow grab handles shall be provided on the side and rear entry doors.	

#### MODULAR INTERIOR DETAILS

QTY	UOM	PRODUCT NAME	DESCRIPTION	IMAGE
1	Each	Suction - Rico - Action Area (Standard)	A RICO RS4X disposable aspirator will be installed in the action area and connected to the vacuum inlet by a quick connect coupler.	 RICO SUCTION
2	Set	IV Hanger - Ceiling Mount (Standard)	IV Hangers will be recessed in the ceiling over the head and foot end of the primary cot.	 ALLSIS
1	System	Upholstrey - Vinyl - Desert Rose	Seamless vacuum formed vinyl material, desert rose, provided on the attendant seat, squad bench cushions and CPR cushions.	 Desert Rose
1	System	Cot Fastener - Power Load - Stryker	A Power Load cot fastener shall be center mounted on the floor of the module.	 stryker
1	System	Cot Fastener Mount - Center (Standard)	The cot fastener shall be center mounted in the patient module.	
1	Set	Seat - Attendant Child 3 Point Safety - Desert Rose w Swivel Base - Wise	Attendant seat with child safety seat, 3 point harness and swivel base shall be located at the head end of the primary cot.	 WISE