



**DAF Concrete**  
Reliability is our promise!

# QUOTE

REMIT TO :  
212 Hicks Drive  
Marietta, GA, 30060  
P: 770.629-4036  
Cell: 404.433.8824

DATE December 11, 2024  
QUOTE  
Customer ID Rochelle Dennis  
[rdennisforestparkga.gov](http://rdennisforestparkga.gov)

TO **CITY OF FOREST PARK**

SALESPERSON	PO	PAYMENT TERMS	DATE OF COMPLETION
Antonio Sanchez			

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	LINE TOTAL
<b>200 Metcalf Road Extension</b>					
	Catch Basin Repair	1	LS	\$ 3,000.00	\$ 3,000.00

SUBTOTAL	\$3,000.00
SALES TAX	
TOTAL	<b>\$3,000.00</b>


DAF Concrete, Inc.  
**THANK YOU FOR YOUR BUSINESS!**

**Proposal for Storm Drain Repair Services**

**To:** City of Forest Park

**From:** FemPro'z

**Date:** 1/09/2025



---

**Subject:** Proposal for Repair of Storm Drain System

---

**Description of Work:**

FemPro'z, LLC is pleased to submit this proposal to the City of Forest Park for the repair of the storm drain system located at 200 Metcalf Rd. Forest Park, Ga. The proposed work includes the following:

1. **Curb and Gutter Repair:** Restoration of any damaged curbs and gutters to ensure proper drainage flow and structural integrity.
2. **Manhole Cover Replacement:** Replacement of manhole covers to maintain safety and accessibility.
3. **Double Wing Storm Drain Cover Replacement:** Installation of a new double wing storm drain cover to restore functionality and compliance with safety standards.
4. **Throat/Wall Repair:** Repairs to the throat and wall of the storm drain to prevent further deterioration and ensure proper water flow.
5. **Pipe Column Installation:** Installation of a reinforced pipe columns to provide additional structural support and mitigate future damage risks.

---

**Special Considerations:**

1. **Unknown Damages:** Please note that the full extent of the damage cannot be assessed until the demolition of the damaged structure and removal of all debris have been completed. Should additional damages be discovered during this process, these changes will be invoiced separately, with prior approval from the City of Forest Park.
2. **\* Material Specification:** The repair work will utilize D.O.T. AirMix grade concrete, which is specially designed for durability and compliance with Department of Transportation standards. This ensures the longevity and resilience of the repaired structures.
3. **Reinforcement:** Pipe columns will be added to the interior wall to add additional structural support to the drain cover top

---

**Quotation:**

Line Item	Description	Estimated Cost
Demolition and removal	Demolish, haul away, disposal	\$ 1,029.60
Curb and Gutter Repair*	Restoration of curbs and gutters	\$ 1,800.00
Manhole Cover Replacement	Replacement with new cover	\$ 838.37
Repair In-Kind Drainage Structure *	Repair storm drain <u>cover</u> (form, reinforce & pour)	\$ 4,803.08
Repair In-Kind Drainage Structure w/reinforcement	Repair storm drain <u>throat/interior wall</u> damage, add reinforce with pipe columns	\$ 2,744.62
Traffic Control	2 flagmen, 3 traffic weighted barriers, cone	\$3,983.60
		<b>\$15,199.27</b>

**Project Timeline:**

Repairs are to be made in multiple pours. Wall pour will have to cure prior to the drain cover pour, adding additional time to completion (2 days/pour). The estimated duration for this project is 3-4, pending approval and weather conditions. A detailed schedule will be provided upon acceptance of this proposal.

---

**Terms and Conditions:**

1. All work will comply with local codes and regulations.
  2. A signed agreement and notice to proceed are required before commencing work.
  3. Payment terms: **\$4,559.78 (30%)** initial draw. **\$10,639.49** Balance due upon completion.
- 

We appreciate the opportunity to work with the City of Forest Park on this important project. Should you have any questions or require further clarification, please do not hesitate to contact us.

Sincerely,

**Mahogany Taylor- G.C.**

Director

**FemPro'z**

678.820.8323 Office

admin@femproz.com

**Nikki Bogus- G.C.**

Construction Supervisor

**FemPro'z**

678.820.8323 Office

admin@femproz.com

