

STEVENS ELECTRICAL, INC.

10157 PINEY MT. ROAD. SW
FROSTBURG, MD 21532

Estimate

Date	Estimate #
1/23/2025	1226

Name / Address
City of Frostburg 37 S Broadway St Frostburg MD 21532

			Project
Description	Qty	Cost	Total
Project: Bureau of Mines Storage Building Change Order/Electric Heat/50A outlets Supply labor and material for the following scope of work: 1) Install 3' QMark electric baseboard heater Model #2543 with a 2-pole baseboard thermostat in the restroom and utility storage room. 2) Install a 3/4" EMT conduit with (3) #6 THHN and (1) #10 ground to the following locations: Far back wall ceiling by the egress door, opposite corner behind the utility storage room. Install that conduit/wire to a welding outlet mounted at 4' AFF. Provide (2) Square D Q0205 breakers in the new panel dedicated to each location. 3) Terminate and test upon completion.		3,575.00	3,575.00
Thank you for the opportunity to provide you with this quote.		Total	\$3,575.00

Customer Signature

