

GARDEN CITY POLICE DEPT. RENOVATION



9/6/2024

CONCEPTUAL BUDGET Based on Progress Set 3/23/24

Project Duration (Months)	6
Building Area (Square Feet)	7145
Site Area (acres)	0.16

HARD COST

SUBTOTALS

Div. 01 General Conditions		\$	312,000.00	\$	43.67
01	General Conditions	\$	312,000.00	\$	43.67
Div. 02 Site Work		\$	216,828.11	\$	30.35
02	Basic Site Means and Methods	\$	25,000.00	\$	3.50
02	Building Excavation	\$	33,750.00	\$	4.72
02	Survey	\$	10,000.00	\$	1.40
02	Wind Weather Protection	\$	15,000.00	\$	2.10
02	Demo of Exterior Site/Regrading and New Topsoil, Site Balance	\$	82,423.26	\$	11.54
02	Utility - Sanitary, Water (fire line not included)	\$	65,000.00	\$	9.10
31	Landscaping and Irrigation report	\$	7,500.00		
02	Demo of Exterior Metal Car Port	\$	14,969.00	\$	2.10
02	Demo of Fence	\$	4,000.00	\$	0.56
02	Demo Shed	\$	4,802.58	\$	0.67
02	Demo Gate		Included Above		
02	Demo Connection Wall	\$	1,221.00	\$	0.17
02	Demo Exterior Door	\$	1,000.00	\$	0.14
02	Demo Roof Section		Included Above		
02	Demo Old Structural Concrete		Included Above		
02	Demo Stair Entryway + New Pavement Locations	\$	547.27	\$	0.08
02	Interior Demolition			\$	-
02	Doors (Protect)	\$	500.00	\$	0.07
02	Demo Interior Partitions	\$	9,865.00	\$	1.38
02	Toss Out Water Heater		Included Above		
02	Demo interior Chain-link Fence		Included Above		
02	Demo Work Bench		Included Above		
02	Demo Structural Beams		Included Above		
02	Demo Flooring and ACT		Included Above		
02	Haul out any light fixtures		Included Above		
02	Haul out any MEP		Included Above		
Div. 03 Concrete		\$	176,553.88	\$	24.71
03	Site Concrete Package	\$	45,000.00	\$	6.30
03	Sidewalk/ Entry Walkway	\$	1,240.36	\$	0.17
	ADA Ramp instead of stairs on E side of building	\$	2,813.52	\$	0.39
03	Exterior Asphalt at Man Door and Roll Up Door (propose concrete)		Included Above		
03	Foundations Package - spread footings frost depth	\$	75,000.00	\$	10.50
03	2.5' Dia x 4' Deep Cylindrical Footers (18) (1.8CY)		Included Above		
03	Wall Footing		Included Above		
03	Rebar Package		Included Above		
03	SOG	\$	52,500.00	\$	7.35
03	Rebar Package WW Mesh		Included Above		
Div. 04 Masonry		\$	18,500.00	\$	2.59
04	New Brick Wainscot	\$	15,600.00	\$	2.18
04	Grout		Included Above		
04	Stucco (Foam Interior) Cornice	\$	2,900.00	\$	0.41
Div. 05 Metals		\$	84,495.42	\$	11.83
05	Structural Steek Pkg. Misc. Metals	\$	38,398.42	\$	5.37
05	8x2.5x16Ga Z purlins	\$	5,000.00	\$	0.70
05	Baseplates and Anchor Bolts	\$	28,890.00	\$	4.04
05	Gussets 3/8" A36		Included Above		
05	Misc. Metals	\$	10,457.00	\$	1.46
05	Flashings	\$	1,750.00	\$	0.24
Div. 06 Woods		\$	344,261.00	\$	48.18
06	Rough Carpentry - Backing Blocking	\$	28,580.00	\$	4.00
06	Wood Framing pkg	\$	262,500.00	\$	36.74
06	Bathroom Casework	\$	35,228.00	\$	4.93
06	Work Stations	\$	3,600.00	\$	0.50
06	CT for Work Stations, Breakroom, restrooms	\$	11,500.00	\$	1.61
06	Tables		Included Above		
06	42"x20" Bench		Included Above		
06	Work Stations		Included Above		
06	Table in Hard Room		Included Above		

9/6/2024

CONCEPTUAL BUDGET
Based on Progress Set 3/23/24

Project Duration (Months)	6
Building Area (Square Feet)	7145
Site Area (acres)	0.16

HARD COST

SUBTOTALS

	Cold Storage Shelving		
06		\$ 951.00	\$ 0.13
06	3/4" Fire Rated Plywood Backing (105)		
06	Would they want evidence room storage	\$ 951.00	\$ 0.13
06	PD Equipment Storage Room	\$ 951.00	\$ 0.13
06	Gun Rack	\$ 951.00	\$ 0.13
Div. 07 Envelope		\$ 217,866.87	\$ 30.46
07	EIFS (AGPRO drawings)	\$ 32,050.00	\$ 4.49
07	Weather Barrier	\$ 9,200.00	\$ 1.29
07	Vapor Control Barrier	\$ 4,700.00	\$ 0.66
07	Flat Roof System	\$ 61,043.72	\$ 8.54
07	Sloped Roofing System	\$ 70,853.00	\$ 9.92
07	Batt Insulation	\$ 27,146.00	\$ 3.80
07	Joint Sealants	\$ 12,674.15	
Div. 08 Openings		\$ 130,353.04	\$ 18.24
08	Wood Interior Doors (Matching Existing) (Sliced White Maple Priced)	\$ 39,714.00	\$ 5.56
08	Installation	\$ 12,000.00	
08	Exterior Windows	\$ 22,000.00	\$ 3.08
08	Exterior Hardware	\$ 2,000.00	
08	Steel Coiling Door	\$ 12,683.00	\$ 1.78
08	Chain Fence Door	\$ 1,890.00	\$ 0.26
26	Day Lighting (Talked in Video & Narrative Not called in Drawings)	\$ 1,466.04	
08	Transaction Slot w/ BP Glass	\$ 38,600.00	\$ 5.40
Div. 09 Finishes		\$ 199,044.00	\$ 27.86
09	Temp Protection Interior Finishes -	\$ 10,000.00	\$ -
09	Drywall	\$ 60,067.50	\$ 8.41
09	Suspended Ceilings -		\$ -
09	2x2 ACT Ceilings	\$ 24,745.00	\$ 3.46
09	Gyp Ceilings	Included Above	
09	Flooring -		
09	Carpet	\$ 15,427.00	\$ 2.16
09	Tile Flooring - Bathrooms (Currently LVT)	\$ 16,860.00	\$ 2.36
09	Sealed Concrete -	\$ 1,331.70	\$ 0.19
09	Wall Base	\$ 25,481.00	\$ 3.57
09	Moisture Mitigation in Tile Flooring Locations	Included Above	
09	Back Splashes	\$ 2,250.00	
09	Painting -	\$ 28,580.00	\$ 4.00
09	Repairing of Existing and New Conditions	Included Above	
09	Wall Base	\$ 2,345.00	
09	Interior Means and Methods	\$ 10,500.00	\$ 1.47
09	Acoustical Treatments - Hard and soft intero.	\$ 1,456.80	\$ 0.20
Div. 10 Specialties		\$ 60,642.00	\$ 8.49
10	Lockers 5 in Each Bathroom	\$ 11,408.00	\$ 0.90
06	Evidence Storage (Rm 105)	\$ 7,500.00	
10	ADA Bathroom Grab Bars showers and restrooms	\$ 6,409.00	
10	New Chain link Fence	\$ 5,850.00	\$ 0.82
10	Appliances	\$ 5,000.00	
10	Refrigerator	\$ 4,300.00	
10	Signage Package	\$ 20,175.00	
Div. 21 Fire Sprinkler		\$ 50,015.00	\$ 7.00
21	Fire Sprinklers	\$ 50,015.00	\$ 7.00
Div. 22 Plumbing		\$ 176,217.50	\$ 24.66
22	Demo	\$ 10,717.50	\$ 1.50
22	Plumbing Pkg.	\$ 145,500.00	\$ 20.36
22	Showers	Included Above	
22	Shower Inserts Connection	Included Above	
22	Sinks	Included Above	
22	Mop Basins	Included Above	
22	Floor Drain	Included Above	
22	Toilets	Included Above	
22	Kitchen Sink	Included Above	
22	New Water Heater	\$ 20,000.00	\$ 2.80
22	Piping for New Water Lines	Included Above	
22	Waste Lines and Vent Piping	Included Above	

9/6/2024

CONCEPTUAL BUDGET

Based on Progress Set 3/23/24

Project Duration (Months)	6
Building Area (Square Feet)	7145
Site Area (acres)	0.16

HARD COST**SUBTOTALS**

Div. 23 HVAC		\$	206,287.50	\$	28.87
23	Demo:	\$	30,000.00	\$	4.20
23	HVAC Pkg.	\$	168,787.50	\$	23.62
23	TAB Report	\$	7,500.00	\$	1.05
Div. 26 Electrical		\$	302,150.00	\$	42.29
26	Demo:	\$	12,000.00		
26	Gear Distribution	\$	19,350.00	\$	2.71
26	Lighting and Controls	\$	69,400.00	\$	9.71
26	Generator 100 kw	\$	42,000.00	\$	5.88
26	Branch Power	\$	104,000.00	\$	14.56
26	Mechanical Power	\$	14,100.00		
26	Owner Equipment Power Connection	\$	6,300.00		
26	Low Voltage Rough	\$	8,000.00	\$	1.12
26	Fire Alarm	\$	27,000.00	\$	3.78
Div. 27 Low Voltage Systems		\$	81,435.00	\$	8.60
27	Structured Cabling	\$	21,435.00	\$	3.00
27	Security Access Control	\$	15,000.00	\$	2.10
27	Video Monitoring CCTV	\$	10,000.00	\$	1.40
27	Audio Visual	\$	15,000.00	\$	2.10
Div. 00 Indirect		\$	467,672.80	\$	65.45
0	Consumable Tax	\$	32,199.24	\$	0.03
0	Use Tax			\$	0.07
0	Insurances	\$	49,898.01	\$	0.02
0	Overhead & Profit	\$	105,844.27	\$	0.04
0	Construction Contingency	\$	105,844.27	\$	0.04
0	Design & Escalation Contingency	\$	151,206.10	\$	0.05
0	Performance & Payment Bond	\$	22,680.92	\$	0.01

TOTAL CONSTRUCTION COST \$ 3,024,122

COST / SF \$ 423.25 \$ 3,024,122.00