



**Vermont Electrical Contracting LLC.**

423 South Main St  
St. Albans, VT 05478  
P: 1-802-528-5332  
F: 1-802-528-5356

March 3, 2025

**ELECTRICAL PROPOSAL**

Project: Georgia Library  
Re: Additional Receptacles  
Date of Quote: 3/3/25

**Scope of Work:**

- Furnish Vermont State Electrical Permit.
- Furnish and install a total of (42) 20amp TR duplex receptacles throughout the library. Locations include the reception desk, meeting room, open area, bathrooms, office, and storage room. Final locations determined on site at time of install.
- Furnish and install new power pole at the reception desk.
  - o Move the existing data line from the wall to the power pole and under the desk. Extension of the wire may be required.
  - o Some new receptacles will be powered from existing circuits when available. Others will be connected to new power circuits from the electrical room.
- Type MC cable will be used above the ceilings and in the electrical room. We will cut boxes into the wall and fish down the wires where possible. Some areas may require surface mounted pipe or wiremold.
- Furnish GFCI protection at all new receptacles that fall under the GFCI protection requirements by NEC.
- Test and label all new receptacles and update the panel schedules.
- Work is to be performed during normal operating hours of 7-3:30 Monday-Friday.

Project Total: \$12,500.00

Thank you for the opportunity to work with you on this project. Please do not hesitate to call with any questions.

Sincerely,

Sean McCabe  
[Sean@vermontelec.com](mailto:Sean@vermontelec.com)  
802-557-1141