ISSUED FOR CONSTRUCTION 4/26/24

ABBREVIATIONS:

EX	EXISTING
TBR	TO BE REMOVED
TBRC	TO BE RECONSTRUCTED
TBRL	TO BE RELOCATED
TRM	TO REMAIN
TBS	TO BE SALVAGED
TYP	TYPICAL

LEGEND

- asphalt area to remain.
- -Asphalt area to be removed/reconstructed.
- -Structures to remain.
- -Structure to be demolished
- -Gravel areas to be removed/replaced. (All Gravel)
- -Concrete to remain.
- -Concrete to be removed/replaced.

NOTES:

1. Refer to specifications for demolition requirements.
2. Refer to the MEP plans for additional utility details and notes.
3. Refer to the Architectural and Structural plans for additional building demolition and coordination details.
4. Field verify location of existing underground utilities in the work area and protect the utilities to remain during construction.
5. Coordinate with utility companies before working near their utilities.
6. Existing utilities are in use. Maintain utility services unless shutdown authorized by owner and utility.
7. All existing Conex boxes, dumpsters, and trailers are to be relocated and or removed from the site by the owner. Contractor to coordinate with the owner.

HORIZONTAL SCALE IN FEET

0 10 20 40 60 80

1" CONTOUR INTERVAL

0 20

PROPERTY OF GEORGIA SELF STORAGE LLC

PROPERTY OF YING & YANG LLC AND GEORGE A LAMPHERE

PROPERTY OF NORTHWEST VT SOLID WASTE MANAGEMENT DISTRICT

PROPERTY OF B & T PROPERTIES LLC

MORSE DRIVE

SETBACK 75'

SETBACK 30'

BROOK SETBACK 200' DEER

(W O O D E D)

VT State Plane

Northwest VT Solid Waste Management District
Georgia, VT

Expansion Project

Morse Dr.
Georgia, VT

Existing Conditions & Demolition Plan

CIVIL

C-2

SHEET 2 OF 5

CCE CROSS CONSULTING ENGINEERS, P.C.
103 Fairfax Rd.
St. Albans, Vermont 05478
Tel. 802-524-2113
Fax. 802-524-9681

© copyright 2024
Cross Consulting Engineers, P.C.

STATE OF VERMONT
PETER J. GAGNON
LICENSED PROFESSIONAL ENGINEER
No. 9999

PROJECT: 21001
DATE: March 26, 2024
DESIGN: NRB
DRAWN: NRB
CHECKED: PJG
APPROVED: PJG

S:\2021 Projects\21001 - NWSWD - Georgia\Current\C-2 Existing Conditions & Demolition Plan.dwg Plotted: 4/25/2024 12:37:03 PM