

Iron Oakes Fencing

29208 Eden Loop Road 218-247-7219 Phone
Bovey, MN 55709 218-259-8490 Mobile

JOB ESTIMATE

Date: 23-Aug-23

Grand Rapids Parks & Recreation
ATT Dale Anderson, Director

Date of original estimate:

Phone 326-7604

danderson@grandrapidsmn.gov

Install 380' of 5' high outfield fence in an arc at the East Elementary site in Grand Rapids, MN

ITEMIZED ESTIMATE: TIME AND MATERIALS

AMOUNT

Materials and Installation:

Line posts 2" OD x 9' x SS20 galvanized steel; Terminal posts 2 1/2" OD x 10' x SS20 galv steel; Top and bottom rail 1 5/8" OD x SS20 galv steel; Fabric 2" x 6' x 9 ga x KK galvanized chain link.

Gates: none

Posts driven 48", 10' 0" or less on center. There will be a bottom rail with the chain link fabric tie-wired to the rail at the bottom diamond. The outfield fence will be an arc, equidistant from home plate at 210'.

All materials and labor:

8,421.00

TOTAL ESTIMATED JOB COST

\$8,421.00

This is an estimate only, not a contract. This estimate is for completing the job described above, based on our evaluation. It does not include unforeseen price increases or additional labor and materials which may be required should problems arise. We will contact Gopher One Call to locate underground utilities; the customer is responsible for locating any private utility lines such as LP gas, wiring to garage from house, etc.

Payment Requirements: One half down, balance upon completion. Once signed, this estimate becomes a contract.

Ed Torconi

(Iron Oakes Representative)

8-23-23

(Date)

(Customer Signature)

(Date)

(Customer Signature)

(Date)