



TRUCK EQUIPMENT

November 22, 2023

Kevin Koetz
Public Works Superintendent
City of Grand Rapids
500 SE 4th Street
Grand Rapids, MN 55744-2662
Office: 218-326-7659
Mobile: 218-398-5201

Propoasl for Bonell Commander Dump Body, Hook lift Hoist and Snow & Ice Equipment

| Item | Description | |
|--------------|--|--------------|
| MCR-14-S2 | 14' Bonnell Commander MCR Series Stainless Steel Multi Purpose Dump Body (201 Stainless Steel) 96" wide OD 7 ga. 201 SS Truncated anti Prism Sides, 26 degree conveyor load angle 7 ga" a 201 SS Front 51.9" 6 panel 7 ga 201SS Tailgate Removable floor, 30.5" wide Self cleaning pintle style chain 201SS Stainless Steel Rear post with S/T/T light cutouts One year limited Warranty | \$ 55,268.00 |
| 2.0 | Stellar Slider40, 54"-62" hydraulic adjustable hook height, designed for 130" to 144" CT chassis. Body lengths 12'-16', Rated Capicity 40000# | \$ 41,995.00 |
| 9.2 | Installation of Stellar Hook Lift | \$ 6,035.00 |
| 9.3 | 61363 Bumper, reinforced to accept pintle hitch 90K. (pintle not included).- LED light kit (FMVSS108 compliant) and backup alarm is included. Stellar-AutoTarper ready. | Deleted |
| 9.3A | Labor to install bumper | Deleted |
| 1.49 | M4000 SCS poly fenders for tandem axle chassis, S/S bolt on brackets inst | \$ 1,925.00 |
| 9.6 | Skid 8574, Body attachment | \$ 2,860.00 |
| 9.7 | Roller kit 24678 | \$ 1,015.00 |
| NCI | Ez-Connect S14 Electrical Connections, 1 truck side female, 1 equipment Male Plugs, 14 Connections Installed | \$ 630.00 |
| BON-012658SS | 201 STAINLESS STEEL CAB SHIELD-NORTH DAKOTA STYLE | \$ 3,148.00 |
| BTE-CSUP | STATIONARY CABSHIELD UPRIGHTS AND LABOR TO INSTALL | \$ 1,275.00 |
| | SS Fold Down Box ladder, installed | \$ 660.00 |
| | Air Trip Gate | Inc |
| | 540 GALLON TANK SYSTEM- 201 STAINLESS BRACKETS, 13' THRU 16' with standard 1 1/2" plumbing kit | \$ 5,112.00 |
| | Tank Installation brackets | \$ 5,517.00 |
| | Installtion of prewet system | \$ 1,440.00 |
| C11320 | Internal Feedback Sensor Providing 60 Pulses per revolution (use on chain conveyor models only) | \$ 880.00 |
| 11.7 | VariTech Direct Slurry Closed Loop Power Unit only (NO CONTROL) SEE HYDRAUICS FOR EXTRA SECTION (1192924) | \$ 3,395.00 |
| | 1 1/2" quick fill kit | \$ 144.00 |
| | 1/1/2" cross fill kit | \$ 293.00 |
| | two Nozzle Spray Kit | \$ 248.00 |
| | 14' Sub-floor with clean-out door, 201 SS | \$ 2,525.00 |
| 1.66-67 | Mud Flaps Front and Rear of Rear Axles | \$ 180.00 |
| | Conveyor Cover plate (Summer Cover) 1/4" AR 400 Optional | \$ 1,822.00 |
| C10618 | Reciever SPinner Assembly 201 Stainless Steel | \$ 1,688.00 |

| | | | |
|----------------------|---|---------|------------|
| 1.00 | Labor/materials to add Receiver spinner mount tube to rear wing Brace | \$ | 325.00 |
| 9.00 | Force America Add-A-fold MPJC-Ultra Load Sensing Hydraulics with SCC-6100 Gen4 Salter Control. Six sections, Hoist, Plow 2X , Wing 2X, and sander, Force America PVWH45L 6.0 cid Load sense Pump. | \$ | 26,830.00 |
| 9.20 | Adder to Upgrade valve for 3500 PSI Hooklift. Price includes the Jib section | \$ | 1,844.00 |
| 9.80 | Repto Drive line Compnents | \$ | 975.00 |
| | Counter balance valve for wing | Incl | |
| | Add section for hydrualic closed loop prewet/Slurry | \$ | 1,125.00 |
| | Add sections for hydrualic reversible underbody and Hyd Buffer bar | \$ | 3,375.00 |
| | adder for 4 stick control | \$ | 625.00 |
| 9.33 | Adder for Slurry Feedback. | \$ | 650.00 |
| 9.22-23 | Seat mount kit (Steel) | \$ | 200.00 |
| 9.77 | Adder for Auto Reverse Scraper Lift/Auto Recall. | \$ | 375.00 |
| 9.830 | 45 gallon SS Stationary cab shield mount reservoir with tank filter and accessoires | \$ | 2,782.00 |
| 9.910 | 11 Section Stainless Steel Vertical Enclosure and Brackets, 9689A011-SS | \$ | 2,998.00 |
| 9.33 | return line manifold | \$ | 80.00 |
| 9.10 | Installation of Hydraulic System | \$ | 8,195.00 |
| 9.11 | Adder for ARC Wireless Temp Sensor. | \$ | 688.00 |
| 9.70-71` | Two Male-Female Stuchi 4 port 1/2 Couplers & parking Plates)) (Body and Front Plow) | \$ | 3,252.00 |
| Falls IBR-11A | 11' Reversible scraper 1" molboard | \$ | 14,089.00 |
| | Install Underbody | \$ | 2,555.00 |
| 5.0-1-24 | Falls 46B Falls Quick Hitch | \$ | 3,089.00 |
| 5.1(1) | Installation of Hitch (includes painting of one way plow) | \$ | 2,655.00 |
| | Falls PR1243 Plow Reversible plow and pushbar for 46B hitch | \$ | 11,665.00 |
| | Falls Snow deflector | \$ | 502.00 |
| | Screw adjustable parking stand | \$ | 382.00 |
| | End Markers | \$ | 151.00 |
| SDLP-10 | Falls SDLP-10 Postless Rear mount wing with all standard Equipment | \$ | 11,840.00 |
| | Rear lift | \$ | 638.00 |
| | Installation of Rear Mout wing | \$ | 5,840.00 |
| 4.16 | hydraulic nitrogen push bar | \$ | 3,074.00 |
| 7.00 | Holland PH400 air cushion pintle hitch, installed | Deleted | |
| 1.102-103 | truck Light LED Plow Lights mounted aluminum hood mounted bar | \$ | 1,825.00 |
| 1.110 | Whelen SYS410D Linear LED Strobe Light Systems with Stainless Steel Rear Housings. Two Stainless Steel Micro 400 with 400 series light heads | \$ | 3,835.00 |
| 1.138 | Install DOT Strobe system | \$ | 1,100.00 |
| 1.104 | LED <u>wing S</u> ander Light, installed (ADDED WING LIGHT) | \$ | 450.00 |
| | Total package as proposed | \$ | 256,064.00 |
| NCI | Curry CW3D 3000 Gallon Water tank on skid for Steller hook lift | \$ | 73,995.00 |
| | See attachedd Specs | | |
| | Options | | |
| | Adder for eack extra Stellar Skid and Wheels | \$ | 3,875.00 |
| | Hot Belt over chainon conveyor | \$ | 6,915.00 |

| | |
|--|-------------|
| Adder for Oilgear FASD60-HP-L-CS 7.94 CID Load Sense Pump. (3750 PSI) (Note: This will derate the hooklift capacity but provide extra oil at the 9.47 low end) | \$ 1,773.00 |
|--|-------------|

Pricing from current MN DOT State Contract valid

Jim McLaughlin, Sales

YOUR TRUCK EQUIPMENT HEADQUARTERS

1-800-232-3787

(218) 233-8681

Fax 218-233-9548

3804 Hwy 75 North

Moorhead, MN 56560

email:jimmc@bertsonline.com