



QUOTATION FORM

Grand Rapids, MN
Rain Garden Inlet Improvements - 2024

Submit quotation form to Matt Wegwerth PE, City of Grand Rapids, 420 North Pokegama Avenue, Grand Rapids, MN by 3:00 pm on Wednesday, May 1st, 2024. Quotes can be mailed, hand delivered or emailed. If mailed or hand delivered, quote should be submitted in a sealed envelope to the City Engineers office:

Quote package shall include the following:

1. Quotation Form
2. Special Provisions
3. Location Map
4. Rain Guardian Bunker Details

All spaces of the quotation form shall be filled in. The quote must be in a sealed envelope labeled "2024 Rain Garden Inlet Improvements".


Project Description: The project includes installation of Rain Guardian Bunkers at nine (9) locations around the Crystal Lake roundabout.

Project will be completed on a lump sum basis, based on the location map, details and the estimated following quantities:

STATEMENT OF ESTIMATED QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
1	REMOVE CONCRETE APRONS	LS	1
2	INSTALL RAIN GUARDIAN BUNKER	EACH	9
3	INSTALL CONCRETE APRON	EACH	9
4	TRAFFIC CONTRL	LS	1
5	EROSION CONTROL	LS	1

Total Lump Sum Bid: \$ 39800.00

We, the undersigned, doing business as TNT Construction Group have carefully examined the Quotation Documents and the site of the proposed work, and are familiar with all of the conditions, laws and regulations surrounding the construction of the proposed project including the availability of materials and labor. We hereby propose to the City of Grand Rapids, MN to furnish all labor, materials, equipment, skills and facilities for the complete construction of the 2024 – Rain Garden Inlet Improvements as described herein. The lump sum price shown includes sales tax and all other applicable taxes, permits and fees.

Dated this 1st day of May, 2024
Name of Company TNT Construction Group
Signature of Authorized Representative 
Printed Name of Authorized Representative Danielle Ellison
Title of Authorized Representative PM
Legal Address 40 Lamb Rd 63 Grand Rapids
Business Phone 218-326-1881

SPECIAL PROVISIONS

General:

1. EJCDC Standard General Conditions of the Construction Contract shall apply to the project.
2. All materials shall be in accordance with applicable building codes and local specifications.
3. Rain Guardian bunkers shall be provided by the contractor and installed per manufacturer's details and include all associated appurtenances.
4. Existing curb and gutter shall not be disturbed. Concrete apron shall be installed per Concrete Apron Detail
5. The Work may not begin until June 1, 2024 and will be substantially completed on or before August 30, 2024
6. The Work shall be coordinated with local community events. Traffic closures shall not impact Tall Timber Days, Classic Car show and/or the Itasca County Fair. Other events may be impacted and shall be coordinated around.
7. Contractor shall complete rough grading around each site. City will place topsoil, seed and erosion control
8. Contractor shall be responsible for site cleanup
9. Traffic control plan must be submitted to the City and approved prior to starting the work. Closures may be allowed assuming proper signage.
10. Contractor shall provide erosion control as necessary
11. Liquidated damages shall be set at \$300 per day for every day after the completion dates that the project is not complete.
12. Contractor will be required to submit a City Stormwater permit. Fee will be waived.