

City of Grand Rapids

Fire Hall----((Server room))

All Total=== \$4600

---Work to be done--- add (5)120 volt 30 amp circuits and (5)30 amp twistlock locations in server room...

---add emergency light in server room

---need dedicated 20 amp circuit,, fire suppression

---possibly move (1)outlet outside of room and into inside

--- run bonding wire between existing racks

Supplies--- #10thhn 1200 ft

(2)runs of ¾"emt 70 ft--- ¾"unistrut---straps and conn, coup

(5)seimans 30 amp 120 volt bolt on breakers

All 4 squares,, slb,, Industrial raised covers, ground tails, twistlock recpts((L5R30),

Tony Bodin

Tru North Electric

218-244-3494