

Minnesota Petroleum Service, Inc. 682 39th Ave NE Minneapolis, MN 55421 763-780-5191 F:763-780-5472

"Service After The Sale" <a href="www.mnpetro.com">www.mnpetro.com</a> <a href="mblazevic@mnpetro.com">mblazevic@mnpetro.com</a>

To: Everett Baumgarner

Grand Rapids Airport - 1500 7th Ave. SE. Grand Rapids, MN 55744

**AV Gas Quote** 

**Quote #: Date:** 14-Feb-2022

DESCRIPTION QTY PRICE AMOUNT

<u>SCOPE</u>: Transfer (1) existing AV gas hose reel to new location on new concrete pad near tank. Make new piping connections from tank to hose reel cabinent. Close to pipe ends in place with slurry mix (will not fill entire pipe). \*\*\*project bid under the assumption that local fire will approve new location of hose reel - if not, pricing will need to be adjusted\*\*\*

## **MATERIALS:**

| (2) 7" Bollard   | 2 | \$375.00   | \$750.00   |
|--|---|------------|------------|
| (1) Solenoid Valve   | 1 | \$998.00   | \$998.00   |
| (2) Braided Flex Lines   | 2 | \$264.00   | \$528.00   |
| Misc. black pipe, fittings, unions.  | 1 | \$1,824.00 | \$1,824.00 |
| Materials Subtotal:  |   |            | \$4,100.00 |
| Materials Tax: 6.875%  |   |            | \$281.88   |
| Labor/MN Blue: Drain (1) existing AV gas line for pipe closure.  | 1 | \$1,760.00 | \$1,760.00 |
| <b>Labor/MPS:</b> Remove existing transition sump in order to fill pipe in place. Bobcat and forks (to transport hose reel to new location). Fill each end of pipe to the best of our ability so the line is closed in place. Relocate (1) existing hose reel and meter box from front gate and move back towards tank. Install necessary piping, fittings, (1) solenoid valve, and unions to make new connectons from tank to existing hose reel. | 1 | \$7,876.00 | \$7,876.00 |
| Hotel / Per Diem:  | 1 | \$775.00   | \$775.00   |

| Labor/Electrical: disconnect and reconnect power to (1) AV Gs submersible using existing conduit.  Disconnect and reconnect power to AV gas hose reel using existing circuitry. | 1 | \$3,405.00 | \$3,405.00 |
|---|---|------------|------------|
| <b>Labor/Concrete:</b> Pour new pad for (1) existing pump near existing AV Gas tank. Set and pour (2) new bollards.   | 1 | \$4,400.00 | \$4,400.00 |
| Mobilization  | 1 | \$1,253.00 | \$1,253.00 |

Total For the above: \$23,850.88

**EXCLUSIONS**: Unmarked public utility repairs. **Any repairs to existing AV Gas reel and meter cabinent**. Private Utility Repairs Including but not limited to sprinkler lines and heads, conduits, wiring, private utility lines. Shoring. Dewatering. Permits. **Electrical (other than listed)**. **Any other tank top items not listed above.** Environmental testing/sampling. Welding. Excavation. Stainless steel pipe. **Winter Conditions.** Demo. Concrete (other than listed). Landscaping restoration. Electrical repairs. **Any other work and material**.

Please remit deposit to:

Minnesota Petroleum Service, Inc. 682 39th Ave NE Minneapolis, MN 55421

Please fax signed and accepted quote to:

**Mick Blazevic**