



February 1, 2021
RE: Green Cove Springs on Houston St
Attention: Mr. Andy Yeager

SUBJECT: Install new overhead line on Houston St from Orange St. to substation on Houston in Green Cove Springs.

Labor, Equipment:

Total Price: \$262,000

Inclusions:

- Install 32-50/ 55' wood poles
- Install 1- 55' concrete poles
- Install 4 transformer banks
- Install 5 set of 600AMP switches
- Install 3- Runs of 3-477 overhead primary cable for 4083'+-
- Install 1- Run of neutral line overhead for 4083'+-
- Install 870 of 1/0 triplex
- Install 536' of #2 triplex
- Install 930' of #6 duplex
- Install all necessary hardware
- Dead end existing overhead wire
- Remove existing poles
- Remove existing overhead wire
- Install 4 sets of LA
- Install 12 sets of anchors and guy wire

IRBY 305,127.⁰⁰

Heart 262,000.⁰⁰

Difference 43,127.⁰⁰

Exclusions:

- * Grassing or Sodding
- * Permitting.
- * Private locates and Private Utilities
- * Supplying of material
- * Install underground conduit
- * Surveying and layout
- * Testing
- * Engineering fees
- * Supplying or installing Electrical Gear or Switch Pit
- * MOT or traffic control

Notes: This quote is valid for 60 days and payment terms are net 30 days.