

Date: 05/15/2025

Green Cove Springs

Proposal Number: SF090052

Project Name: New Quote for Green Cove Springs

Southern States is pleased to provide the following proposal per your request.

- Prices are **FOB Hampton, freight prepaid and added to invoice at cost.**
- This proposal is valid until 07/15/2025.
- Payment terms are 30 Days after receipt of invoice.
- The proposed equipment is covered by Southern States 12/18 Month Limited Warranty.
  - 12 months from installation or 18 months from shipment
- The equipment listed in this proposal is subject to the [Southern States Standard Terms and Conditions.](#)
- Order cancellation subject to the [Southern States Cancellation Policy Schedule – Distribution Automation Division.](#)

***Note:** Pricing does not include applicable sales tax unless specifically itemized in the proposal. If a current tax exemption certificate has not been provided, the applicable sales tax will be added to the invoice. Southern States reserves the right to ship and invoice a partial amount of an order.*

Due to ongoing tariff adjustments, there is a possibility that new tariffs or costs may be introduced that are not currently known. Should this occur, any applicable tariffs on materials necessary for fulfilling this quotation will be added at cost to the invoice, with prior notice provided.

Your consideration of Southern States equipment is much appreciated. We trust you will find our bid favorable and look forward to working with you on this requirement.

Sincerely,

Omar Lodge  
Area Sales Manager  
404-403-9934  
o.lodge@southernstatesllc.com



Component	Description
Side-B Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)
Side-C Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)

**Item: 2**      **Description: 27kv Ganged, Single Tank Vertical Mount  
w/651RA Relay**

**Lead 18 - 20  
Time: Wks**

**Unit Price: \$24,475.00**

**Qty: 1**

**Ext Price: \$24,475.00**

Component	Description
Switch	27 KV VERTICAL 90-DEG GANGED SINGLE TANK 1 HANDLE (R4V) (08136751) <ul style="list-style-type: none"> <li>• Rating: 27kV Rated Maximum Voltage</li> <li>• Operation: Ganged</li> <li>• Handle: Single</li> <li>• HCEP Encapsulated Interrupters</li> <li>• 900A Continuous Current Rating Range @-40 to +60 C</li> <li>• Six (6) built in Voltage Sensors</li> <li>• Fault Interrupting Rating: 12.5kA</li> <li>• BIL: 150kV</li> <li>• Creepage Distance (Terminal to Terminal): 876mm/34.5in.</li> <li>• Creepage Distance (Terminal to Ground): 938mm/36.9in.</li> <li>• Device Orientation: Vertical</li> <li>• Outer Phase Orientation: Rotated</li> </ul>
Cabinet	651RA CONTROL CABINET (37-Pin) (24540003) <ul style="list-style-type: none"> <li>• Surge Protection, AC &amp; DC Breakers, Heater with Controller</li> <li>• 10 Year Rated Lithium ION battery</li> <li>• Communications Mounting Panel with DC Terminal block</li> <li>• Door Alarm</li> </ul>
Relay	00 Standard SEL0651RA01XGAAAE1A2XXXXXXX (01492261)
Mount	VERTICAL MOUNTING BRACKET (01984452)
Control Cable	00 Standard - 52 FT CONTROL CABLE (37-Pin) (01492138)
Power Cable	00 Standard 52 FT POWER CABLE (01492081)
Additional Battery	20 AH BATTERY, 24Vdc (10 year rated Lithium ION) (08247475)
Top-A Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)
Top-B Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)
Top-C Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)
Side-A Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)
Side-B Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)
Side-C Pad	NEMA 2 HOLE STRAIGHT TERMINAL (01984688)