

District Two Local Agency Change Order Request

Change Order Number 2

Financial Project Number: 435677-1-58-01

Contract Number: G2390

Project Description: Palmetto Avenue Sidewalk

Local Agency: City of Green Cove Springs

Contractor: Elton Alan

Original Contract Amount: \$1,544,374.81
Change in Contract Amount CO #1: \$633.19
Change in Contract Amount CO #2: \$1,328.05
Present Contract Amount: \$1,546,366.05

Original Contract Days: 296 days
Change in Contract Days-CO #1: Twelve (12) days
Change in Contract Days- CO #2: Twelve (12) days
Current Contract Days: 320 days

Change due to Design Error or Omission Yes No X

Description of Changes:

1. Adds 19.55 Sy of 6" Concrete Sidewalk and an additional 13.33 Sy of concrete removal.
2. Adds 12 Days for Weather and Holidays from 12/1/22 to 2/28/23.

Justification for Changes

1. The existing driveway located at station 142+60 does not extend far enough back to match the proposed sidewalk. If the sidewalk is poured per the plans there will be a 3' gap at the rear of the sidewalk across the driveway. By adding the additional concrete removal and 6" concrete sidewalk the sidewalk will remain a constant width through the corridor.
2. Adds the following Days from 12/1/22 to 2/28/23:
 - Weather; 12/15/22, 2/2/23
 - Holiday; 12/24/22 thru 1/2/23

Resources/ Materials

Item No.	Item Description	Quantity	Unit Price	Total Additional Cost
110-4-10	Existing Concrete Removal	13.33 SY	\$12.82	\$170.89
522-2	6" Concrete Sidewalk and Driveways	19.55 SY	\$59.19	\$1157.16
Estimated Total Change Cost				\$1328.05

Local Agency Representative

Date

District Two Program Administrator

Date

Contractor

Date