Quote

Date	November 18, 2024
Valid Until	90 days from above
Sales Representative	Darin Aarnio
	daarnio@impactsurface.com

Customer:

Mr. Greg Bauer
City of Green Cove Springs
321 Walnut Street
Green Cove Springs, FL 32043
gbauer@greencovesprings.com

Quote/Project Description

Thomas Hogan Memorial Gym
Athletic Flooring Replacement
Sourcewell Contract: #031022-RBI

Description	Line Total
Robbins Pulastic Classic 110 system:	
Demo and removal of existing floor system and components from property	
Grind & shot blast existing slab to bare concrete & remove all prior Adhesives / Sealants	
Apply Sikafloor®-1620 specially formulated epoxy coating to treat high moisture concrete floors	
9mm granulated shock pad with 2mm ***Robbins Pulastic*** seamless urethane wear layer	
Topcoat: Color as selected by owner from manufacturers standard color pallet	
Gamelines - Graphics: Equal to existing	
Perimeter 4" vinyl cove base	
Aluminum saddles at transitions	$ 183,279.00

Special Notes and Instructions

Moisture / Tolerance evaluation of the existing slab included

Freight / delivery to site included

Approximate lead time = 5-6 weeks

Subtotal	$ 183,279.00
Total	$ 183,279.00

Notes & Clarifications: **Impact** to provide dumpsters for process. Required power supplied by Owner. Permanent lighting and HVAC must be funcional during delivery/install. All work in compliance with Manufacturer Specifications. Additional work only to commence with the reciept of an approved Change Order.

Please confirm your acceptance of this quote by signing this document

Signature | Print Name | Date

Thank you for your business!

Should you have any inquiries concerning this quote, please contact Darin Aarnio: 561-721-5718

1121 S. Military Trail #318, Deerfield Beach, FL. 33442
Tel: 954-796-4567 Fax: 954-719-3784 Web: www.impactsurface.com