

To: Bill

From: Connor Hart

Date: 3/6/2026

Re: Riverview Rd Guiderail Accident Repair

Per your request and after inspecting the above referenced site, specs and plans where and when applicable, we are pleased to submit as follows (prices from current Saratoga Co. Contract 25-PWGR-24R2):

Project Scope- mobilize to site, establish WZTC measures as needed and verify UFPO mark out; remove/dispose 36' existing damaged box beam rail/posts; remove/store 24' box beam guiderail; furnish/install 3 new 3" I posts, 1 new drop end post, rehang 24' existing box beam; furnish/install 36' new box beam rail on new 3" I posts and hardware.

Project Cost-	36 ft @ \$27.76/ft Item 5A	\$ 999.36
	10 ea @ \$81.86/ea Item 11A	\$ 818.60
	1 ea @ \$60.44/ea Item 19	\$ 60.44
	2 ea @ \$80.00/ea Item 17	\$ 160.00
	5 ea @ \$0.67/ea Item 21	\$ 3.35
	5 ea @ \$1.63/ea Item 25	\$ 8.15
	1 ea @ \$6.68/ea Item 22	\$ 6.86
	6 hrs @ \$447.00/hr rental post pounder w/oper.	\$ 2,682.00
	6 hrs @ \$447.00/hr service truck w/laborers	\$ 2,682.00

Total Project Cost \$ 7,420.76

Price includes material, delivery, labor, equipment and traffic control. Work can commence 7-10 days after NTP. Please call 269-9497 with questions and or concerns.