

MANLY BENNETT PARK & WATER TRAIL ACCESS IMPROVEMENT PROJECT

HAMBURG TOWNSHIP LIVINGSTON COUNTY, MI














BY MARK REVISIONS DATE

THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.

MANLY BENNETT PARK & WATER TRAIL ACCESS IMPROVEMENT PROJECT

COVER

DATE DECEMBER, 2024 FILE NO.
SCALE DPL-1214- 1

DRAFT

DE. BY:
DR. BY:



	Tel. 989-754-47 Fax. 989-754-44 www.SpicerGro	140		
CAT CAT		PROJECT NO. 133809SG2023		
SHEET 1	OF 13	T		

230 S. Washington Ave. Saginaw, MI 48607

GENERAL NOTES

NO WORK SHALL BE PERFORMED BEFORE 7:00 AM OR AFTER 7:00 PM MONDAY THROUGH SATURDAY. NO WORK SHALL HAPPEN ON SUNDAYS OR HOLIDAYS. UNLESS AUTHORIZED BY THE OWNER.

CONTRACTOR SHALL NOTIFY ENGINEER 48 HOURS PRIOR TO START OF CONSTRUCTION, CONSTRUCTION STAKING AND INSPECTION.

CONTRACTOR TO PROVIDE DUST CONTROL AND SWEEP ROADS DAILY.

ALL EXCAVATED MATERIAL NOT TO BE REUSED OR DISPOSED OF ON SITE SHALL BE REMOVED FROM SITE. THE CONTRACTOR IS RESPONSIBLE FOR DISPOSING MATERIALS ACCORDING TO LOCAL AND STATE REQUIREMENTS.

UNDERGROUND UTILITIES/MISS DIG

FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 174, 2013, THE CONTRACTOR SHALL DIAL 1-800-482-7171 OR 811 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.

THE EXISTING UTILITIES ON THESE DRAWINGS HAVE BEEN SHOWN ACCORDING TO THE BEST AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD LOCATE ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION AND SHALL NOTIFY THE ENGINEER AS TO WHERE POSSIBLE CONFLICT EXISTS.

ALL CONSTRUCTION UNDER EXISTING UTILITIES, INCLUDING HOUSE SERVICES, SHALL BE COMPLETELY BACKFILLED WITH SAND, IN 12" LAYERS, AND COMPACTED TO NOT LESS THAN 95% OF THE MAXIMUM UNIT WEIGHT.

ANY UTILITIES ENCOUNTERED DURING CONSTRUCTION SHALL BE SUPPORTED, PER THE SPECIFICATIONS OF THE INDIVIDUAL UTILITY COMPANY CLAIMING OWNERSHIP OF THE UTILITY.

SOIL EROSION AND SEDIMENTATION CONTROL MEASURES

APPROPRIATE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO EARTH-DISTURBING ACTIVITIES. PLACE TURF ESTABLISHMENT ITEMS AS SOON AS POSSIBLE ON POTENTIAL ERODABLE SLOPES AS DIRECTED BY THE ENGINEER. CRITICAL DITCH GRADES SHALL BE PROTECTED WITH EITHER SOD OR SEED/MULCH OR MULCH BLANKET AS DIRECTED BY THE ENGINEER.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT SOIL EROSION AND SEDIMENTATION CONTROL MEASURES ARE IN PLACE AND MAINTAINED UNTIL THE CONTRACT HAS BEEN COMPLETED AND ACCEPTED. MEASURES SHALL ONLY BE PAID FOR ONCE.

ALL CATCHBASINS AND SEDIMENTATION TRAP/BASIN SHALL BE CLEANED OUT UPON COMPLETION OF THE PROJECT.

ALL DEWATERING REQUIRED FOR CONSTRUCTION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR UTILITY BEING INSTALLED.

ALL RIPRAP SHALL BE MDOT PLAIN RIPRAP TYPE MATERIAL, UNLESS OTHERWISE NOTED.

CONTRACTORS SHALL FINISH GRADE, SEED, FERTILIZE, AND MULCH DAILY ON ALL DISTURBED AREAS.

CONTRACTOR SHALL CONFORM TO SOIL EROSION AND SEDIMENTATION CONTROL ACT, PART 91 OF ACT 451 OF

PROPERTY OWNERS

PROPERTY OWNERS' NAMES, WHERE SHOWN, ARE FOR INFORMATION ONLY, AND THEIR ACCURACY IS NOT GUARANTEED.

ADJUSTING MONUMENT BOXES

ALL GOVERNMENT CORNERS ON THIS PROJECT SHALL BE PRESERVED, WHETHER SHOWN OR NOT. IT MAY BE NECESSARY TO PLACE OR ADJUST MONUMENT BOXES, AS REQUIRED.

THE CONTRACTOR SHALL MAINTAIN LOCAL TRAFFIC AT ALL TIMES. SIGNAGE MUST BE IN ACCORDANCE WITH THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND SHALL BE COORDINATED WITH THE ENGINEER AND GOVERNING ROAD AGENCY. PERMITS MAY BE REQUIRED.

PRIOR TO COMMENCING CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS REQUIRED BY THE APPROPRIATE AGENCIES.

CONSTRUCTION PROCEDURES SHALL CONFORM TO THE REQUIREMENTS OF THE APPROPRIATE AGENCIES.

SITE WORK

ALL TRENCHED CONSTRUCTION UNDER EXISTING, PROPOSED AND FUTURE GRAVEL, PAVED SURFACES OR UTILITIES SHALL BE COMPLETELY BACKFILLED WITH CLASS II SAND OR OTHER APPROVED GRANULAR MATERIAL IN 12" LAYERS AND COMPACTED TO 95% OF ITS MAXIMUM UNIT WEIGHT.

UNPAVED AREAS SHALL BE SMOOTHLY GRADED AND THE SURFACE STABILIZED BY SEEDING OR OTHERWISE. THE MAXIMUM DESIRABLE SLOPE IS 3 HORIZONTAL TO 1 VERTICAL UNLESS NOTED OTHERWISE.

CONTRACTOR IS RESPONSIBLE TO MAINTAIN POSITIVE DRAINAGE PATTERN TO ENSURE NO PONDING OF WATER ON

ADJACENT EXISTING AND PROPOSED PAVED SURFACES. WHERE A DISCREPANCY OCCURS BETWEEN PROPOSED WORK AND FIELD CONDITIONS, THE CONTRACTOR SHALL

NOTIFY THE ENGINEER FOR CLARIFICATION. PAVEMENT / SIDEWALK

PAVEMENT.

CONTRACTOR SHALL SAWCUT PAVEMENT AND CURB & GUTTER FOR A CLEAN EDGE TO INSTALL PROPOSED PAVEMENT AND CURB & GUTTER.

HMA PAVEMENT SHALL NOT BE PLACED WHEN THE SURFACE BEING OVERLAID IS WET, OR WHEN RAIN IS FORECAST OR THREATENING.

SIDEWALK SHALL BE CONSTRUCTED WITH A CROSS SLOPE SLOPED TOWARD THE STREET OR PARKING AREAS, SLOPES NOT TO EXCEED 2% UNLESS NECESSARY TO PROVIDE POSITIVE DRAINAGE OR MEET EXISTING SIDEWALKS,

CURBS OR PAVEMENT. IN GRASS AREAS, THE SURFACE OF THE SIDEWALK SHALL BE ABOUT $\frac{1}{4}$ INCH HIGH THAN THE ADJACENT GROUND

SURFACE, UNLESS NECESSARY TO PROVIDE POSITIVE DRAINAGE OR MEET EXISTING SIDEWALKS, CURBS OR

THE CONTRACTOR SHALL PROTECT FRESH HMA FROM DAMAGE BY THE WEATHER, TRAFFIC OR VANDALISM. DAMAGED HMA OR CONCRETE SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.

BC = BACK OF CURB BM = BENCH MARK C/C = CENTER TO CENTER CB = CATCH BASIN CL = CENTERLINE CJ = CONSTRUCTION JOINT CMP = CORRUGATED METAL PIPE CSP = CORRUGATED STEEL PIPE CONC = CONCRETE DI = DUCTILE IRON PIPE EF = EACH FACE ELEC = ELECTRIC EL OR ELEV = ELEVATION EOM = EDGE OF METAL EOP = EDGE OF PAVEMENT EQ/SP = EQUALLY SPACED ESMT = EASEMENT EW = EACH WAY EX OR EXIST = EXISTING FF = FINISH FLOOR FL = FLOW LINE FS = FINISH SURFACE

PROP = PROPOSED PVC = POLYVINYL CHLORIDE ROW = RIGHT OF WAY SAN = SANITARY SB = SOIL BORING SS = STAINLESS STEEL STA = STATION STM = STORM

TC = TOP OF CURB TOB = TOP OF BANK TOS = TOE OF SLOPE TELE = TELEPHONE TW = TOP OF WALK

WM = WATER MAIN WS = WATER SURFACE ELEVATION

ABBREVIATIONS

FG = FINISH GROUND GALV = GALVANIZED G = GUTTER HDG = HOT DIP GALVANIZED HDPE = HIGH DENSITY POLYETHYLENE HP = HIGH POINT HMA = HOT MIX ASPHALT HYD = HYDRANTINV = INVERT LP = LOW POINTOC = ON CENTER OH = OVERHEAD MH = MANHOLE MIN = MINIMUMMON = MONUMENT NFL = NOT FIELD LOCATED NTS = NOT TO SCALE

RCP = REINFORCED CONCRETE PIPE SWR = SEWER T/B = TOP AND BOTTOM

TRW = TOP OF RETAINING WALL UNO = UNLESS NOTED OTHERWISE

> ← ○ - GUY ANCHOR AND POLE - MAIL BOX ■ - WATER METER

> > © - ELECTRIC MANHOLE M.W. - MONITORING WELL • - HAND HOLE ☐ - TRANSFORMER

> > > - BARRIER FREE PARKING

FOR UTILITIES CONTACT ELECTRIC SERVICE DTE Energy 1095 Lawson Rd. Howell, MI 48843 TEL 248-427-2200 EMAIL: NWPD@dteenergy.com

LINE TYPE LEGEND

- EXISTING ROAD CENTERLINE ______ - EXISTING WATER MAIN - EXISTING SANITARY SEWER OR FORCEMAIN ______ - EXISTING STORM SEWER - EXISTING TELEPHONE CABLE _____ - EXISTING GAS MAIN _____ - EXISTING ELECTRIC ______ - PROPOSED UTILITY - EXISTING CURB & GUTTER - PROPOSED CURB & GUTTER - FENCE LINE ____x ___x ___x ___ - OVERHEAD UTILITY ____//____ - RAILROAD TRACKS - STATION LINE - LIMITS OF RIGHT OF WAY - EASEMENT - SILT FENCE - REVERSE PAN CURB & GUTTER - TREE LINE - EXISTING CONTOURS - PROPOSED CONTOURS

SYMBOL LEGEND **EXISTING SYMBOLS**

△ - SPRINKLER O - MANHOLE a⊐o - RAILROAD SIGNAL ANTENNA ⊗ - SATELLITE DISH - AIR CONDITIONING UNIT ⊕ - GAS VALVE • SOIL BORING ⊗ - WATER VALVE □ - TELEPHONE PEDESTAL + - BENCH MARK ● - POWER POLE FOUND SURVEY CORNER Ø - TELEPHONE POLE ○ - SET 1/2" IRON ROD • - 1/4 SECTION CORNER —√— - BREAK IN LINE - - EXISTING SIGN-1 POST - - EXISTING SIGN-2 POST Pl - STUMP ① - TELEPHONE MANHOLE - PINE · TREE - ELECTRICAL PEDESTAL

PROPOSED SYMBOLS

O - MANHOLE - CATCHBASIN **O** - FIRE HYDRANT WATER VALVE - BARRIER FREE PARKING - LIGHT POLES ⇒ - DRAINAGE FLOW - SPOT ELEVATION LABELS G = GUTTERTW = WALK

TC = TOP OF CURB

FS = FINISH SURFACE

REVISIONS THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION DESIGN OR PURPOSE.

ACCESS IMPROVEMENT PROJECT


MANLY BENNETT PARK & WATER TRAIL


NOTES





230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com


CH. BY: CAT PROJECT NO. 133809SG2023 DR. BY: APP. BY: CAT SHEET 2 of 13FILE NO. DATE DECEMBER, 2024 DPL-1214- 2 N/A























MODEL: 6263 INCLUSIVE WHIRL NATURAL (1 QTY) COLOR MATERIALS: METAL & HDPE 2 TONE

MODEL: 5208 SAUCER SWING (1 QTY) COLOR MATERIALS: METAL & ROTO PLASTIC

TREETOP TRAVERSE (3 CLIMBERS)

MODEL: 6370 TREETOP TRAVERSE (1 QTY)


COLOR MATERIALS: METAL & ROTO PLASTIC

CONCRETE EDGE; -FLUSH WITH PLAY SURFACING; SEE DETAIL 7, SHEET 12 SAFETY SURFACING ENGINEERED WOOD FIBER (EWF); SEE DETAIL 5, SHEET 12 SENSORY DOME MEDIUM PROPOSED 6' WIDE 21AA CRUSHED LIMESTONE PATH; SEE DETAIL 2, SHEET 12

PLAY POD 2 - SENSORY DOME



MANUFACTURER: GAMETIME www.gametime.com REPRESENTATIVE: SINCLAIR RECREATION (800) 444-4954 MODEL: 6256 SENSORY DOME MEDIUM (1 QTY) COLOR MATERIALS: METAL, ROTO PLASTIC, & ROPE OPTIONAL GT SENSOR PANELS (2)



PLAY POD 3 - MUSICAL QUARTET



MANUFACTURER: Percussion Play www.percussionplay.com REPRESENTATIVE: SNIDER RECREATION (248) 431-2796

MODEL: C4-C6 DECRIPTION: SOPRANO QUARTET ENSEMBLE MOUNT: GROUND INSTALL

- REPRESENTATIVE. DIMENSIONS PROVIDED ON THE PLAN FOR LOCATING ON SITE. TO BE FIELD VERIFIED.
- 2. ROUGH GRADING OF PROPOSED PATHS AND PLAYGROUND AREAS SHALL BE FIELD EVALUATED AND APPROVED PRIOR TO FINE GRADING.
- FINISH GRADE OF CONCRETE CURBING, PLAY SURFACING, AND CRUSHED LIMESTONE SHALL BE FLUSH WHEN ADJACENT.
- 4. PLAYGROUND SURFACE SHALL BE HORIZONTALLY LEVEL. SURROUNDING LAWN SHALL BE FLUSH AND SLOPE AT 1:6 MAX TO ENSURE POSITIVE DRAINAGE AWAY FROM PLAYGROUND. ROUGH SITE GRADING AROUND THE PLAYGROUND SHALL BE EVALUATED FOR ANY POTENTIAL PONDING AROUND THE PLAYGROUND, AT THAT TIME FINE GRADING MEASURES SHALL BE MADE TO ELIMINATE FUTURE PONDING.
- 5. PLAYGROUND AREAS, WITH PLAY SURFACING, SHALL INCLUDE SUBSURFACE DRAINAGE. SUBSOIL SHALL SLOPE 2% TOWARD DRAINAGE PIPING. DRAINAGE PIPE TO DAYLIGHT DOWNSLOPE IF POSSIBLE OR CONNECT TO AN EXISTING STORMWATER SYSTEM. IF EITHER OF THESE OPTIONS AREN'T FEASIBLE DUE TO SITE CONSTRAINTS, THEN DRAINAGE LINE SHALL CONNECT TO FRENCH

BY	MARK	REVISIONS	DATE		
THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.					

MANLY BENNETT PARK & WATER TRAIL ACCESS IMPROVEMENT PROJECT

> PLAY PODS AND EQUIPMENT

SCALE 1/4"=1'-0"

SAGINAW OFFICE 230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

PROJECT NO. CH. BY: CAT DR. BY: APP. BY: CAT *133809SG2023* STDS. OF **13** SHEET **11** DATE DECEMBER, 2024 | FILE NO.

DPL-1214- 11

GAMESTIME COLOR OPTIONS



METAL Green



Sky Blue Red Yellow Black Brown

Adaptive Switch Capable Adaptive Switch Capable Adaptive Switch Capable Sensors Adaptive switch capability provides individuals with limited upper body or fine motor control the ability to activate auditory features. Switch not included



GAMESTIME GT SENSORS - OPTIONAL




HDPE SOLID AND 2 TONE

DRAFT


INCLUSIVE WHIRL - NATURAL

SAUCER SWING



SHEET 12 OF 13 DATE DECEMBER, 2024 | FILE NO. DPL-1214- 12 10 SCALE AS SHOWN





MICHIGAN ASSOCIATION OF COUNTY DRAIN COMMISSIONERS **EROSION & SEDIMENT CONTROL MEASURES**

KEY	SESC MEASURE	SYMBOL	WHERE USED
1	SEEDING	Manual Control of the	When bare soil is exposed, temporarily or permanently, to erosive forces from wind and or water on flat areas, mild slopes, grassed waterways and spillways, diversion ditches and dikes, borrow and stockpile areas, and spoil piles.
2	MULCH		On flat areas, mild slopes, grassed waterways and spillways, diversion ditches and dikes, borrow and stockpile areas, and spoil piles when areas are subject to raindrop impact, and erosive forces from wind or water.
3	SODDING		When a temporary or permanent vegetative cover is necessary or desired to prevent soil erosion and filter sediment in residential, commercial or high traffic areas; or on steep slopes, auxiliary spillways, and grassed swales
21	SHEET PILING		As a temporary cofferdam during construction.

DETAILED DRAWINGS AND SPECIFICATIONS ARE LOCATED IN THE MICHIGAN ASSOCIATION OF COUNTY DRAIN COMMISSIONERS SOIL EROSION AND SEDIMENTATION CONTROL AUTHORIZED PUBLIC AGENCY PROCEDURES MANUAL

SYMBOLOGY FOR INSERTION INTO CONSTRUCTION DRAWINGS:

= TEMPORARY MEASURE

= PERMANENT MEASURE

= COFFERDAM ______ = SILT FENCE

Contractor shall conform to Soil Erosion and Sedimentation Control Act, Part 91 of Public Act 451 of 1994, as amended. All catch basins, on the site and adjacent to the site, shall be covered with cloth filters for Soil Erosion and Sedimentation Control.

SOIL EROSION AND SEDIMENTATION CONTROL NOTES

- 1. ALL EROSION AND SEDIMENT CONTROL WORK SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF THE AGENCY HAVING JURISDICTION.
- 2. EROSION AND ANY SEDIMENT FROM WORK ON THIS SITE SHALL BE CONTAINED ON THE SITE AND NOT ALLOWED TO COLLECT ON ANY OFF-SITE AREAS OR IN WATERWAYS. WATERWAYS INCLUDE BOTH NATURAL AND MANMADE OPEN DITCHES, STREAMS, STORM DRAINS) LAKESJAND PONDS.
- 3. DAILY INSPECTIONS SHALL BE MADE BY THE CONTRACTOR TO DETERMINE EFFECTIVENESS OF EROSION AND SEDIMENT CONTROL MEASURES, AND ANY NECESSARY REPAIRS SHALL BE PERFORMED' WITHOUT DELAY.
- 4. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CONSTRUCTION, SEDIMENT CONTROL PRACTICES WILL BE APPLIED AS A PERIMETER DEFENSE AGAINST ANY TRANSPORTING OF SILT OFF THE SITE.
- 5. CONTRACTOR SHALL APPLY TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES. HE SHALL REMOVE TEMPORARY MEASURES AS SOON AS PERMANENT STABILIZATION OF SLOPES, DITCHES, AND OTHER EARTH CHANGES HAS BEEN ACCOMPLISHED AND APPROVED BY THE AGENCY WITH
- 6. DEBRIS FROM THE PROJECT SHALL BE LEFT ON THE SITE BY DELIVERY OR CONSTRUCTION VEHICLES THROUGH THE USE OF CLEAN STONE EXITS. SHOULD THE STONE BECOME INEFFECTIVE IT WILL BE REPLACED. ALL CONSTRUCTION TRAFFIC WILL USE THE CLEAN STONE EXITS.
- 7. IMMEDIATELY AFTER SEEDING, MULCH ALL SEEDED AREAS WITH UNWEATHERED SMALL GRAIN STRAW OR HAY SPREAD UNIFORMLY AT THE RATE OF 1 - 1 /2 TO 2 TONS PER ACRE. ANCHOR MULCH WITH DISC-TYPE MULCH ANCHORING TOOL OR OTHER MEANS AS APPROVED BY THE AGENCY WITH
- 8. ALL MUD, DIRT, AND DEBRIS TRACKED OR SPILLED ONTO EXISTING ROADS FROM THIS SITE SHALL BE PROMPTLY REMOVED BY THE CONTRACTOR.
- 9. PERMANENT SOIL EROSION CONTROL MEASURES FOR ALL SLOPES, CHANNELS, DITCHES, OR ANY DISTURBED LAND AREA SHALL BE COMPLETED WITHIN 15 CALENDAR DAYS AFTER FINAL GRADING OR FINAL EARTH CHANGES HAVE BEEN COMPLETED WHEN IT IS NOT POSSIBLE TO PERMANENTLY STABILIZE A DISTURBED AREA AFTER AN EARTH CHANGE HAS BEEN COMPLETED OR WHERE SIGNIFICANT EARTH CHANGE ACTIVITY CEASES, TEMPORARY SOIL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED IMMEDIATELY ALL TEMPORARY SOIL EROSION CONTROL MEASURES SHALL BE MAINTAINED UNTIL PERMANENT SOIL EROSION CONTROL MEASURES ARE ESTABLISHED. ALL, PERMANENT SOIL EROSION CONTROL MEASURES WILL BE IMPLEMENTED AND ESTABLISHED BEFORE A CERTIFICATE OF COMPLIANCE IS ISSUED ALL DRAIN BANKS DISTURBED BY CONSTRUCTION SHALL BE RESTORED WITHIN FIVE CALENDAR DAYS AND SOD PEGGED IN PLACE.
- 10. PARTICULAR CARE SHOULD BE TAKEN WHEN WORKING ALONG THE PERIMETER OF THE SITE. IN NO EVENT SHALL WORK AREA EXTEND BEYOND THE LIMITS INDICATED ON THE PLANS.
- 11. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO DEWATER THE GROUND IN THE COURSE OF CONSTRUCTING THE PROPOSED UTILITY, THE CONTRACTOR SHALL CONSTRUCT A TEMPORARY SOIL EROSION CONTROL DEVICE IN A MANNER THAT WILL FILTER ALL DISCHARGED WATER FROM THE DEWATERING OPERATION IN NO INSTANCE SHALL THE DEWATERING DISCHARGE BE PERMITTED TO FLOW UNFILTERED FROM THE
- 12. THE CONTRACTOR SHALL CONTROL THE DUST ON THE SITE DURING THE LIFE OF THE CONTRACT. IN ACCORDANCE WITH THE SPECIFICATIONS AND THE REQUIREMENTS OF THE COMMUNITY THIS DUST CONTROL SHALL BE ACCOMPLISHED BY THE APPLICATION OF A POSITIVE DUST PICK-UP METHOD WITH WATER ON HARD SURFACES. SUCH DUST CONTROL MATERIALS SHALL BE APPLIED AS OFTEN AS IS NECESSARY IN THE OPINION OF
- 13. SHOULD THE SOIL EROSION CONTROL REQUIREMENTS BE NEGLECTED OR NOT ADEQUATELY FOLLOWED, THE COMMUNITY MAY REQUIRE THE CONTRACTOR TO CEASE CONSTRUCTION OPERATIONS AND TO APPLY HIS ENTIRE FORCE TO MEET THE REQUIREMENTS BEFORE PROCEEDING
- 14. ALL WORK CONNECTED WITH SOIL EROSION AND SEDIMENTATION CONTROL) EITHER TEMPORARY OR PERMANENT, AS REQUIRED BY THE SOIL EROSION CONTROL PERMIT, IS TO BE IMPLEMENTED DURING CONSTRUCTION.

SEQUENCE OF CONSTRUCTION - SESC

1. INSTALL ALL TEMPORARY SOIL EROSION CONTROL MEASURES PRIOR TO DISTURBING ANY EARTH ON THE SITE.

SCHEDULE

- 2. STABILIZE SLOPES STEEPER THAN 1 ON 4, CHANNELS AND SWALES WITHIN 7 DAYS OF EARTH DISTURBANCE. INSTALL PERMANENT STABILIZATION
- 3. CLEAN ALL ACCUMULATED SEDIMENT FROM CATCH BASINS, SEWERS AND PAVEMENT AREAS AS REQUIRED FOLLOWING COMPLETION OF
- 4. THE EXACT SCHEDULE OF SOIL EROSION AND SEDIMENTATION CONTROL EVENTS (WITH DAY AND/OR DATES OF THE VARIOUS ACTIVITIES) SHALL BE SUBMITTED TO LIVINGSTON COUNTY BY THE CONTRACTOR, FOR REVIEW AND APPROVAL, PRIOR TO OBTAINING A PERMIT.

NEAREST WATER BODY

HALL CREEK

TIMING SEQUENCE

OPERATION TEMPORARY CONTROL MEASURES

STRIPPING/STOCKPILING OF SOIL

ROUGH GRADING/SEDIMENTATION CONTROL PERMANENT CONTROL MEASURE

SITE CONSTRUCTION

FINISH GRADING

* SCHEDULE TO BE FILLED OUT BY CONTRACTOR/PERMITEE.

DRAFT

THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE. MANLY BENNETT PARK & WATER TRAIL ACCESS IMPROVEMENT PROJECT SESC PLAN

SAGINAW OFFICE 230 S. Washington Ave. Saginaw, MI 48607 Tel. 989-754-4717 Fax. 989-754-4440 www.SpicerGroup.com

PROJECT NO. 133809SG2023 APP. BY: CAT DR. BY: SHEET **13** OF **13**

SCALE AS SHOWN

DATE DECEMBER, 2024 | FILE NO. DPL-1214- 13