







BENCHMARKS (NAVD 88)

- BM 0 NGS Benchmark
PID - DE7787, Designation - 4K05
Elev 780.50'
- BM 1 "X" Cut in Concrete Light Pole Base
±175' South of Club House, Southerly of 3 Light Poles
Elev 755.82'
- BM 2 "X" Cut in Rim of Sanitary Manhole
±65' South of Club House
Elev 781.37'
- BM 3 Fire Hydrant, Tag Bolt
±35' North of Clubhouse
Elev 785.67'

LOCATION MAP



General Notes:

- Zoning Information**
Village of Harrison:
General Agricultural District (AG)
Shoreland Zoning Overlay District
Setbacks:
Water (OHWM): 50 Feet
Side Yard: 25 Feet
Rear Yard: 50 Feet
Height: Principle - 35 Feet
- Floodplain Information**
(Subject Site mapped in Multiple Zones per FIRM Map No. 55015C0029E with and effective date of Feb. 02, 2009)
a) Partially Mapped as "Zone X": Area determined to be outside the 0.2% annual chance floodplain.
b) Partially Mapped as "Zone AE": Area of Special Flood Hazard which is subject to flooding by the 1% annual chance flood (100 year flood).
- Public Trust Information**
s.236.20 (6) "Any land below the ordinary high water mark of a lake or a navigable stream is subject to the public trust in navigable waters that is established under article IX, section 1, of the state constitution."
- Existing utilities shown are indicated in accordance with available records and field measurements. However, lacking excavation, the exact location of underground features cannot be accurately, completely, and reliably depicted. In addition, in some jurisdictions, 811 or other similar utility locate requests from surveyors may be ignored or result in an incomplete response. The contractor shall be responsible for obtaining exact locations & elevations of all utilities, including sewer & water from the property owners of the respective utilities. All utility the property owners shall be notified by the contractor 72 hours prior to excavation. Contact Digger's Hotline (1-800-242-8511) for exact utility locations.
- This is not a boundary survey.

Sanitary Structures

Structure	#	Rim	Inv	Size	Material	Direction
MH	1	783.94				
MH	2	781.47	770.92	8"	PVC	NW
			770.92	8"	PVC	NE
MH	3	780.29	770.71	8"	PVC	SW
			770.71	8"	PVC	E
MH	4	781.38	773.82	8"	PVC	NW
			773.82	8"	PVC	NE

Storm Structures

Structure	#	Rim	Inv	Size	Material	Direction
CB	A	781.57	776.95	6"	PVC	S
MH	B	782.66	776.71	8"	PVC	NW
			776.93	8"	PVC	SE
			776.57	8"	PVC	N
INL	C	783.31	779.05	8"	PVC	NW
INL	D	779.61	775.21	18"	CMP	SE
MH	E	764.94	751.38	27"	RCP	S
			757.96	16"	RCP	N
CB	F	764.85	760.24	16"	RCP	S
			760.24	24"	RCP	N
INL	G	771.86	765.80	6"	PVC	N
			765.82	8"	PVC	W
			770.07	10"	HDPE	N
			765.59	24"	RCP	S
CB	H	775.04	773.41	6"	PVC	N
			772.73	8"	PVC	E
			772.88	8"	PVC	S

SURVEYOR'S CERTIFICATE

I, Scott R. Andersen, hereby certify that I have surveyed this property and this topographical map is a true representation thereof and shows the size and location of the property and the location of all apparent roadways. I hereby certify that said topographical survey and map were made in accordance with acceptable professional standards and that the information contained thereon is, to the best of my knowledge, information and belief, a true and accurate representation thereof.

Scott R. Andersen,
Wisconsin Professional
Land Surveyor No. S-3169

Date



DAVEL ENGINEERING & ENVIRONMENTAL, INC.
Civil Engineers and Land Surveyors
1164 Province Terrace, Menasha, WI 54952
Ph: 920-991-1866 Fax: 920-441-0804
www.davel.pro



TOPOGRAPHIC SURVEY

N8421 North Shore Road
Village of Harrison, Calumet County, WI
For: North Shore Golf Club, Inc.

Date:
07/25/2025

Filename:
8042Topo.dwg

Author:

SR


Last Saved by:

scott

Page

C1.1


LEGEND




NOTES:

- Existing utilities shown are indicated in accordance with available records and field measurements. The contractor shall be responsible for obtaining exact locations & elevations of all utilities, including sewer and water from the owners of the respective utilities. All utility owners shall be notified by the contractor 72 hours prior to excavation. Contact Digger's Hotline (1-800-242-8511) for exact utility locations.
- The Contractor shall verify all staking and field layout against the plan and field conditions prior to constructing the work and immediately notify the Engineer of any discrepancies.
- Contractor shall coordinate with North Shore Golf Club staff for stockpile location and/or remove all excess materials from the site. Earthwork contractors shall verify topsoil depth.
- Updated survey and title search have not been authorized and the boundary and easements shown may be inaccurate or incomplete.

LOCATION MAP



Match Line



Match Line



DRAINAGE & GRADING
PLAN



N8421 North Shore Road
Village of Harrison, Calumet County County, WI
For: North Shore Golf Club, Inc.

LEGEND


	Sanitary Sewer		Sanitary MH / Tank / Base		Flag Pole
	Storm Sewer		Clean Out / Curb Stop / Pull Box		Deciduous Tree
	Underground Electric		Storm Manhole		Benchmark
	Water Main		Inlet		Asphalt Pavement
	Underground Telephone		Catch Basin / Yard Drain		Concrete Pavement
	Fence - Steel		Hydrant		Rip Rap
	Treeline		Utility Valve		
	Index Contour - Existing		Utility Meter		
	Intermediate Contour - Existing		Light Pole / Signal		
			Electric Pedestal		
			Telephone Pedestal		
			Air Conditioner		
			Ex Spot Elevation		
	Proposed Storm Sewer		Proposed Storm Manhole		
	Proposed Contour		Proposed Curb Inlet		
	Proposed Swale		Prop. Catch Basin / Yard Drain		
	Proposed Culvert		Proposed Endwall		
	Proposed Silt Fence		Proposed Rip Rap		
	Prop. Drainage Direction		Proposed Urban Type B Erosion Mat		
	Proposed Tracking Pad		Proposed Class I Type B Erosion Mat		
			Proposed Class II Type B Erosion Mat		
	Proposed Ditch Check		Proposed Inlet Protection		
	Proposed Building				
	Proposed Asphalt				
	Proposed Concrete				
	Proposed Gravel				

NOTES:


1. Refer to Sheet C2.1 for erosion and sediment control notes.



Match Line



Match Line



Schmalz
Custom Landscaping
and Garden Center

LANDSCAPE ARCHITECTURE
DEVELOPMENT
CONSTRUCTION

AWARD WINNING DESIGN
AND INSTALLATION

W2484 CTY RD KK
APPLETON, WI 54915-9464
PHONE 920-733-8223
FAX 920-733-3262
WWW.SCHMALZLANDSCAPING.COM

All ideas, designs, arrangements and plans indicated by this drawing are owned by, and are the property of Schmidt Custom Landscaping. None of these ideas, arrangements or plans shall be disclosed to any person, firm or contractor for any purpose without the written permission of Schmidt Custom Landscaping, Inc. Written dimensions on this plan shall have precedence over scaled dimensions.

DO NOT SCALE
© 2025, Schmolz Custom Landscaping, Inc.

PROJECT INFORMATION

NORTH SHORE GOLF CLUB - NEW POOL & LAKE HOUSE IMPROVEMENTS

D N 8421 N Shore W Rd
Menasha, WI 54952



ISSUANCE AND REVISIONS

DATE	DESCRIPTION
07/25/2025	CONSTRUCTION DOCUMENTS

C

North Shore Golf Club
N8421 N. Shore Rd.
Menasha, WI 54952

KEY PLAN

**B**

DATE: 07/2025

REVISÉ: _____

PHONE NO.: _____
E-MAIL: _____

SCALE: $|^i = |\varrho^i - \varrho^0|$

DRAWN BY:
IPM 161

SHEET TITLE

Landscape Pl

100

SHEET NO. 11

L-1


PROJECT MANAGER TH

PROJECT NUMBER 923505

LANDSCAPE PLAN

1

©25 Eppstein Uhen Architects, Inc.



1

2

3

4

5

6

7

E

PROJECT INFORMATION

NORTH SHORE
GOLF CLUB - NEW
POOL & LAKE
HOUSE
IMPROVEMENTS

D


N 8421 N Shore W Rd
Menasha, WI 54952

ISSUANCE AND REVISIONS

DATE	DESCRIPTION
07/25/2025	CONSTRUCTION DOCUMENTS

C

KEY PLAN



B

SHEET INFORMATION

PROJECT MANAGER TH
PROJECT NUMBER 923505

LOWER LEVEL PLAN
- LAKE HOUSE



A101

FLOOR PLAN NOTES


- A. BEFORE BEGINNING WORK, VERIFY THE EXISTENCE AND LOCATION OF PLUMBING, MECHANICAL AND ELECTRICAL SYSTEMS AND OTHER CONSTRUCTION AFFECTING THE WORK. IF DISCREPANCIES ARE DISCOVERED, NOTIFY ARCHITECT PROMPTLY.
- B. ALL DIMENSION STRINGS ARE TO FINISH FACE OF WALL, UNLESS NOTED OTHERWISE.
- C. VERIFY STRUCTURAL ELEMENTS AND FLOOR SLABS PRIOR TO CORING OR CUTTING. COORDINATE VERIFICATION METHOD WITH OWNER.
- D. REFER TO SHEET A101 FOR REFERENCED PARTITION TYPES AND DETAILS. WALLS NOT TAGGED ON THESE PLANS SHALL BE PARTITION TYPE WEA-S11.
- E. PROVIDE MOISTURE- AND MOLD-RESISTANT GYPSUM BOARD AT THE FOLLOWING LOCATIONS: ENTIRE WALL DIRECTLY BEHIND OR ADJACENT TO ANY PLUMBING FIXTURE INCLUDING, BUT NOT LIMITED TO, WATER CLOSETS, SHOWERS, DRINKING FOUNTAINS, SINKS, LAVATORIES AND EYEWASHES; AND ALL WALLS OF AREAS INCLUDING, BUT NOT LIMITED TO, CHANGING ROOMS, SINGLE OCCUPANT TOILET ROOMS, JANITOR CLOSETS, COMMERCIAL KITCHENS, DISHWASHING, ETC. WHERE CERAMIC TILE OR SOLID SURFACE WALL CLADDING IS SCHEDULED, PROVIDE CEMENT BOARD BACKER BOARD IN LIEU OF GYPSUM BOARD.
- F. LOCATE ALL DOOR JAMBS 4" FROM ADJACENT PERPENDICULAR WALL, UNLESS NOTED OTHERWISE.
- G. REPAIR, PATCH AND CLEAN ALL EXISTING SURFACES SCHEDULED TO REMAIN THAT ARE AFFECTED BY DEMOLITION OR NEW CONSTRUCTION. MAKE APPEAR NEW, MATCHING ADJACENT CONSTRUCTION. PREPARE ALL SURFACES AS REQUIRED FOR SCHEDULED FINISHES. SKIM COAT AND PREPARE ALL DAMAGED OR UNFINISHED SURFACES.
- H. PATCH ALL WALL BASE SCARS AT EXISTING WALL SURFACES. PREPARE SMOOTH TO RECEIVE NEW WALL BASE FOR UNIFORM APPEARANCE.
- I. PATCH WALLS TO MATCH ADJACENT SURFACES AT ALL ABANDONED OR REMOVED OUTLET AND SWITCH LOCATIONS. BLANK COVER PLATES ARE NOT ACCEPTABLE.
- J. PREPARE FLOOR LEVEL AND SMOOTH FOR NEW HARD SURFACE FINISHES. PATCH EXISTING PENETRATIONS AND ABNORMALITIES IN CONCRETE FLOOR.
- K. ALL AREAS DISTURBED BY DEMOLITION SHALL BE PATCHED AND PROPERLY PREPARED FOR NEW FINISH APPLICATIONS. WHERE ADJACENT FINISHES ARE EXISTING TO REMAIN, PATCH AND MATCH EXISTING FINISHES. CONSULT WITH THE OWNER TO IDENTIFY ATTIC STOCK AND/OR PREVIOUS MATERIAL SPECIFICATIONS.
- L. PROVIDE BLOCKING IN WALLS AS REQUIRED FOR NEW MILLWORK, CASEWORK, DOOR BUMPERS, ACCESSORIES, EQUIPMENT, FIXTURES, AND OWNERS WALL-MOUNTED EQUIPMENT, INCLUDING BUT NOT LIMITED TO, TELEVISIONS/MONITORS, MARKER BOARDS, TACK BOARDS AND SIGNAGE. OPEN EXISTING WALLS AS NEEDED TO INSTALL CONCEALED BLOCKING WHERE REQUIRED, AND PATCH WALLS TO MATCH EXISTING CONSTRUCTION. COORDINATE WITH OWNER ON LOCATIONS OF WALL-MOUNTED EQUIPMENT.
- M. PROVIDE 3/4" FIRE-RETARDANT TREATED PLYWOOD AS BACKING PANELS FOR DATA & ELECTRICAL EQUIPMENT. INSTALL AT 1'-0" AFF TO FINISHED CEILING. PAINT PLYWOOD TO MATCH ADJACENT WALL FINISH. COORDINATE FINAL SIZE AND LOCATION WITH ELECTRICAL CONTRACTOR.

KEYNOTES PER SHEET

- 0103 INFILL EXISTING WALL; MATCH EXISTING WIDTH; CONSTRUCTION, ACOUSTIC INSULATION AND ANY SMOKE OR FIRE RATINGS.



A1 POOL EQUIPMENT ROOM STEP
1" = 1'-0" | REF: A3/A101



A3 LOWER LEVEL PLAN - LAKE HOUSE
3/16" = 1'-0" | A101



milwaukee | madison | green bay | denver | atlanta

E

PROJECT INFORMATION

NORTH SHORE
GOLF CLUB - NEW
POOL & LAKE
HOUSE
IMPROVEMENTS


D N 8421 N Shore W Rd
Menasha, WI 54952

ISSUANCE AND REVISIONS

DATE	DESCRIPTION
07/25/2025	CONSTRUCTION DOCUMENTS

C

KEY PLAN



B

SHEET INFORMATION

PROJECT MANAGER TH
PROJECT NUMBER 923505


1ST FLOOR PLAN -
LAKE HOUSE

A102

© 2025 Epstein Uhan Architects, Inc.

FLOOR PLAN NOTES	
A.	BEFORE BEGINNING WORK, VERIFY THE EXISTENCE AND LOCATION OF PLUMBING, MECHANICAL AND ELECTRICAL SYSTEMS AND OTHER CONSTRUCTION AFFECTING THE WORK. IF DISCREPANCIES ARE DISCOVERED, NOTIFY ARCHITECT PROMPTLY.
B.	ALL DIMENSION STRINGS ARE TO FINISH FACE OF WALL, UNLESS NOTED OTHERWISE.
C.	VERIFY STRUCTURAL ELEMENTS AND FLOOR SLABS PRIOR TO CORING OR CUTTING. COORDINATE VERIFICATION METHOD WITH OWNER.
D.	REFER TO SHEET A010 FOR REFERENCED PARTITION TYPES AND DETAILS. WALLS NOT TAGGED ON THESE PLANS SHALL BE PARTITION TYPE WAA S11.
E.	PROVIDE MOISTURE- AND MOLD-RESISTANT GYPSUM BOARD AT THE FOLLOWING LOCATIONS: ENTIRE WALL DIRECTLY BEHIND OR ADJACENT TO ANY PLUMBING FIXTURE INCLUDING, BUT NOT LIMITED TO, WATER CLOSETS, SHOWERS, DRINKING FOUNTAINS, SINKS, LAVATORIES AND EYEWASHES; AND ALL WALLS OF AREAS INCLUDING, BUT NOT LIMITED TO, CHANGING ROOMS, SINGLE OCCUPANT TOILET ROOMS, JANITOR CLOSETS, COMMERCIAL KITCHENS, DISHWASHING, ETC, WHERE CERAMIC TILE OR SOLID SURFACE WALL CLADDING IS SCHEDULED. PROVIDE CEMENT BOARD BACKER BOARD IN LIEU OF GYPSUM BOARD.
F.	LOCATE ALL DOOR JAMBS 4" FROM ADJACENT PERPENDICULAR WALL, UNLESS NOTED OTHERWISE.
G.	REPAIR, PATCH AND CLEAN ALL EXISTING SURFACES SCHEDULED TO REMAIN THAT ARE AFFECTED BY DEMOLITION OR NEW CONSTRUCTION. MAKE APPEAR NEW, MATCHING ADJACENT CONSTRUCTION. PREPARE ALL SURFACES AS REQUIRED FOR SCHEDULED FINISHES. SKIM COAT AND PREPARE ALL DAMAGED OR UNFINISHED SURFACES.
H.	PATCH ALL WALL BASE SCARS AT EXISTING WALL SURFACES. PREPARE SMOOTH TO RECEIVE NEW WALL BASE FOR UNIFORM APPEARANCE.
I.	PATCH WALLS TO MATCH ADJACENT SURFACES AT ALL ABANDONED OR REMOVED OUTLET AND SWITCH LOCATIONS. BLANK COVER PLATES ARE NOT ACCEPTABLE.
J.	PREPARE FLOOR LEVEL AND SMOOTH FOR NEW HARD SURFACE FINISHES. PATCH EXISTING PENETRATIONS AND ABNORMALITIES IN CONCRETE FLOOR.
K.	ALL AREAS DISTURBED BY DEMOLITION SHALL BE PATCHED AND PROPERLY PREPARED FOR NEW FINISH APPLICATIONS. WHERE ADJACENT FINISHES ARE EXISTING TO REMAIN, PATCH AND MATCH EXISTING FINISHES. CONSULT WITH THE OWNER TO IDENTIFY ATTIC STOCK AND/OR PREVIOUS MATERIAL SPECIFICATIONS.
L.	PROVIDE BLOCKING IN WALLS AS REQUIRED FOR NEW MILLWORK, CASEWORK, DOOR BUMPERS, ACCESSORIES, EQUIPMENT, FIXTURES, AND OWNERS WALL-MOUNTED EQUIPMENT, INCLUDING BUT NOT LIMITED TO, TELEVISIONS/MONITORS, MARKER BOARDS, TACK BOARDS AND SIGNAGE. OPEN EXISTING WALLS AS NEEDED TO INSTALL CONCEALED BLOCKING WHERE REQUIRED, AND PATCH WALLS TO MATCH EXISTING CONSTRUCTION. COORDINATE WITH OWNER ON LOCATIONS OF WALL-MOUNTED EQUIPMENT.
M.	PROVIDE 3/4" FIRE-RETARDANT TREATED PLYWOOD AS BACKING PANELS FOR DATA & ELECTRICAL EQUIPMENT. INSTALL AT 1'-0" AFF TO FINISHED CEILING. PAINT PLYWOOD TO MATCH ADJACENT WALL FINISH. COORDINATE FINAL SIZE AND LOCATION WITH ELECTRICAL CONTRACTOR.

KEYNOTES PER SHEET



N
TRUE
PLAN
A3 1ST FLR PLAN - LAKE HOUSE
3/16" = 1'-0" | A102

1

2

3

4

5


6

7

FLOOR PLAN NOTES	
A.	BEFORE BEGINNING WORK, VERIFY THE EXISTENCE AND LOCATION OF PLUMBING, MECHANICAL AND ELECTRICAL SYSTEMS AND OTHER CONSTRUCTION AFFECTING THE WORK. IF DISCREPANCIES ARE DISCOVERED, NOTIFY ARCHITECT PROMPTLY.
B.	ALL DIMENSION STRINGS ARE TO FINISH FACE OF WALL, UNLESS NOTED OTHERWISE.
C.	VERIFY STRUCTURAL ELEMENTS AND FLOOR SLABS PRIOR TO CORING OR CUTTING. COORDINATE VERIFICATION METHOD WITH OWNER.
D.	REFER TO SHEET A100 FOR REFERENCED PARTITION TYPES AND DETAILS. WALLS NOT TAGGED ON THESE PLANS SHALL BE PARTITION TYPE WAA-S11.
E.	PROVIDE MOISTURE- AND MOLD-RESISTANT GYPSUM BOARD AT THE FOLLOWING LOCATIONS: ENTIRE WALL DIRECTLY BEHIND OR ADJACENT TO ANY PLUMBING FIXTURE INCLUDING, BUT NOT LIMITED TO, WATER CLOSETS, SHOWERS, DRINKING FOUNTAINS, SINKS, LAVATORIES AND EYEWASHES; AND ALL WALLS OF AREAS INCLUDING, BUT NOT LIMITED TO, CHANGING ROOMS, SINGLE OCCUPANT TOILET ROOMS, JANITOR CLOSETS, COMMERCIAL KITCHENS, DISHWASHING, ETC. WHERE CERAMIC TILE OR SOLID SURFACE WALL CLADDING IS SCHEDULED, PROVIDE CEMENT BOARD BACKER BOARD IN LIEU OF GYPSUM BOARD.
F.	LOCATE ALL DOOR JAMBS 4" FROM ADJACENT PERPENDICULAR WALL, UNLESS NOTED OTHERWISE.
G.	REPAIR, PATCH AND CLEAN ALL EXISTING SURFACES SCHEDULED TO REMAIN THAT ARE AFFECTED BY DEMOLITION OR NEW CONSTRUCTION. MAKE APPEAR NEW, MATCHING ADJACENT CONSTRUCTION. PREPARE ALL SURFACES AS REQUIRED FOR SCHEDULED FINISHES. SKIM COAT AND PREPARE ALL DAMAGED OR UNFINISHED SURFACES.
H.	PATCH ALL WALL BASE SCARS AT EXISTING WALL SURFACES. PREPARE SMOOTH TO RECEIVE NEW WALL BASE FOR UNIFORM APPEARANCE.
I.	PATCH WALLS TO MATCH ADJACENT SURFACES AT ALL ABANDONED OR REMOVED OUTLET AND SWITCH LOCATIONS. BLANK COVER PLATES ARE NOT ACCEPTABLE.
J.	PREPARE FLOOR LEVEL AND SMOOTH FOR NEW HARD SURFACE FINISHES. PATCH EXISTING PENETRATIONS AND ABNORMALITIES IN CONCRETE FLOOR.
K.	ALL AREAS DISTURBED BY DEMOLITION SHALL BE PATCHED AND PROPERLY PREPARED FOR NEW FINISH APPLICATIONS. WHERE ADJACENT FINISHES ARE EXISTING TO REMAIN, PATCH AND MATCH EXISTING FINISHES. CONSULT WITH THE OWNER TO IDENTIFY ATTIC STOCK AND/OR PREVIOUS MATERIAL SPECIFICATIONS.
L.	PROVIDE BLOCKING IN WALLS AS REQUIRED FOR NEW MILLWORK, CASEWORK, DOOR BUMPERS, ACCESSORIES, EQUIPMENT, FIXTURES, AND OWNERS WALL-MOUNTED EQUIPMENT, INCLUDING BUT NOT LIMITED TO, TELEVISIONS, MONITORS, MARKER BOARDS, TACK BOARDS AND SIGNAGE. OPEN EXISTING WALLS AS NEEDED TO INSTALL CONCEALED BLOCKING WHERE REQUIRED, AND PATCH WALLS TO MATCH EXISTING CONSTRUCTION. COORDINATE WITH OWNER ON LOCATIONS OF WALL-MOUNTED EQUIPMENT.
M.	PROVIDE 3/4" FIRE-RETARDANT TREATED PLYWOOD AS BACKING PANELS FOR DATA & ELECTRICAL EQUIPMENT. INSTALL AT 1'-0" AFF TO FINISHED CEILING. PAINT PLYWOOD TO MATCH ADJACENT WALL FINISH. COORDINATE FINAL SIZE AND LOCATION WITH ELECTRICAL CONTRACTOR.

KEYNOTES PER SHEET	
0641-100	8" DIAMETER BLACK METAL GROMMET - MCKEYTT TM28-80M
0641-101	10" DIAMETER BLACK METAL GROMMET - MCKEYTT TM108-80M
1021-01	PHENOLIC CEILING-HUNG TOILET PARTITIONS WITH FLUSH DOORS
1051-01	PHENOLIC 2-TIER LOCKERS
1051-02	PHENOLIC LOCKER BENCH
1120-02	SWIMSUIT SPINNER - SUITMATE EC3
1420-01	VERTICAL PLATFORM LIFT, 3 OPENINGS
A1010-01	RIGID INSULATION, DRAINAGE MAT, WATERPROOFING, FOUNDATION WALL
B2010-01	BRICK VENEER, AIR SPACE, RIGID INSULATION, AIR BARRIER, CONCRETE WALL
B2010-03	BRICK VENEER, AIR SPACE, RIGID INSULATION, AIR BARRIER, EXTERIOR SHEATHING, METAL STUDS W/ BATT INSULATION, GYPSUM BOARD

TOILET ROOM ACCESSORY SCHEDULE					
TAG	DESCRIPTION	LENGTH	MANUFACTURER	MODEL	REMARKS
CH01	BABY CHANGING STATION SURFACE MOLDED		KOALA	KB310-SWMM-MBLK	
GB02	GRAB BAR STRAIGHT	1'-6"	DELTA	CONTEMPORARY MB	MATTE BLACK
GB03	GRAB BAR STRAIGHT	2'-0"	DELTA	CONTEMPORARY MB	MATTE BLACK
GB05	GRAB BAR STRAIGHT	3'-0"	DELTA	CONTEMPORARY MB	MATTE BLACK
GB06	GRAB BAR STRAIGHT	3'-6"	DELTA	CONTEMPORARY MB	MATTE BLACK
GB23	GRAB BAR STRAIGHT	2'-0"	KOHLER	SQUARE K-23295-2MB	MODERNE BRASS
GB25	GRAB BAR STRAIGHT	3'-6"	KOHLER	SQUARE K-23297-2MB	MODERNE BRASS
NR20	MIRROR WITH FRAME		UTTERMOST	79251709200 TORREIRA ARCH BRASS	
ND01	SURFACE MOUNT NAPKIN DISPOSAL		BOBRICK	TRIMLINE SURFACE MOUNT	MATTE BLACK
PB04	SOAP DISH	0"		WALL MOUNT SHAMPOO SHELF	INCLUDE WITH SHOWER SURROUND
PB21	SOAP DISH, CORNER			CORNER MOUNT SHAMPOO SHELF	INCLUDE WITH SHOWER SURROUND
PD01	PAPER TOWEL DISPENSER, FOLDED SURFACE		BOBRICK	B-9262-MBLK	MATTE BLACK
SH11	SHOWER SEAT RECTANGLE		GBS	PHEN-RECTANGULAR-SEAT-WOODGR AIN 32"	WOOD GRAIN
SH21	SHOWER SEAT RECTANGLE		GBS	PHEN-RECTANGULAR-SEAT-WOODGR AIN 30"	WOOD GRAIN
SR01	CURTAIN ROD & CURTAIN	<varies>	GATCO	MODERN SHOWER ROD29MX	MATTE BLACK, INCLUDE HOOKLESS LINER AND CURTAIN FROM STANDARD TEXTILE
TP10	TOILET PAPER DISPENSER, DOUBLE SURFACE MOUNT		BOBRICK	B-540-MBLK B-540-MBLK B-540-MBLK	MATTE BLACK
TP20	TOILET PAPER DISPENSER, DOUBLE SURFACE MOUNT		KOHLER	SQUARE K-23288-2MB	MODERNE BRASS
TW40	TOWEL PIN		DELTA	TETRA 78935-BL	MATTE BLACK





milwaukee | madison | green bay | denver | atlanta

E

PROJECT INFORMATION

NORTH SHORE
GOLF CLUB - NEW
POOL & LAKE
HOUSE
IMPROVEMENTS


D N 8421 N Shore W Rd
Menasha, WI 54952

ISSUANCE AND REVISIONS

DATE	DESCRIPTION
07/25/2025	CONSTRUCTION DOCUMENTS

C

KEY PLAN



B

SHEET INFORMATION

PROJECT MANAGER TH
PROJECT NUMBER 923505

ROOF PLAN -
CHANGING BLDG



A104

© 2025 Epstein Uhen Architects, Inc.



FLOOR PLAN NOTES	
A.	BEFORE BEGINNING WORK, VERIFY THE EXISTENCE AND LOCATION OF PLUMBING, MECHANICAL, AND ELECTRICAL SYSTEMS AND OTHER CONSTRUCTION AFFECTING THE WORK. IF DISCREPANCIES ARE DISCOVERED, NOTIFY ARCHITECT PROMPTLY.
B.	ALL DIMENSION STRINGS ARE TO FINISH FACE OF WALL, UNLESS NOTED OTHERWISE.
C.	VERIFY STRUCTURAL ELEMENTS AND FLOOR SLABS PRIOR TO CORING OR CUTTING. COORDINATE VERIFICATION METHOD WITH OWNER.
D.	REFER TO SHEET A010 FOR REFERENCED PARTITION TYPES AND DETAILS. WALLS NOT TAGGED ON THESE PLANS SHALL BE PARTITION TYPE W4A.S11.
E.	PROVIDE MOISTURE- AND MOLD-RESISTANT GYPSUM BOARD AT THE FOLLOWING LOCATIONS: ENTIRE WALL DIRECTLY BEHIND OR ADJACENT TO ANY PLUMBING FIXTURE INCLUDING, BUT NOT LIMITED TO, WATER CLOSETS, SHOWERS, DRINKING FOUNTAINS, SINKS, LAVATORIES AND EYEWASHES; AND ALL WALLS OF AREAS INCLUDING, BUT NOT LIMITED TO, CHANGING ROOMS, SINGLE OCCUPANT TOILET ROOMS, JANITOR CLOSETS, COMMERCIAL KITCHENS, DISHWASHING, ETC. WHERE CERAMIC TILE OR SOLID SURFACE WALL CLADDING IS SCHEDULED, PROVIDE CEMENT BOARD BACKER BOARD IN LIEU OF GYPSUM BOARD.
F.	LOCATE ALL DOOR JAMBS 4" FROM ADJACENT PERPENDICULAR WALL, UNLESS NOTED OTHERWISE.
G.	REPAIR, PATCH AND CLEAN ALL EXISTING SURFACES SCHEDULED TO REMAIN THAT ARE AFFECTED BY DEMOLITION OR NEW CONSTRUCTION. MAKE APPEAR NEW, MATCHING ADJACENT CONSTRUCTION. PREPARE ALL SURFACES AS REQUIRED FOR SCHEDULED FINISHES. SKIM COAT AND PREPARE ALL DAMAGED OR UNFINISHED SURFACES.
H.	PATCH ALL WALL BASE SCARS AT EXISTING WALL SURFACES. PREPARE SMOOTH TO RECEIVE NEW WALL BASE FOR UNIFORM APPEARANCE.
I.	PATCH WALLS TO MATCH ADJACENT SURFACES AT ALL ABANDONED OR REMOVED OUTLET AND SWITCH LOCATIONS. BLANK COVER PLATES ARE NOT ACCEPTABLE.
J.	PREPARE FLOOR LEVEL AND SMOOTH FOR NEW HARD SURFACE FINISHES. PATCH EXISTING PENETRATIONS AND ABNORMALITIES IN CONCRETE FLOOR.
K.	ALL AREAS DISTURBED BY DEMOLITION SHALL BE PATCHED AND PROPERLY PREPARED FOR NEW FINISH APPLICATIONS. WHERE ADJACENT FINISHES ARE EXISTING TO REMAIN, PATCH AND MATCH EXISTING FINISHES. CONSULT WITH THE OWNER TO IDENTIFY ATTIC STOCK AND/OR PREVIOUS MATERIAL SPECIFICATIONS.
L.	PROVIDE BLOCKING IN WALLS AS REQUIRED FOR NEW MILLWORK, CASEWORK, DOOR BUMPERS, ACCESSORIES, EQUIPMENT, FIXTURES, AND OWNERS WALL-MOUNTED EQUIPMENT, INCLUDING BUT NOT LIMITED TO, TELEVISIONS/MONITORS, MARKER BOARDS, TACK BOARDS AND SIGNAGE. OPEN EXISTING WALLS AS NEEDED TO INSTALL CONCEALED BLOCKING WHERE REQUIRED, AND PATCH WALLS TO MATCH EXISTING CONSTRUCTION. COORDINATE WITH OWNER ON LOCATIONS OF WALL-MOUNTED EQUIPMENT.
M.	PROVIDE 3/4" FIRE-RETARDANT TREATED PLYWOOD AS BACKING PANELS FOR DATA & ELECTRICAL EQUIPMENT. INSTALL AT 1'-0" AFF TO FINISHED CEILING. PAINT PLYWOOD TO MATCH ADJACENT WALL FINISH. COORDINATE FINAL SIZE AND LOCATION WITH ELECTRICAL CONTRACTOR.

ROOF PLAN LEGEND	
RD	ROOF DRAIN
OFD	OVERFLOW DRAIN
DS	DOWNSPOUT
←	SLOPE DIRECTION OF ROOF & TAPERED INSULATION
■	TAPERED INSULATION
SEE SHEET A010 FOR ROOF ASSEMBLY INFORMATION	

KEYNOTES PER SHEET	
0535-01	1" X 3/16" GALV. STEEL BAR GRATING W/ L3X3X9/16 (GALV.) AND 5/8" DIA. S.S. EXPANSION ANCHORS AT 24" O.C. ON (4) SIDES
0776-16	PORCELAIN TILE PAVER SYSTEM - ADJUSTABLE PEDESTAL SYSTEM
1420-01	VERTICAL PLATFORM LIFT, 3 OPENINGS
B3010-01	ROOFING MEMBRANE, COVER BOARD, RIGID INSULATION, SLOPED PRECAST CONCRETE PLANKS



C2 ROOF PAVER PLAN - CHANGING BLDG
1/4" = 1'-0" | A104



A2 ROOF PLAN - CHANGING BLDG
1/4" = 1'-0" | A104

EXTERIOR ELEVATION NOTES

- A SEE SHEET A201 FOR EXTERIOR FRAME TYPES AND DIMENSIONS.
B ALL INSIDE AND OUTSIDE CORNERS OF PRECAST TRIM TO BE MITERED.
C EXTERIOR SIGNAGE ON BUILDING TO BE COORDINATED AND VERIFIED WITH ARCHITECT, OWNER AND SIGNAGE VENDOR.
D ALL VERTICAL INSIDE CORNERS TO HAVE 1/2" MOVEMENT JOINT.
E MJ = INDICATES MOVEMENT JOINT - 1/2" GAP.
F WINDOW DIMENSIONS ARE NOMINAL. CONTRACTOR TO ACCOUNT FOR SHIM SPACE IN WINDOW SIZING.

KEYNOTES PER SHEET



milwaukee | madison | green bay | denver | atlanta

E

PROJECT INFORMATION

NORTH SHORE
GOLF CLUB - NEW
POOL & LAKE
HOUSE
IMPROVEMENTS


D N 8421 N Shore W Rd
Menasha, WI 54952

ISSUANCE AND REVISIONS

DATE	DESCRIPTION
07/25/2025	CONSTRUCTION DOCUMENTS

C

KEY PLAN



B


SHEET INFORMATION

PROJECT MANAGER TH
PROJECT NUMBER 923505


EXTERIOR
ELEVATIONS - LAKE
HOUSE

A200

© 2025 Epstein Uhen Architects, Inc.



C1 SOUTH - LAKE HOUSE
1/4" = 1'-0" | REF: A3/A101



A1 EAST - LAKE HOUSE
1/4" = 1'-0" | REF: A3/A101

1

2

3

4

5

6

7

EXTERIOR ELEVATION NOTES

A	SEE SHEET A201 FOR EXTERIOR FRAME TYPES AND DIMENSIONS.
B	ALL INSIDE AND OUTSIDE CORNERS OF PRECAST TRIM TO BE MITERED.
C	EXTERIOR SIGNAGE ON BUILDING TO BE COORDINATED AND VERIFIED WITH ARCHITECT, OWNER AND SIGNAGE VENDOR.
D	ALL VERTICAL INSIDE CORNERS TO HAVE 1/2" MOVEMENT JOINT.
E	MJ = INDICATES MOVEMENT JOINT - 1/2" GAP.
F	WINDOW DIMENSIONS ARE NOMINAL. CONTRACTOR TO ACCOUNT FOR SHIM SPACE IN WINDOW SIZING.

KEYNOTES PER SHEET



milwaukee | madison | green bay | denver | atlanta

E

PROJECT INFORMATION

NORTH SHORE
GOLF CLUB - NEW
POOL & LAKE
HOUSE
IMPROVEMENTS


D N 8421 N Shore W Rd
Menasha, WI 54952

ISSUANCE AND REVISIONS

DATE	DESCRIPTION
07/25/2025	CONSTRUCTION DOCUMENTS

C

KEY PLAN



B


SHEET INFORMATION

PROJECT MANAGER TH
PROJECT NUMBER 923505


EXTERIOR
ELEVATIONS -
CHANGING BLDG

A201

© 2025 Epstein Uhen Architects, Inc.



A1 WEST - CHANGING BLDG
1/4" = 1'-0" | REF: A1/A103



A3 SOUTH - CHANGING BLDG
1/4" = 1'-0" | REF: A1/A103