



BUILDING SIDE

- ALUMINUM FACE CABINET
- ALUMINUM FORMED CABINET
- PUSH-THRU DEPTH = 1.27" (3/4" MATERIAL) TRANSLUCENT WHITE ACRYLIC
- TRANSLUCENT WHITE PRINTED VINYL DECAL - SEE COLOR SCHEDULE
- MATE LAMINATION FOR PRINTED VINYL
- 1/8" ALUMINUM FACES ROUTED / BACKED WITH LEXAN
- PAINTED W/ SATIN FINISH - SEE COLOR SCHEDULE
- INTERIALLY LIT W/ WHITE LEDS
- EMC UNIT
- D/F WATCHFIRE EMC UNITS
- FULL COLOR 10MM - R68
- SIZE: (67") X (29")
- V/D: (64") X (24")
- 120V POWER SUPPLIES 18.0 AMPS (9.0 PER FACE)
- SINGLE PHASE SERVICE
- SEPARATE CIRCUIT REQUIRED
- TEXTURE PLUS BASE
- FAUX STONE SUBSTRATE
- STYLE: FAUX CONTEMPORARY - INTERLOCK
- COLOR: TAN
- FORMED ALUMINUM CAP
- PAINTED W/ SATIN FINISH - SEE COLOR SCHEDULE
- 1/8" ROUTED ALUMINUM FLAT CHIPS - PAINTED W/ SATIN FINISH
- POLE FOUNDATION
- 6" STEEL SQUARE TUBE OR ROUND POLE
- DIRECT EMBED & DEEP
- INTO 2" DIAMETER AUGURED HOLE
- FILLED W/ CONCRETE
- ELECTRICAL CONDUIT REQUIRED FOR POWER

COLOR SCHEDULE

- 1 PAINT: SATIN WHITE
- 2 VINYL: CHARCOAL VINYL
- 3 PRINTED: TANS WHITE VINYL DECAL
- 4 PRINTED: PASTEL TOUC
- 5 PAINT: PMS COOL GREY

FIELD SERVICE REQUIRED?

ELECTRICAL REQUIREMENTS

- X INTERIALLY LIT WITH LEDS - POWER TO SIGN IS REQUIRED
- 120V - 277V POWER SUPPLIES USED

CLIENT APPROVAL

BY SIGNING THIS CONTRACT, YOU ARE AGREEING TO ALL SPECIFICATIONS, SCOPE OF WORK, AND SCHEDULE. YOU ARE ALSO AGREEING TO ALL CHANGES AND ADDITIONAL WORK ORDER CHARGES. YOU ARE AGREEING TO ALL CHANGES AND ADDITIONAL WORK ORDER CHARGES. YOU ARE AGREEING TO ALL CHANGES AND ADDITIONAL WORK ORDER CHARGES.

X DATE: _____

CALCULATED SQUARE FOOTAGE: **NA** **260129-01**

A OPT. 1 MANUFACTURE AND INSTALL THE FOLLOWING: A. ONE(1) D/F INTERNALLY LIT MORMENT SIGN W/ EMC FOR FIRE DEPARTMENT

DISCLAIMERS:

CONCEPTUAL ONLY! NOT FOR USE FOR PRODUCTION