

BID FORM

The undersigned has carefully examined the work items and will provide the products specified or approved equivalents for the following amounts:

Backstop: Furnish and install a 24 foot high backstop with 20-foot long sections. 6 gauge galvanized fabric on lower 12-foot tier. 9 gauge on the upper half. 4-inch posts concrete set \$ 27,673.00 and in words

Twenty Seven Thousand Six Hundred and Seventy Three Dollars

10-foot Sideline: Furnish and install two 70 foot runs of 10-foot-high galvanized chain link fence. Posts driven 6 feet deep. Three 1 5/8" horizontal rails and 9-gauge galvanized fabric \$ 8,617.99 and in words:

Eight Thousand Six Hundred and Seventeen Dollars and Ninety Nine Cents

6-foot Sideline: Furnish and install two 70 foot runs of 10-foot-high galvanized chain link fence with top rail and bottom tension wire. 9-gauge galvanized fabric. Post driven to 6 feet deep. One 10-foot double swing serve gate included \$ 6,542.20

and in Words: Six Thousand Five Hundred and Forty Two Dollars and Twenty Cents

4 foot Dugouts: Furnish and install 67 feet of 4-foot-high galvanized chain link fence with top and bottom rail. 9 gauge fabric. Post driven to 6 feet deep \$

3,370.61 Three Thousand Three Hundred and Seventy

and in words Dollars and Sixty One Cents

8-foot Outfield: Furnish and install 433 feet of 8-foot-high galvanized chain link fence plus one 12-foot single swing service gate. Fence shall have top wire and bottom tension wire. Posts driven to 6 feet deep. \$ 14,974.98 and words:

Fourteen Thousand Nine Hundred and Seventy Four Dollars and Ninety Eight Cents

Ever Secure Fence Sign Bracket: 100 brackets to reinstall existing advertising signs on the new chain link fence in the outfield \$ 1,100.22 and words: One Thousand One Hundred Dollars and Twenty Two Cents

Total Bid Amount: \$ 62,279.00


**** All existing fencing shall be removed prior to fence supplier mobilizing to complete the work by Harrison Athletic Association.**

Bidder: AmeriFence Corporation of Wisconsin

Address: 4701 McFarland

Phone Number: 608.509.5857

Email Address: j.scalero@americafence.com

Signature: Jackson Scalero A digital signature stamp is located over the signature line. It contains the following text: "Digitally signed by Jackson Scalero", "CN=J. Scalero, E=j.scalero@americafence.com, O=AmeriFence Corporation of Wisconsin, OU=Commercial Estimator", "C=US", and "Date: 2025.05.14 14:01:39 -05'00'".

Printed Name: Jackson Scalero

Title: Commercial Estimator Date: 05.14.2025

AMERIFENCE CORPORATION



AmeriFence Corporation - Kansas City • AmeriFence Corporation - Madison • American Security & Gate Company - Fargo
American Fence Company: Omaha • Lincoln • Grand Island • Kearney • Sioux City • Des Moines • Cedar Rapids • Sioux Falls • Rochester

FENCE PROPOSAL

Date: 05.14.2025	
Project: Harrison Athletic Association Fencing Proposal	
Project Location: W5298 WI-114 Trunk, Menasha, WI 54952	
Addendum Received: N/A	
Plan Sheets: Request for Bids	Specifications: Request for Bids

Project Scope Information:

Inclusions:

- Furnish & Install 60 LF of 24'H Chain Link Fence at the Backstop
 - Fabric:
 - Bottom: 12'H x 6ga (2" Mesh) Galvanized Chain Link Fabric KK
 - Top: (2 sections) 72"H x 9ga (2" Mesh) Galvanized Chain Link Fabric KK
 - Post: 4" O.D. Galvanized SS40 Steel Pipe set in a 18" O.D. x 72" Deep Concrete Footer
 - Rails: 1-5/8" O.D. Galvanized SS40 Steel Pipe spaced every 6' O.C.
- Furnish & Install 140 LF of 10'H Chain Link Fence at the Sideline
 - Fabric: 120"H x 9ga (2" Mesh) Galvanized Chain Link Fabric KK
 - Terminal Post: 3" O.D. Galvanized SS20 Steel Pipe driven 6' deep
 - Line Post: 2.5" O.D. Galvanized SS20 Steel Pipe driven 6' deep
 - Top, Middle, and Bottom Rail: 1-5/8" O.D. Galvanized SS40 Steel Pipe
- Furnish & Install 140 LF of 6'H Chain Link Fence with (1ea) 10'W Double Swing Gate at the Sideline
 - Fabric: 72"H x 9ga (2" Mesh) Galvanized Chain Link Fabric KK
 - Terminal Post: 2.5" O.D. Galvanized SS20 Steel Pipe driven 6' deep
 - Line Post: 2" O.D. Galvanized SS20 Steel Pipe driven 6' Deep
 - Top Rail: 1-5/8" O.D. Galvanized SS20 Steel Pipe
 - Bottom Tension Wire: 7ga Coil Spring Galvanized Tension Wire
 - Gate Frame: 1-5/8" O.D. Galvanized SS20 Steel Pipe
 - Gate Post: 4" O.D. Galvanized SS40 Steel Pipe set in a concrete footer
- Furnish & Install 67 LF of 4'H Chain Link Fence at the Dugouts
 - Fabric: 48"H x 9ga (2" Mesh) Galvanized Chain Link Fabric KK
 - Terminal Post: 2.5" O.D. Galvanized SS20 Steel Pipe driven 6' deep
 - Line Post: 2" O.D. Galvanized SS20 Steel Pipe driven 6' deep
 - Top & Bottom Rail: 1-5/8" O.D. Galvanized SS20 Steel Pipe
- Furnish & Install 433 LF of 8'H Chain Link Fence with (1ea) 12'W Double Swing Gate at the Outfield

- Fabric: 96"H x 9ga (2" Mesh) Galvanized Chain Link Fabric KK
- Terminal Post: 3" O.D. Galvanized SS20 Steel Pipe driven 6' deep
- Line Post: 2.5" O.D. Galvanized SS20 Steel Pipe driven 6' deep
- Brace Rail: 1-5/8" O.D. Galvanized SS20 Steel Pipe
- Top & Bottom Tension Wire: 7ga Coil Spring Galvanized Tension Wire
- Gate Frame: 1-5/8" O.D. Galvanized SS20 Steel Pipe
- Gate Post: 4" O.D. Galvanized SS40 Steel Pipe set in a concrete footer
- Furnish 100ea Ever Secure Fence Sign Bracket
 - Installation of brackets and signs is not included

If not listed herein, it is not included. Advise, prior to acceptance of required additional items.

Project Specific Notes & Exclusions:

1. No delegated design, engineering, or stamped engineered drawings included in price of proposal.
2. Permitting, Bid Bonds, and Performance & Payment Bonds are not included in this proposal.
3. Private Utilities must be marked by Others. AmeriFence will not be responsible for damage to unmarked Utilities.
4. Core drilling and rock drilling are not included in this proposal. If necessary, additional charges will apply.
5. Davis Bacon Wages and Prevailing Wages are not included in this proposal.
6. Proposal is not compliant with the BABA Act, Buy American Act, or American Iron and Steel requirements.
7. Removal of spoils is not included in this proposal. Spoils to be spread around AmeriFence excavations.
8. Tax is not included in this proposal.
9. Existing Fence must be removed prior to AmeriFence mobilizing.
10. Ever Secure Fence Sign Brackets are being furnished, but installation of the signs and brackets is not included. Signs are not included.

Start Date: Allow 2 weeks for submittals. Once approved, allow 6 weeks for receipt of materials

Crew Size: 2-3 depending upon available work.

Notes are specific to the scope and directly impact project pricing. If not agreeable, advise prior to acceptance.

Project Pricing:

Item No.	Description	Qty	Unit	Extension
1	Backstop	60	LF	\$27,673.00
2	10-Foot Sideline	140	LF	\$8,617.99
3	6-Foot Sideline	140	LF	\$6,542.20
4	4-Foot Dugouts	67	LF	\$3,370.61
5	8-Foot Outfield	433	LF	\$14,974.98
6	Ever Secure Fence Sign Bracket	100	EA	\$1,100.22
Bid Total:				\$62,279.00

Unless otherwise stated, pricing does not include sales tax, subject to change after 10 days of date of proposal. This proposal is not binding unless signature is affixed to page two. Do not sign and return this sheet without signed second page.

Amerifence Contact Information:

Name: Jackson Scalero

Email: j.scalero@americafence.com

Mobile: 608.354.9031

Office: 608.509.5857