

BID FORM

The undersigned has carefully examined the work items and will provide the products specified or approved equivalents for the following amounts:

Backstop: Furnish and install a 24 foot high backstop with 20-foot long sections. 6 gauge galvanized fabric on lower 12-foot tier. 9 gauge on the upper half. 4-inch posts concrete set \$ 15,660.00 and in words
Fifteen Thousand Six Hundred Sixty Dollars

10-foot Sideline: Furnish and install two 70 foot runs of 10-foot-high galvanized chain link fence. Posts driven 6 feet deep. Three 1 5/8" horizontal rails and 9-gauge galvanized fabric \$ 6,650.00 and in words:
Six Thousand Six Hundred Fifty Dollars

6-foot Sideline: Furnish and install two ¹⁵⁰~~70~~ foot runs of ⁶~~10~~-foot-high galvanized chain link fence with top rail and bottom tension wire. 9-gauge galvanized fabric. Post driven to 6 feet deep. One 10-foot double swing serve gate included \$ 7,275.00
and in Words: Seven Thousand Two Hundred Seventy Five Dollars

4 foot Dugouts: Furnish and install 67 feet of 4-foot-high galvanized chain link fence with top and bottom rail. 9 gauge fabric. Post driven to 6 feet deep \$ 2,144.00
and in words Two Thousand One Hundred Forty Four Dollars

8-foot Outfield: Furnish and install 433 feet of 8-foot-high galvanized chain link fence plus one 12-foot single swing service gate. Fence shall have top ^{rail}~~wire~~ and bottom tension wire. Posts driven to 6 feet deep. \$ 14,289.00 and words:
Fourteen Thousand Two Hundred Eight Nine Dollars

270

Ever Secure Fence Sign Bracket: ~~100~~ brackets to reinstall existing advertising signs on the new chain link fence in the outfield \$ 4,680.00 and words: Four Thousand Six Hundred Eighty Dollars

Total Bid Amount: \$ 50,698.00

**** All existing fencing shall be removed prior to fence supplier mobilizing to complete the work by Harrison Athletic Association.**

**** SEE LAST PAGE FOR FENCE BREAK DOWN, NOTES AND EXCLUSIONS ****

Bidder: CENTURY FENCE COMPANY

Address: 1225 LAKEVIEW DRIVE GREEN BAY, WI 54313

Phone Number: 920-857-2624

Email Address: jplate@centuryfence.com

Signature: Jason Plate

Printed Name: Jason Plate

Title: Estimator Date: 5/16/2025

**** SEE LAST PAGE FOR FENCE BREAK DOWN, NOTES AND EXCLUSIONS ****

Quote

Century Fence Company
1225 Lakeview Drive
Green Bay, WI 54313

**Quote To:**

VILLAGE OF HARRISON
W5298 STATE ROAD 114
HARRISON, WI 54952

Project Location:

HARRISON ATHLETIC ASSOCIATION
WEST BALLFIELD
W5298 STATE ROAD 114
44.19739129796914, -
88.30300235768854
HARRISON, WI 54952

Quote #: 30165

Quote Date: 5/16/2025

Description

24' H BACKSTOP

- All posts set in 12" x 72" concrete footings. Intermediate posts spaced at a maximum of 8' OC
- Horizontal rails will be spaced at every 6' OC across all (3) backstop sections, plus top and bottom rails. The middle section will include an additional horizontal rail 3' up from the ground

10' H SIDELINE FENCE

- 3" OD terminal posts and 2-1/2" OD line posts driven 6' deep. Line posts spaced at max of 10' OC

6' H SIDELINE FENCE

- 3" OD terminal posts, 3" OD gate posts and 2-1/2" OD line posts driven 6' deep. Line posts spaced at max of 10' OC

4' H DUGOUT FENCE

- 2-1/2" OD terminal posts and 2-1/2" OD line posts driven 6' deep. Line posts spaced at max of 10' OC

8' H OUTFIELD FENCE WITH FOUL POLES

- 3" OD terminal posts and 2-1/2" OD line posts driven 6' deep. Line posts spaced at max of 7' OC (closer together due to the signs being installed onto fence)
- The fence will include (2) 3" OD foul poles which will be 20' out of the ground and driven 6' deep. Painting of Posts by others.

RE-HANG (45) SIGNS ON OUTFIELD FENCE

- Re-hang up to (45) of the existing signs that were removed from the previous fence by others. Each sign will have (6) sign holders (one for each corner and two in the center)

Notes: Fence will follow the same layout as the current fence is in. There will be openings between the backstop and 10' H sideline fence as well as between the 6' H sideline fence and the 8' H outfield fence ; All posts and rails will be SS40 weight

Excludes: Any Netting Above Backstop, Painting Foul Poles, Existing Fence Removal, Asphalt Patching if Needed After Fence Removal (Fence removal by others)

Quote Valid For 15 days

Buyer's Signature: _____

Date: _____

Submitted by: _____

Jason Plate

Change

Acceptance:

This quote when accepted in writing by purchaser and by Century Fence Company includes the terms and conditions set forth on www.centuryfence.com which are incorporated by reference and becomes a contract between two parties. If the project is cancelled upon agreement and special materials were purchased, the customer agrees to pay 100% of the material cost

Terms of Payment: Net Cash upon receipt of invoice.

Jason Plate

Office: 920-857-2624

Cell: 920-360-6398

Email: jplate@ffence.com