

PLAN SYMBOLS LEGEND

EXISTING CONSTRUCTION TO BE DEMOLISHED	EXISTING CONSTRUCTION TO REMAIN	SPACE NAME
NEW WALL CONSTRUCTION - FOR INT. WALLS 1/2" C.P. BO. EACH SIDE OF 2x4 STUDS @ 16" O.C. (EXCEPT AS NOTED) - FOR EXT. WALLS SEE SECTION	NEW FOUNDATION CONSTRUCTION - REFER TO PLAN.	WINDOW TAG, SEE ELEVATIONS
EXISTING DOOR TO REMAIN	NEW DOOR - NUMBER REFERS TO DOOR SIZE	FRAMING DESIGNATIONS
SPECIAL NOTE - REFER TO KEY NOTES ON SHEET	ALIGN SYMBOL	SECTION SYMBOL
DRAWING NUMBER		

ELECTRICAL SYMBOLS LEGEND

SINGLE POLE SWITCH	INCANDESCENT CEILING-MOUNTED LIGHT FIXTURE
THREE WAY SWITCH	INCANDESCENT WALL-MOUNTED LIGHT FIXTURE
DIMMER SWITCH	PENDANT LIGHT FIXTURE
DOOR SWITCH	INCANDESCENT WALL SCONCE FIXTURE
200V. 30A RECEPTACLE, UNLESS NOTED OTHERWISE	RECESSED CEILING FIXTURE
DUPLEX RECEPTACLE	INCANDESCENT WALL WASHER
GROUND FAULT INTERRUPTER DUPLEX RECEPTACLE	UNDER CABINET LIGHT FIXTURE
QUAD RECEPTACLE	EXTERIOR FLOOD LIGHT
WATERPROOF DUPLEX RECEPTACLE	FAN / INCANDESCENT LIGHT FIXTURE COMBINATION
DUPLEX RECEPTACLE ON DEDICATED CIRCUIT	EXHAUST FAN - VENT TO EXTERIOR
DUPLEX RECEPTACLE - FLOOR MOUNTED	SMOKE DETECTOR / CARBONMONOXIDE DETECTOR TO BE HARDWIRED, INTERCONNECTED W/ BATTERY BACK-UP IN EACH UNIT.
TELEPHONE JACK	
CABLE TV JACK	
DOOR BELL	

DEMOLITION KEY NOTES: FOUND./GARAGE

1. REMOVE EXISTING FOUNDATION AND ASSOCIATED FOOTINGS AS SHOWN.
2. REMOVE EXISTING CHIMNEY IN ITS ENTIRETY.
3. REMOVE EXISTING MASONRY STAIRS & LANDING IN THEIR ENTIRETY.
4. REMOVE EXISTING WOOD STAIRS & DECK IN THEIR ENTIRETY.

CONSTRUCTION KEY NOTES: FOUND./GARAGE

1. NEW INSULATED FLOOD VENT BY SMART VENT #1540-520 (OR APPROVED EQUAL).
2. INSTALL EXISTING CRANK ACCESS OPENING (IF USING EXISTING FOUNDATION).
3. PROVIDE CONCRETE LANDING PAD W/ FOOTING AS SHOWN.
4. FIRE RATED CEILING STRUCTURE AT GARAGE (SEE DETAIL).
5. PROVIDE NEW ONE-HOUR FIRE RATED, FIBERGLASS INSULATED DOOR WITH (3) ST. STL. HINGES.
6. NEW 36" WIDE WOOD STAIRS & RAILINGS FROM ACCESS FOYER TO FIRST FLOOR.
7. INSTALL 18" DEEP SHELF & CLOTHES ROD. PROVIDE CENTER SUPPORT ROOF IF LONGER THAN 5'.
8. 5" SLAB - W/ EXO 10/10 MIN ON RAIL VAPOR BARRIER AND 5" CRUSHED STONE ON COMPACTED DIRT.
9. 3" SLAB - W/ EXO 10/10 MIN ON RAIL VAPOR BARRIER AND 5" CRUSHED STONE ON COMPACTED DIRT.
10. INSTALL SMOKE & CO DETECTOR(S) AS REQUIRED BY CODE. (TYPICAL)
11. ALT. DOOR HEADER: STEEL BEAM, W10x45 FOR SINGLE 18" DOOR OHD.
12. 1-HOUR RATED PARTITION (SEE DETAIL)
13. 5" DIA. STEEL "LALLY" COLUMN ON 36"x12" CONCRETE FOOTING.

RES-CHECK "R" VALUES USED ARE AS FOLLOWS:
WALLS R-38
FLOORS & ROOFS R-50 MIN.
TRIPLE GLAZED DOORS & WINDOWS R-5

IN COMPLIANCE W/RC TABLE R301.2.1.2 "PROTECTION OPENINGS", ALL WINDOWS WILL USE "OPENING PROTECTIVES" AS ALLOWED UNDER THE EXEMPTION, USING 7/16" PLYWOOD AND CORROSION RESISTANT ATTACHMENT HARDWARE (SCREWS, ETC.) IN COMPLIANCE WITH ASCE 7.

FOUNDATION PLAN

Scale: 1/4"=1'-0"


Landgrebe- Highlands, NJ

JAMES T. DALEY
ARCHITECT
& ASSOCIATES
273 FIRST STREET, KEYPORT, NJ 07735
phone 732-739-2584 fax 732-739-0837

NJ LIC
#11519

DRAWN BY


A-2



FIRST FLOOR PLAN
Scale: 1/4"=1'-0"

- DEMOLITION KEY NOTES: FIRST FLOOR**
1. REMOVE EXISTING PARTITION & ASSOCIATED DOORS, WINDOWS, MILLWORK, PLUMBING, ELECTRICAL, OUTLETS, ETC. FORMING BRICK TO NEAREST JUNCTION BOX, DISCONNECT & TERMINATE AS REQUIRED BY CODE. SUPPORT & PROTECT BUILDING TO REMAIN AS REQUIRED. PATCH REMAINING WALLS AS REQ'D.
 2. REMOVE EXISTING WINDOW, INFILL TO MATCH EXISTING ADJACENT. PREP FOR NEW INTERIOR & EXTERIOR FINISHES.
 3. REMOVE EXISTING INTERIOR COLUMN. PATCH, PREP, & RETINISH FLOOR & CEILING AS REQUIRED.
 4. REMOVE EXISTING SINK, TOILET, ETC. REMOVE AND CAP ALL ASSOCIATED PLUMBING.


- CONSTRUCTION KEY NOTES: FIRST FLOOR**
1. SUPPLY J-BOX W/ POWER FOR APPLIANCE AS PER MANU. SPECIFICATIONS.
 2. SUPPLY J-BOX W/ POWER FOR RANGE HOOD AS PER MANU. SPECIFICATIONS.
 3. CUSTOM MILLWORK CABINETRY. PROVIDE SHOP DRAWINGS PRIOR TO CONSTRUCTION.
 4. INSTALL NEW MARBLE SADDLE W/ BEVELED EDGES @ DOOR TRANSITION FROM WOOD FLOOR TO TILE FINISH.
 5. INSTALL RECESSED MEDICINE CABINET CENTERED ON SINK.
 6. 1000 CFM EXHAUST FAN.
 7. INSTALL 18" DEEP SHELF & CLOTHES ROD. PROVIDE CENTER SUPPORT RODS IF LONGER THAN 9'.
 8. 3/4" WIDE (O.C. TO VERRY) WOOD STAIRS AND RAILING AS SHOWN.
 9. CUSTOM BANQUETTE SEATING AS PER OWNER.
 10. INSTALL SMOKE & CO DETECTORS AS REQUIRED BY CODE. (TYPICAL)
 11. MILLWORK SHELVING, REVIEW WOOD FINISH & SPACING WITH OWNER.



ELEVATOR SECTION
Scale: 1/4"=1'-0"

ACCREDITED HOME ELEVATOR OR EQUAL

CONTRACTOR TO COMPLY WITH ELEVATOR SPECS. FROM MANUFACTURER FOR SHAFT SIZE, PIT DEPTH & CLEARANCE AT TOP.



ELEVATOR PLAN
Scale: 1/2"=1'-0"

PLAN SYMBOLS LEGEND

---	EXISTING CONSTRUCTION TO BE DEMOLISHED	□	SPACE NAME
---	EXISTING CONSTRUCTION TO REMAIN	△	WINDOW TAG, SEE ELEVATIONS
---	NEW WALL CONSTRUCTION - FOR INT. WALLS: 1/2" CYP. BD. EACH SIDE OF 2x4 STUDS @ 16" O.C. (EXCEPT AS NOTED) - FOR EXT. WALLS SEE SECTION	---	FRAMING DESIGNATIONS
---	NEW FOUNDATION CONSTRUCTION - REFER TO PLANS	---	---
---	EXISTING DOOR TO REMAIN	---	---
---	NEW DOOR - NUMBER REFERS TO DOOR SIZE	---	---
---	SPECIAL NOTE - REFER TO KEY NOTES ON SHEET	---	---
---	ALIGN SYMBOL	---	---
---	SECTION SYMBOL - SECTION LETTER	---	---
---	DRAWING NUMBER	---	---

ELECTRICAL SYMBOLS LEGEND

⊕	SINGLE POLE SWITCH	⊕	INCANDESCENT CEILING-MOUNTED LIGHT FIXTURE
⊕	THREE WAY SWITCH	⊕	INCANDESCENT WALL-MOUNTED LIGHT FIXTURE
⊕	THREE WAY SWITCH	⊕	WET RATED FOR EXTERIOR INSTALLATIONS
⊕	DIMMER SWITCH	⊕	PENDANT LIGHT FIXTURE
⊕	DOOR SWITCH	⊕	INCANDESCENT WALL SCONCE FIXTURE
⊕	250V, 30A RECEPTACLE, UNLESS NOTED OTHERWISE	⊕	RECESSED CEILING FIXTURE
⊕	DUPLEX RECEPTACLE	⊕	INCANDESCENT WALL WASHER
⊕	GROUND FAULT INTERRUPTER DUPLEX RECEPTACLE	⊕	UNDER CABINET LIGHT FIXTURE
⊕	QUAD RECEPTACLE	⊕	EXTERIOR FLOOD LIGHT
⊕	WATERPROOF DUPLEX RECEPTACLE	⊕	FAN / INCANDESCENT LIGHT FIXTURE COMBINATION
⊕	DUPLEX RECEPTACLE ON DEDICATED CIRCUIT	⊕	EXHAUST FAN - VENT TO EXTERIOR
⊕	DUPLEX RECEPTACLE - FLOOR MOUNTED	⊕	SMOKE DETECTOR / CARBONMONOXIDE DETECTOR TO BE HARDWIRED, INTERCONNECTED W/ BATTERY BACK-UP IN EACH UNIT.
⊕	TELEPHONE JACK	⊕	
⊕	CABLE TV JACK	⊕	
⊕	DOOR BELL	⊕	

Landgrebe - Highlands, NJ

JAMES T. DALEY
ARCHITECT
+ ASSOCIATES
279 FIRST STREET, KEYPORT, NJ 07735
phone: 732-739-2584 fax: 732-739-0837

NJ LIC
#11519

DRAWN J.P.

A-3





1. SUPPLY J-BOX W/ POWER FOR APPLIANCE AS PER MANU. SPECIFICATIONS.
2. INSTALL 3/8" DIA. (MIN.) CEILING MOUNTED CEILING FAN WITH INTEGRAL LIGHT. PROVIDE SEPARATE WALL SWITCHES FOR EACH FUNCTION.
3. 3/8" WIDE (G.C. TO VERIFY) MOOD STAIRS AND RAILING AS SHOWN.
4. INSTALL NEW MARBLE SADDLE W/ BEVELED EDGES @ DOOR TRANSITION FROM WOOD FLOOR TO TILE FINISH.
5. INSTALL RECESSED MEDICINE CABINET COUNTER ON VANITY.
6. 1000 CFM EXHAUST FAN.
7. INSTALL 18" DEEP SHELF @ CLOTHES ROD. PROVIDE CENTER SUPPORT RODS IF LONGER THAN 5'.
8. INSTALL SMOKE & CO DETECTORS AS REQUIRED BY CODE. (TYPICAL)
9. CABLE RAILING (SPEC. TO FOLLOW).

1. DOUBLE JOISTS UNDER TUB/SHOWER
- CUSTOM SHOWER STALL - INSTALL 1/2"X4"X8" HARDBOARD 500 ON WALLS & CEILING OVER 1/4" TUB MASTIC BARRIER, OVER FLOOR W/ 1/4" X4" X8" HARDBOARD, AS PER MANUFACT. INSTALL MID-BED TO SHORE A MIN. OF 1/4" PER FOOT, HIGH SUBSTRATE UNDER SHALL MATCH THIS SPEC. INSTALL 1/2"X4"X8" HARDBOARD OVER THE CORNERS & EXTENDING A MIN. 3" UP WALLS AND OVER THE GUBS AT THE ENTRY. FINISH FLOOR W/ BUILT-UP MUD BED & TILE. FINISH WALLS & CEILING W/ MASTIC & TILE.
- NON FRAMELESS GLASS SHOWER DOOR/ENCLOSURE
- SHOWER ENCLOSURES INCLUDE SEAT, RECESSED SHAMPOO SHED TWO SHAMPOO SHELVES AND A WASH CLOTH BAR. SUBMIT SHOP DRAWINGS FOR APPROVAL.
2. DOUBLE JOISTS UNDER TUB/SHOWER
- TUB/SHOWER STALL - INSTALL 1/2"X4"X8" HARDBOARD 500 ON WALLS & CEILING OVER 1/4" TUB MASTIC BARRIER, AS PER MANU. SPEC. FINISH WALLS & CEILING W/ MASTIC & TILE.
- NON FRAMELESS GLASS SHOWER DOOR & ENCLOSURE
- SHOWER ENCLOSURES INCLUDE RECESSED SHAMPOO SHED TWO SHAMPOO SHELVES AND A WASH CLOTH BAR. SUBMIT SHOP DRAWINGS FOR APPROVAL.



1. INSTALL 3/8" DIA. (MIN.) CEMENT MOUNTED CEMENT FAN WITH INTEGRAL LIGHT. PROVIDE SEPARATE WALL SWITCHES FOR EACH FUNCTION.
3. 3/6" WIDE (C.G. TO VERIFY) MOOD STAIRS AND RAILING AS SHOWN.
4. INSTALL NEW MARBLE SADDLE W/ BOULED EDGES @ DOOR TRANSITION FROM INTERIOR FLOOR TO TILE FLOOR.
5. INSTALL RECESSED MEDICINE CABINET. CENTER ON VANITY.
6. 1000 CM DRYWALL FIN.
7. 1000 CM 1" DEEP SHELF @ CLOTHES ROD. PROVIDE CLOTHES SUPPORT RODS IF LONGER THAN 5'.
8. MILLWORK SHELVING, MIRROR, WOOD FINISH & SPACING WITH DINNER.
9. CABLE RAILING (SPEC. TO FOLLOW).
10. INSTALL SMOKE & CO DETECTORS AS REQUIRED (BY CODE, TYPICAL).
11. TRIM TRIMMED OPENINGS W/ 3/4" POPLAR. EXTEND TRIM 3/4" PAST OP.SD.
12. EACH SIDE-VERIFY FINISH W/ OWNER.

1. DOUBLE JOISTS UNDER TUB/SHOWER.
CUSTOM SHOWER SLAT - INSTALL 1/2" JAMES HARDBOARD 500 ON WALLS & CEILING OVER 15# FELT MOISTURE BARRIER, COVER FLOOR W/ 1/4" JAMES HARDBOARD, AS PER MANU. SPEC. INSTALL MUD-BED TO SLOPE A MIN. OF 1/4" PER FOOT, EACH SUCCESSIVE LAYER SHALL MAINTAIN THIS SLOPE. INSTALL A CONTINUOUS MEMBRANE FOLDED INTO THE CORNERS & EXTENDING A MIN. 3" UP WALLS & OVER THE CURB TO THE ENTRY. FINISH FLOOR W/ BUILT-UP MUD BED & TILE. FINISH WALLS & CEILING W/ MASTIC & TILE.
NEW FRAMELESS GLASS SHOWER DOOR/ENCLOSURE.
SHOWER ACCESSORIES INCLUDE SEAT, RECESSED SOAP DISH TWO SHAMPOO SHELVES AND A WASH CLOTH BAR, SUBMIT SHOP DRAWINGS FOR APPROVAL.





	SINGLE POLE SWITCH		INCANDESCENT CEILING-MOUNTED LIGHT FIXTURE
	THREE WAY SWITCH		INCANDESCENT WALL-MOUNTED LIGHT FIXTURE
	THREE WAY SWITCH		WET RATED FOR EXTERIOR INSTALLATIONS
	DIMMER SWITCH		PENDANT LIGHT FIXTURE
	DOOR SWITCH		INCANDESCENT WALL SCONCE FIXTURE
	250V, 30A RECEPTACLE		RECESSED CEILING FIXTURE
	UNLESS NOTED OTHERWISE		INCANDESCENT WALL WASHER
	DUPLEX RECEPTACLE		UNDER CABINET LIGHT FIXTURE
	GROUND FAULT INTERRUPT DUPLEX RECEPTACLE		EXTERIOR FLOOD LIGHT
	QUAD RECEPTACLE		FAN / INCANDESCENT LIGHT FIXTURE COMBINATION
	WATERPROOF DUPLEX RECEPTACLE		EXHAUST FAN - VENT TO EXTERIOR
	DUPLEX RECEPTACLE ON DEDICATED CIRCUIT		SMOKE DETECTOR / CARBON MONOXIDE DETECTOR
	DUPLEX RECEPTACLE - FLOOR MOUNT		TO BE HARDWIRED, INTERCONNECTED W/ BATTERY BACK-UP IN EACH UNIT.
	TELEPHONE JACK		
	CABLE TV JACK		
	DOOR BELL		

JAMES T. DALEY
A R C H I T E C T
+ A S S O C I A T E S
273 FIRST STREET, KEYPORT, NJ 07735
phone: 732-739-2684 fax: 732-739-0837






DRAWN: J

A-4





B BUILDING SECTION
Scale: 1/4"=1'-0"



WFCM HIGH WIND NAILING SCHEDULE (120 MPH)


JOIST TO SILL OR GIRDERS:
SOLE PLATE TO JOIST OR BLOCKING:
TOP OR SOLE PLATE TO STUD:
STUD TO SOLE PLATE:
DOUBLE TOP STUDS:
DOUBLE TOP PLATES:
-OFFSET LAPS 48" MIN.
TOP PLATE LAPS AT CORNERS AND INTERSECTIONS:
BUILT UP HEADER, TWO PIECE WITH SPACER:
CONTINUOUS HEADER, TWO PIECES:
CEILING JOISTS TO PLATE:
CEILING JOISTS LAPPED OVER PARTITIONS:
CEILING JOISTS TO PARALLEL RAFTERS:
RAFTERS TO PLATE:
RAFTERS TO RIDGE, VALLEY, HIP:
RAFTER TIES TO RAFTERS:
PLYWOOD TO FRAMING (for 15' o.c. spacing or less):
For 5/8"=1-1/4" (top & wall), 8d (end) @ 6" o.c. edges, 12" o.c. field.
For 15/32"=1-1/8" @ 6" o.c. edges, 6" o.c. field.
For 1/2"=1-1/4" galv. roofing nail or 8d @ 4" o.c. edges, 8" o.c. field.
For 5/8"=1-1/4" galv. roofing nail or 8d @ 4" o.c. edges, 8" o.c. field.
For 3/4"=1-1/8" 8d deformed or 8d @ 6" o.c. edges, 12" o.c. field.
For 1-1/8"=1-1/4"=8d deformed or 10d @ 8" o.c. edges, 12" o.c. field.

WIND UPLIFT STRAP/NAIL GUIDE

120 MPH

TRUSS CLIP (SIMPSON)	HOUSE WIDTH (FEET)							
	24	26	30	32	34	36	38	40
ENDWALL PLYWOOD EDGE NAIL SPACING	6"	6"	6"	6"	6"	6"	6"	6"
ENDWALL PLYWOOD EDGE NAIL SPACING	4"	4"	4"	4"	4"	4"	4"	4"
PLYWOOD TOP & BOTTOM NAIL SPACING	4"	4"	4"	4"	4"	4"	4"	4"
PLYWOOD SP-4 STRAP @	48"	48"	48"	48"	48"	48"	48"	48"
PLYWOOD TOP & BOTTOM NAIL SPACING	6"	6"	6"	6"	6"	6"	6"	6"
SIMPSON SP-4 STRAP @	32"	32"	32"	32"	32"	32"	32"	32"

STRAP/NAIL GUIDE PARAMETERS: SLAB ON GRADE
STRUCTURE LENGTH=60 FEET
TRUSS SPACING=16 INCH
STUD SPACING=16 INCH
STUD TYPE=SPRUC



Landgrebe - Highlands, NJ

JAMES T. DALEY
ARCHITECT
& ASSOCIATES

273 FIRST STREET, KEYPORT, NJ 07735
phone 732-736-2664 fax 732-736-0637

NJ LIC
#15159

DRAWN: JP

A-8

Figure 1 is a cross-sectional diagram of a 12-in. diameter prestressed concrete pile. The diagram shows a central 11-in. diameter section with a 11/16-in. diameter hole. The outer shell is 1/2-in. thick. The total diameter is 12 in. The diagram is labeled with dimensions and a note: "MIN. RATING REQUIRED".

[illegible]

A detailed technical cross-section diagram of a foundation wall assembly. The diagram illustrates the following components and dimensions from top to bottom:

- Top Section:** A horizontal layer labeled "0 1/2\" T4" with a "ROST. HANGER" below it.
- Insulation:** A thick vertical layer of "NEW R-25 FLOOR INSULATION" on the exterior side.
- Wall Core:** A vertical section of "11\" ICF UNITS BY: BUILD BLOCKCO." with a "1\" gap" between units.
- Internal Structure:** An "ICF LEADER CONNECTION SYSTEM (BY SIMPSON) - BOLTED" is shown within the wall.
- Garage Area:** On the interior side, there is a "GARAGE /FOYER" area with a "2x12" joist and "2\" MIN." gap.
- Concrete Garage Slab:** A "5\" CONCRETE GARAGE SLAB (2\" IN FUTURE W/ASB MIN-AT-OR ABOVE FINISHED GRADE)" is shown.
- Barrier:** A "GAS VAPOR BARRIER" is located between the concrete slab and the exterior insulation.
- Exterior Layers:** A "1/2\" CEMENT PARGE" is applied to the exterior face of the ICF units.
- Grading:** The exterior surface is graded, with a "GRADE" line indicated.
- Foundation Footing:** The base consists of a "12\"x24\" CONCRETE FOOTING, 3000 PSI W/ (3) #4 REBAR EACH WAY." with a "12\" height and "2'-0\" FOOTING" width.
- Backfill:** The area between the footing and the exterior wall is filled with "COMPACTED IMPERVIOUS FILL".

11" x 17" UNITS W/ BUILD BLOCKCOM

FLOOR FINISHING
NAILING AT 6" IN O.C.
(NAIL) TO JOIST W/
HOLD-DOWN

1/2" x 4" ONLY, USE
SCREWING W/ LUGGER
50K OR SHAPESIN IN
ACCORDANCE W/ IRC
TABLE R502.2.2.1 (IRC
TABLE 1907.2)

FLASHING-ALUM. 20 ga. MIN.
ENVI. PYLWOOD & LEDGER

FLASHING-ALUM. 20 ga. MIN.
BEH. SONDHONG-OR LEADER

2x10 P.T. LEDGER BOARD

5/4" x 16, BEADING (OIL
TREAT, 2X12" OR WOOD)

2x6 P.T. DECK JOIST

TENSION THE HTA STRIPS
BY SHAPESIN OR APPROVED
EQUAL, MOUNT ONE EACH 18"
FROM END OF DECK,
HORIZONTALLY.

"TEDO" JOIST HANGER

1/2" CBB SHAPESIN
WALLS ONLY

Diagram illustrating the construction details of a window assembly, showing the relationship between the window frame, wall structure, and insulation.

Labels and components shown in the diagram:

- SIDING
- TRIM
- 1/2" OSB SHEATHING WALLS ONLY
- 2x4 WALL STUDS, 16" O.C.
- ALT. METAL STUD
- 11" OF UNITS BY BUILD BLOCK.COM
- PITCH SILL
- 2x4 WALL STUDS, 16" O.C.
- ALT. METAL STUD
- R19 WALL INSULATION
- 1/2" GYP. BD.
- AS REAR AS HEAD, S.C. TO CONFORM W/ O.F. MANUF. FOR QUANTITIES/SPACING
- 2x12
- EXTENDED WINDOW TRIM/SILL
- 2x12

Technical drawing of a window sill assembly showing a cross-section. The drawing includes the following labels and dimensions:

- POWDER COATED METAL CABLE RAILS BY: TOLUENTS PAUL SYSTEM**
- 2 1/2" x 3/8" x 1/8" METAL STANCHION**
- W/POWDER COAT FINISH**
- FIBERGLASS DECK PRICKED AWAY FROM HOUSE SLOPE: 1/4" PER 12"**
- SILICONE CAULK**
- 4" BUSHY GRIP KISS SELF DRILLING SCREWS**
- NEW RIPPED FLOOR JOISTS**
- 2x12 SILL**
- 11" ST UNITS BY: BILD BLOODLOOM**
- 1/2" PLYWOOD**
- 5/4" PLYWOOD**
- 2x6 SLEEPER TAPERED TO FIT AWAY FROM HOUSE**
- #6 REBAR AS REQUIRED, G.C. TO CONFORM WITH ICF MANUF. FOR QUANTITIES/SPACING**
- FRONT SILL/CURT**

REAR BALCONY

5/4" THL DECKING (OPT. TREX, AZEK OR WOOD)

2x10 PL. DECK JOIST -CANTILEVERED

POWDER COATED METAL CABLE RAILS BY: ATLANTIS RAIL SYSTEM

2 1/2" x 3/8" THL METAL STRINGER W/POWDER COAT FINISH

4) 8x15 DRILL BITSS SELF DRILLING SCREWS

"TODENSE" SHALING SYSTEM BY
TIMBER TECH, COLOR: SLATE GREY
WITH METAL CABLE RAILS (TYP.)

5.5" X 6" BECKING-SCREWED
DOWN TENS. CABLE SYSTEM
COLOR: SLATE GREY

"SIMPSON" HURRICANE
TIE #1

2x8 JOIST

2x8 RM JOIST

3/4" X 6" X 10" TRIM
BOARD OR EQUAL

7/16" X MIN. 10"
CORRUG. BOLTS
GALVANIZED

2x12 P.T.
(ORDER, MAILED)

1 1/2" NOTCH SEAT

6x6 P.T. POST

2 3/4"

"SIMPSON" RMW ADJUST.
BASE W/ STANDOFF FOR
6x6 POST

GRADE

14" DIA. CONCRETE
FOOTING (U.O.N.)

10" DIA. SUTURE
BOTTOM-UP HOLE
OF SUTURE

5'-0"


VIBRON
SOIL

[illegible][illegible]



REAR ELEVATION

Scale: 1/4"=1'-0"




ROOF PLAN

Scale: 1/8"=1'-0"

ROOFING GENERAL/KEY NOTES:

- VERIFY ALL DEMOLITION DIMENSIONS WITH CONSTRUCTION DIMENSIONS ON FLOOR PLANS, COORDINATE AS REQUIRED.
 PROTECT ALL EXISTING CONSTRUCTION & MATERIALS AS REQUIRED DURING ALL PHASES OF CONSTRUCTION, COORDINATE WITH OWNER.
 INSTALL NEW EXTERIOR ROOFING (40 YEAR ASPHALT, COLOR TO FOLLOW), WITH NEW UNDERLAMENT & GUTTERS THROUGHOUT.
1. NEW METAL STANDING SEAM ROOF - FINISH SPEC. TO FOLLOW.
 2. NEW SKYLIGHTS AS SHOWN.
 3. REFER TO SOLAR PANEL DRAWING FOR LAYOUT: COULBERN EDO X
 4. REFER TO SOLAR PANEL DRAWING FOR LAYOUT: SONENHOT HOT WATER SYSTEM



SOLAR PANEL PLAN

Scale: 1/8"=1'-0"



SIDE ELEVATION

Scale: 1/4"=1'-0"

ELEVATION KEY NOTES:

- GENERAL:
 VERIFY ALL DEMOLITION DIMENSIONS WITH CONSTRUCTION DIMENSIONS ON FLOOR PLANS, COORDINATE AS REQUIRED.
1. 12" COURSE SIDING: FIBER CEMENT OR COMPOSITE BY HARDIE, INCHES OR EQUAL.
 2. CORRUGATED VERTICAL METAL (ALUM./STEEL) SIDING IN EXTERIOR ACCENTED VERTICAL AREAS AS SHOWN (SPEC. TO FOLLOW).
 3. FIBERGLASS BALCONY WITH METAL CABLE RAIL SYSTEM (SEE DETAIL).
 4. WOOD BALCONY WITH METAL CABLE RAIL SYSTEM (SEE DETAIL).
 5. WOOD DECK & 36" WIDE WOOD STAIRS W/METAL CABLE RAIL SYSTEM (SEE DETAIL).
 6. 16" WIDE OHD GARAGE DOORS BY CLOPAY OR APPROVED EQUAL.
 7. OPERABLE/ELECTRIC SKYLIGHT WITH RAIN SENSOR CLOSER.
 8. NEW METAL STANDING SEAM ROOF - FINISH SPEC. TO FOLLOW.
 9. 2 1/2"x2 1/2" TUBE STEEL BRACKETS AS SHOWN (FINISH T.B.D.)-TYPICAL FOR 9
 10. CONCRETE PLASTER AS SHOWN.
 11. 50 YEAR ASPHALT ROOF - SEE SOLAR PANEL LAYOUT BY OWNER.
 12. 18" COURSE SIDING: FIBER CEMENT OR COMPOSITE BY HARDIE, INCHES OR EQUAL.

Landgrebe- Highlands, NJ

JAMES T. DALEY
 ARCHITECT
 + ASSOCIATES
 273 FIRST STREET, KEYPORT, NJ 07735
 phone 732-739-2984 fax 732-739-0637

NJ LIC
 #11519

DRAWN J.P.

A-6



