



The Construction & Design Group, Inc.

9825 W Roosevelt Rd, Westchester, IL 60154 | Mailing P.O. Box 1276 North Riverside, IL 60516
Phone: 708-434-0443 Fax: 708-298-5733

Village of Homewood **paver repair /install from Hickory to 183rd along Harwood Ave.**

Address: 17755 Ashland avenue
Homewood IL 60430

Phone: 708 206 3470
Fax: 708 206 3499

Attention: Patrick Mc Aneney, Max Massi

Date: September ,12 2022

Subject: paver repair and install existing pavers

C & D's Quote No: B0220912- Proposal Validity: 30 Calendar Days from the date above
1

Construction & Design Group is pleased to submit our proposal to for the work described and detailed below:

1 This proposal has included the following items:

- | | | | | |
|---|--|------------------------------------|---|---|
| <input checked="" type="checkbox"/> Supervision | <input checked="" type="checkbox"/> Labor | <input type="checkbox"/> Material | <input checked="" type="checkbox"/> Tools | <input checked="" type="checkbox"/> Small Equipment |
| <input type="checkbox"/> Crane | <input checked="" type="checkbox"/> Design | <input type="checkbox"/> Shop Dwgs | <input checked="" type="checkbox"/> Consumables | <input type="checkbox"/> Permits |
| <input type="checkbox"/> Sales Tax | <input type="checkbox"/> Other Fees | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Scope of work: pavers along Harwood Ave from Hickory to 183rd Ave. are sinking and are trip hazards so after walk thru with Patrick Mc Aneney we walk off approximately **1350sf-1500 sf** of paver repairs thru the above stretch of sidewalks

2. We will remove existing pavers compact sub grade make sure it is compacted (note that we will ensure subgrade material is of good compact material if not we may need to take out more material (we will notify Village Engineer if there are any abnormalities)
3. Note we will start by hickory and work south as we pull existing brick out some will be damaged and we will not be able to use them so we will take existing pavers from gas station walk way so all bricks match, that will leave a void in the gas station walk way .We will then use a new paver to match the existing pavers as close as possible public works team will determine that color
4. We will add torpedo sand as setting bed
5. We will install paver pattern the same way we took it out
6. Project to take 5 working days to complete
7. we will also use some brick in storage at public works yard
8. We assume a laydown area for our equipment
9. we assume we can use gravel and sand from public works yard
10. We assume to dump all debris at public works yard



The Construction & Design Group, Inc.

9825 W. Roosevelt Rd, Westchester, IL 60151 Mailing P.O. Box 1276 North Riverside, IL 60516
Phone: 708-431-0413 Fax: 708-298-5733

11. We assume village to buy the new bricks to be used (we will help to select samples and bring samples to village)

price per square foot \$14.66 for brick repair work Example \$14.66x 1500sf = \$21990

6 TREE RING REMOVAL ADD RUBBERIZED PAVER MATERIAL

There are six tree rings that need to take out and new rubberized paver material to be installed

— We will remove metal grates

— We will remove at least 6" of concrete ring

We will dig and least 6" below grade

We will install 4" of ca-6 compact to 95% compaction

We will install 2" of rubberized paver material

We assume village will supply all materials for rubberized pavers and dumping to complete this project

Cost to install 6 rubberized tree areas is \$13200

For the sum of: Please see above for separate pricing
payment to be made as follows: Net 30 Days

with

Should you have any questions, please feel free to contact the undersigned at 708-434-0443.

Sincerely,

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date: _____

Signature: _____
ACCEPTANCE

Title: _____

All work to be completed in a workmanlike manner according to standard practice. Any alternation or deviation from above specifications involving extra costs will be executed only upon written order and will become an extra charge over and above the proposal. All agreements are contingent upon strikes, accidents or delays beyond our control. Owners to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Workman's Insurance.

By: Bob Filec

Title: Project Manager