

Kankakee Truck Equipment
785 Eastgate Industrial Parkway
Kankakee, IL 60901
815-939-2541
kankakeetruckequipment@outlook.com

Village of Homewood
2020 Chesnutt Road
Homewood, IL 60430

17 July 2026

We are pleased to make the following proposal: 2027 F600 Upfit

- Henderson MK3 18 U-9'
- 18" Fixed Sides
- 10ga Sides and End
- 3/16" AR. Floor
- Stainless Steel 304 sides and ends
- Extra Reinforcement on Sides
- 24" Quick Release Tail Gate
- Mailhot telescopic DA Head-Lift Hoist
- Integral Cab Shield
- 2500 LB Dump BodyVibrator Installed
- Chelsea PTO and Direct Mount Pump
- Force VT15 Tank/Valve Combination
- Valve set up for possible salt spreader installation
- Electric Switch Control for Hoist
- Backup Alarm
- Whelen Amber flashing lights and STT in rear corner post and on Cab Shield
- Whelen Ion T Amber/White Strokes in the Grill and Rear Outer Corner of Body
- Wire ran for Roof Top LED Minibar
- Poly Fenders
- ½" No-Sail Rear Mud Flaps on SS angles
- ½" Receiver Hitch Plate with bargeman plug
- All above equipment mounted and painted, where appropriate

Total price for one (1) complete unit: \$50,945


We thank you for the opportunity to be of service. If there are any questions regarding this proposal, please contact us at your convenience.

***Due to the rising cost of steel and stainless steel because of tariffs, a surcharge may be added to the final cost at the time of invoicing.*

***All proposals and quotes over 30 days old are subject to change and must be requoted prior to final Purchase Orders being issued.*

Kankakee Truck Equipment
785 Eastgate Industrial Parkway
Kankakee, IL 60901
815-939-2541
kankakeetruckequipment@outlook.com

Respectfully submitted,



Nicholas Kleinert

President

Kankakee Truck Equipment

Approved by

Signature

Printed Name/ Date

Position/ Organization