

The #1 Contractor

One Contractor for All Your Construction Needs

Client:	Eddy – Suite #6
Email:	Eddy1986@yahoo.com
Project:	Grease Trap & Commercial Plumbing Installation

Scope of Work

- Install main 4" grease line for grease trap installation.
 - Install approximately 33 feet of 4" pipe and 30 feet of 3" pipe for cleanouts.
 - Install (3) 3" floor drains.
 - Install (2) floor sinks — one 2" floor sink and one 3" floor sink.
 - Install (1) mop sink.
 - Install (2) hand sinks.
 - Install (1) three-compartment sink.
 - Saw cut and trench approximately 36 feet of concrete for the main line installation.
 - Saw cut concrete area approximately 5' x 9' for grease trap installation.
 - Pour back concrete as needed after completion of work.
 - Install (2) cleanouts with bronze covers for the grease trap system.
 - Supply and install one 250-gallon plastic grease trap.
 - Install gravel base required for grease trap installation.
-
- Complete installation of full grease trap system and required plumbing connections.
 - Price includes installation of hand sinks, mop sink, and three-compartment sink.

Project Investment

Description	Amount
Material & Labor Included	\$23,500.00

Payment Schedule

- 10% deposit required upon approval.
- 40% due once work has started.
- Remaining balance due upon completion of work.