
It is the responsibility of the architect and/or contractor to determine proper fit and function of any product relative to code requirements in the municipality of a given building site. - All installations should be performed by an approved, certified installer and be installed in accordance with AAMA Installation Masters methodology. - It is the responsibility of the installer to properly install products and to verify compatibility of sealants, flashing, and all building envelope membrane system components, - It is the responsibility of the installer to adequately shim all windows and doors. The shim placement should start no more than 4 inches from each corner, then every 12 to 16 inches thereafter. Shims are required at the check rails on double hung windows. - For complete and product specific installation instructions please refer to our installation manual or contact your Sierra Pacific Windows Representative. - Blocking, sealant / caulking, installation, interior trim, fasteners, flashing, metal trim, sill pans and shims are not supplied unless otherwise noted. - Sierra Pacific Windows is not responsible for repair or replacement of products damaged by other trades, window protection or storage following delivery, label removal orfinal cleaning. - For warranty questions, please refer to Sierra Pacific Limited Warranty. - Improper installation will void the warranty. - Manufacturing lead time does not begin until all signed submittals have been received at the Sierra Pacific Windows Office. - Sierra Pacific is not responsible for the design of, conditions in, or performance of building construction beyond the perimeters of the Sierra Pacific units. - Sierra Pacific is not responsible for any errors incurred through the use of these drawings by others. - Sierra Pacific is not responsible for improper installation. - It is the Distributor's responsibility to verify that all items specified on the order are correct. TEMPERED GLASS NOTES: The manufacturing of tempered glass involves heating and cooling pro





•35.5" X 63.5" FRAME SIZE •36" X 64" ROUGH OPENING

APPROVED SHOP DRAWINGS MUST BE SIGNED OR STAMPED BY THE FOLLOWING BEFORE THIS PROJECT WILL BE RELEASED INTO A PRODUCTION ORDER. THE SIGNATURES REQUIRED ARE TO CONFIRM THAT QUANTITIES, SIZES AND HANDING. HAVE BEEN REVIEWED AND APPROVED.

Distributor Date Architect Date Contractor Date