

EDWARDS EQUIP.CO.,INC

PO BOX 669
156 CHURCH STREET
Asheville, NC 28802

ESTIMATE

DATE	ESTIMATE NO.
9/7/2023	3043

NAME/ADDRESS
City of Hendersonville City Ops 305 Williams St Hendersonville NC 28792 Jay 828-388-0258

	P.O. No.	Terms	PROJECT
			Data Drop Project
DESCRIPTION	QTY	COST	TOTAL
DATA AND STRUCTURED WIRING INSTALLATION FOR 1ST FLOOR RENOVATION PER DRAWINGS			
FIRST FLOOR DATA EQUIPMENT	1	32,068.00	32,068.00T
4 Horizontal Wire Management Sets	4		
4 48 Port Patch Panels, fully populated (143 spots to be used of 144)	4		
67 Dbl Wall Plates, White, Plastic (59 data locations, 2 extra locations not on drawings for Jay's Office, 6 TV locations)	67		
4 Quad Wall Plates (for 16 data drops at knee wall area, then custom patch cables for modular cubicles)	4		
134 CAT6 Keystones, White	134		
12 Thin CAT6 Patch Cables, Plenum, Green (6 TV locations, dbl drops)	12		
3 Thin CAT6 Patch Cable, Plenum, Yellow (3 AP single drops)	3		
134 Thin CAT6 Patch Cables, Plenum, Blue (63 data dbl drops)	134		
38 Boxes Plenum CAT6 Blue (Data), 2 Boxes Plenum CAT6 Yellow (for APs), 2 Boxes Green (for TVs), Connectors, Velcro straps, Mag Hooks, Strapping for Wire Racking System, etc.	1		
Scaffolding Rental	1		
Unexpected Occurrence (ONLY BILLED IF NEEDED AND CUSTOMER APPROVED)	1		
Two Year Parts and One Year Labor Warranty			
All Permit Fees, LAN and 110V Requirements, and Cost of COI, if Required, are Customer Responsibility	Total		

Phone #	Fax #	E-mail
828-252-8588	828-252-0315	office@eecsecurity.com

EDWARDS EQUIP.CO.,INC

PO BOX 669
156 CHURCH STREET
Asheville, NC 28802

ESTIMATE

DATE	ESTIMATE NO.
9/7/2023	3043

NAME/ADDRESS
City of Hendersonville City Ops 305 Williams St Hendersonville NC 28792 Jay 828-388-0258

	P.O. No.	Terms	PROJECT
			Data Drop Project
DESCRIPTION	QTY	COST	TOTAL
<p>NOTE: -All J-hook pathway, cable tray pathway provided above, but conduit work is NOT provided anywhere. -Any lift needed for work on this project is not included in this bid. -This is not a "certified" install, but we guarantee full speed connectivity in our two year warranty</p> <p>Installation and Labor for Interior Structured Wiring to Include: -Pulling CAT6 cable to each location as marked on the drawings, termination in to above quoted patch panels, and attempt to clean up both data closets. -Each AP will be a single CAT6 drop w/RJ45 termination and we will hang the APs if VC3 will have them on site when needed. -Each wall outlet will have customer approved labeling scheme.</p> <p>Credit Card Payments Received Are Subject to a 3% Convenience Fee</p>	1	37,500.00	37,500.00T
All Permit Fees, LAN and 110V Requirements, and Cost of COI, if Required, are Customer Responsibility		Total	

Phone #	Fax #	E-mail
828-252-8588	828-252-0315	office@eecsecurity.com

EDWARDS EQUIP.CO.,INC

PO BOX 669
156 CHURCH STREET
Asheville, NC 28802

ESTIMATE

DATE	ESTIMATE NO.
9/7/2023	3043

NAME/ADDRESS
City of Hendersonville City Ops 305 Williams St Hendersonville NC 28792 Jay 828-388-0258

	P.O. No.	Terms	PROJECT
			Data Drop Project
DESCRIPTION	QTY	COST	TOTAL
<p>NOTE: This proposal is good for a period of 10 days. Please let me know if you have any questions. Thank you for this opportunity to earn your business. Hope to hear from you soon.</p> <p>Thank You, Brad Edwards Cell 828-242-2350 www.edwardsequipmentinc.com</p> <p>Signed: _____ Date: _____</p> <p>TAX TO BE ADDED BASED ON CERTIFICATES PROVIDED OR STATE REQUIREMENTS Sales Tax</p>			
		0.00%	0.00
		6.75%	4,695.84
All Permit Fees, LAN and 110V Requirements, and Cost of COI, if Required, are Customer Responsibility		Total	\$74,263.84

Phone #	Fax #	E-mail
828-252-8588	828-252-0315	office@eecsecurity.com