



October 12, 2021

Maybin's Emergency Power  
Jim Maybin

Prepared by

Rick Smith  
[REDACTED]  
[REDACTED]

We are pleased to provide you this quotation based on your inquiry.  
[REDACTED]

Item	Description	Qty
1	<b>DQCA, Commercial Diesel Generator Set, 600kW Standby 60Hz</b> U.S. EPA, Stationary Emergency Application 600DQCA, Diesel Genset, 60Hz, 600kW Duty Rating-Standby Power (ESP) Emission Certification, EPA, Tier 2, NSPS CI Stationary Emergency Fuel Tank- Sub-Base, 1000 Gallon, UL142 Compliant Listing, ULC-S601-07 Listing-UL 2200 Alarm-High Fuel Fill Fuel Tank Connection-Dual Stub Up Fuel Water Separator Control Mounting-Left Facing PowerCommand 2.3 Controller Control Cabinet Heater, 120/240 Volt AC Compatible LCD Control Display Relays-Genset Status, User Configured Stop Switch-Emergency, Externally Mounted Signals-Auxiliary, 8 Inputs/8 Outputs Relay-Alarm Shutdown Control Display Language-English Circuit Breaker or Entrance Box or Terminal Box-Left Only Circuit Breaker-1200A, Left, 3P, 600/415V, UL/IEC, Serv Ent, 100%UL Terminal Box-Low Voltage, Right-None Bottom Entry, Left Circuit Breaker or Entrance Box or Terminal Box, Top Entry, Right-None Circuit Breaker Accessory, 24 Volts DC Trip, Aux and Trip Contacts, Left Side Engine Air Cleaner-Normal Duty External Battery Charger-12 Amp, Regulated Engine Cooling-Radiator, 50C Ambient Shutdown-Low Coolant Level Coolant Heater-208/240/480 Volts AC, Below 40F Ambient Temperature Voltage-277/480, 3 Phase, Wye, 4 Wire Oil Sampling Valve Cummins Certified Test Record Genset Warranty-2 Years Base Alternator-60Hz, Wye, 480 Volts, 80C-Standby Literature-English Packing-None, Base Mounted Housing Alternator Heater, 240 Volt AC Steel Sound Attenuated Level 2 Enclosure, with Exhaust System Enclosure Color-Green, Steel Cooling Air Outlet-Horizontal, Sound Attenuated Louvers-Air Inlet, 24 Volts DC Spring Closed, Motor Opened Louvers-Air Outlet, 24 Volts DC Spring Closed, Motor Opened DQCA Design Choice	1



	Generator <b>[REDACTED]</b>	
2	Remote fuel tank fill station with transfer pumps, control, bypass, NEMA3R enclosure, and level switches (shipped loose)	1
	Remote fill station <b>[REDACTED]</b>	
3	<b>CXRESE, CXR Series Service Entrance Transfer Switch with PowerCommand Control:1200A</b> CXR1200SE, Transfer Switch, PowerCommand, 1200 Amp Anti-Condensation Cabinet Heater S1 SPD, 120KA, For WYE Systems Listing-UL 1008 Application-Utility to Genset Transfer Switch Warranty-2 Year Comprehensive Packing-Wooden Crate Cabinet-Type 3R Cable Lugs-Mechanical, 1/0-750 MCM Transfer Mode-Delayed Transition Poles-3 (Solid Neutral) Frequency-60 Hz System-3 Phase, 4-Wire (Solid or Switched Neutral) Voltage-480 Volts AC PC80 Control Integrated High Accuracy Power Quality Metering Integral Control Power Supply Premium Customer I/O	1
	ATS <b>[REDACTED]</b>	

**TOTAL: \$326,025.00**

Installation by others

Startup **[REDACTED]**

Fuel by others

Batteries **[REDACTED]**

Generator distribution panel and support circuits(battery charger, block heaters, condensation heaters) by others

Surge suppression on ATS only-all others by others

Conduit/wiring from remote fill station to fuel tank by others

Elevated support by others

Off-loading by others

Spare parts by others

Quote value does not include any tax.

**NOTES:**

- Current Submittal Lead Time: 4 weeks
- Current Production Lead Time (after receipt of approved submittal and accepted PO):
  - Transfer Switch(es): 10 weeks
  - Generator: 22 weeks
- Proposal based upon conversation/description only.
- Price quoted is F.O.B. factory with freight allowed to the first U.S. destination.
- Price does not include any applicable taxes unless listed above.
- All ship loose items installed by others.
- Unloading, installation, and fuel are not included and will be the responsibility of others.
- **Indoor Generator:**
  - All exhaust and fuel piping provided by others. All calculations for determining of sizing of exhaust and fuel piping sizes provided by others.
  - Providing xx grade muffler and stainless-steel flex connector(s) only. All other piping, accessories and installation are provided by others.
- **Natural Gas or LP Gas Generator:**
  - Main gas regulator, flex piping and stepdown regulator provided by others. Installation of main gas regulator not done by Cummins Personnel