

Project Plant List

Large Trees - 13 Total					
Key	Qty	Botonical Name	Common Name	Size	Remarks All Plants to Meet Ansi Z60.1 Stnds.
AO	3	Acer 'October Glory'	October Glory Maple	2" Caliper, 10' Height	B&B, Single Straight Leader
Cwk	4	Crategus viridis'Winter King'	Winter King Hawthorn	2" Caliper, 10' Height	B&B, Single Straight Leader
QP	6	Quercus phellos	Willow Oak	2" Caliper, 10' Height	B&B, Single Straight Leader

Evergreen	Shrubs .	- 130	Total
Lvergreen		100	10141

Key	Qty	Botonical Name	Common Name	Size	Remarks All Plants to Meet Ansi Z60.1 Stnds.
AG	8	Abelia grandiflora	Glossy Abelia	3 gallon, 18" Height	Full Plant
IGS	9	Ilex glabra 'Shamrock'	Shamrock Inkberry Holly	3 gallon, 18" Height	Full Plant
Sky	33	Ilex crenata 'Sky Pencil'	Sky Pencil Holly	3 gallon, 18" Height	Full Plant
LF	20	Leucothoe 'Margie Jenkins'	Leucothoe 'Margie Jenkins'	3 gallon, 18" Height	Full Plant
Plo	27	Prunus laurecarasus 'Otto Luyken'	Otto Luyken Cherry Laurel	3 gallon, 18" Height	Full Plant
RC	15	Rhododendron catawb. 'English Roseum'	English Roseum Rhododendron	3 gallon, 18" Height	Full Plant
RA	18	Rhododendron 'Autumn Amethyst'	Autumn Amethyst Azalea	3 gallon,18" Height	Full Plant

DeciduousShrubs - 143 Total

Key	Qty	Botonical Name	Common Name	Size	Remarks All Plants to Meet Ansi Z60.1 Stnds.
BD	17	Buddleia 'Miss Molly'	Miss Molly Butterfly Bush	3 gallon, 18" Height	Full Plant
CD	9	Calicarpa dichtoma	Purple Beautyberry	3 gallon, 18" Height	Full Plant
СН	9	Clethra alnifolia 'Hummingbird'	Hummingbird Clethra	3 gallon, 18" Height	Full Plant
HLL	11	Hydrangea 'Little Lime'	Little Lime Hydrangea	3 gallon, 18" Height	Full Plant
Hsd	42	Hydrangea 'Sikes Dwarf'	Sikes Dwarf Hydrangea	3 gallon, 18" Height	Full Plant
HA	3	Hydrangea 'Amma Belle'	Anna Belle Hydrangea	3 gallon, 18" Height	Full Plant
НВ	9	Hydrangea paniculata 'Bobo'	Bobo Hydrangea	3 gallon, 18" Height	Full Plant
Irs	26	Ilex 'Res Sprite'	Red Sprite Holly	3 gallon, 12" Height	Full Plant
MU	17	Muhlenbergia reverchonii 'Undaunted'	Undaunted Muhly Grass	3 gallon, 12" Height	Full Plant







Irs - Red Sprite Holly

AO - October Glory Maple



Cwk - Winter King Hawthorn



QP - Willow Oak



AG - Glossy Abelia



PLO - Otto Luyken **Cherry Laurel**



Sky - Sky Pencil Holly



IGS - Shamrock Inkberry Holly



LF - Margie Jenkins Leucothoe



RC - English Roseum Rhodo



RA - Autumn Amethyst Azalea



BD - Miss Molly Butterfly Bush



CD-Purple Beautyberry



Tree Planting Detail



HA - Anna Belle Hydrangea



Hsd - Sikes Dwarf Hydrangea



HLL - Little Lime Hydrangea




Landscape Notes

1. ALL AREAS SHOWN AS LARGE TREES, SMALL FLOWERING TREES, AND SHRUB AND PERENNIAL LANDSCAPING ON THE LANDSCAPE PLAN IS TO BE MULCHED AND SHALL RECEIVE A 3" DEPTH OF SHREDDED PINE BARK MULCH.

2. CONTRACTOR SHALL VERIFY QUANTITIES ON THE PLAN AND IS RESPONSIBLE FOR ALL PLANTS AS SHOWN ON THE PLANT LIST. REPORT ANY DISCREPANCIES TO LANDSCAPE ARCHITECT. PROVIDE UNIT PRICES FOR ALL PLANT AND TREE MATERIALS.


3. CONTRACTOR SHALL GUARANTEE ALL PLANTINGS FOR ONE YEAR FROM COMPLETION OF WORK. REPLACEMENT PLANTS AND LABOR SHALL BE PROVIDED AT CONTRACTORS'

- EXPENSE. 4. PRUNE ONLY AS DIRECTED BY LANDSCAPE ARCHITECT. DO NOT REMOVE THE CENTRAL LEADER OF ANY TREE OR PLANT. PLANTS SHALL NOT HAVE A SHEARED APPEARANCE AND MUST MEET MINIMUM SIZES AS INDICATED ON THE PLANT LIST.
- 5. ALL PLANT MATERIAL IS TO CONFORM TO THE LATEST EDITION OF AMERICAN STANDARDS FOR NURSERY STOCK. SEE PLANT LIST FOR SPECIFICATIONS AND SIZES. (NOTE: SIZE TO BE 'DBH' MEASURED 6" ABOVE GROUND)
- 6. LANDSCAPE ARCHITECT AND/OR OWNER RESERVES THE RIGHT TO REJECT ANY PLANT MATERIAL, ESPECIALLY DUE TO UNDERSIZED OR DAMAGED MATERIALS.
- 7. CONTRACTOR IS RESPONSIBLE FOR THE LOCATION AND IDENTIFICATION OF ALL UTILITIES. ANY UTILITIES DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S COST.
- 8. ALL DEMOLISHED MATERIALS AND TRASH ARE TO BE REMOVED FROM THE SITE AND DISPOSED OF PROPERLY.
- 9. ALL PLANTINGS HOLES AND BEDS ARE TO BE CLEANED OF ROCKS AND DEBRIS >1", EACH PLANT OR TREE IS TO BE HOLE AMENDED AND THE EXISTING NATIVE SOIL IS TO BE AMENDED WITH 25% OF NATURES HELPER AND 25% OF ORGANIC COMPOST (OR APPROVED EQUAL), THEN THOROUGHLY MIXED TOGETHER TO CREATE A PLANTING SOIL MIX.
- 10. ALL EXISTING AND PROPOSED TREES NOT CONTAINED WITHIN A MULCHED BED ARE TO RECEIVE A 3" DEPTH OF A 4' DIAMETER CIRCLE OF ABOVE SPECIFIED MULCH AROUND EACH TREE. EXCEPT WHERE TREES OCCUR IN SWALES, DITCHES, OR DRAINAGE PATTERNS, THEN ONLY USE 1' DIAMETER CIRCLES.
- 11. REPORT ANY POORLY DRAINED SOILS OR ANY DRAINAGE PROBLEMS TO LANDSCAPE ARCHITECT IMMEDIATELY. FAILURE TO REPORT SUCH CONDITIONS WILL RESULT IN THE CONTRACTOR BEING RESPONSIBLE FOR CORRECTING THE PROBLEM AND REPLACING DAMAGED OR LOST PLANTS. PROPER PLANT DRAINAGE IS DEFINED BY FLOODING PLANTING HOLE TO SURROUNDING SOIL LEVEL WITH WATER AND COMPLETE PERCOLATION OF THE WATER WITHIN THE HOLE IN A 24 HOUR PERIOD.
- 12. LANDSCAPE ARCHITECT OR OWNER TO FIELD APPROVE THE PLACEMENT OF ALL PLANT MATERIALS.
- 13. FINE GRADE ALL PLANTING AREAS TO INSURE PROPER DRAINAGE. AREAS TO BE SEEDED ARE TO BE FREE OF DEBRIS AND ROCKS > 1" PRIOR TO LAYING SOD OR APPLYING SEED.
- 14. PRIOR TO INSTALLATION, CONTRACTOR SHALL REVIEW PLANT AND LIGHT LOCATIONS WITH LANDSCAPE ARCHITECT OR OWNER TO ELIMINATE CONFLICTS.
- 15. PROVIDE LABOR, EQUIPMENT, MATERIALS, AND SERVICE NECCESSARY TO COMPLETE THE LANDSCAPE WORK.
- 16. INSTALL ALL PLANT MATERIALS IN ACCORDANCE WITH LOCAL CODES AND ORDINANCES.
- 17. MAINTAIN ALL PLANT MATERIALS UNTIL FINAL ACCEPTANCE OR SUBSTANTIAL COMPLETION OF WORK. MAINTENANCE TO INCLUDE: WATERING, MULCHING, WEEDING, SPRAYING, MOWING, STRAIGHTENING, FERTLIZING, CLEANUP, ECT.



5. THIS DETAIL INCLUDES TREES WITH 3 $\frac{1}{2}$ CALIPER AND BELOW.

1. DETAIL APPLIES TO MATERIALS PLANTED AT GREATER THAN 18" O.C. 2. CONTRACTOR SHALL ASSURE PERCOLATION OF ALL PLANTING BEDS/PITS PRIOR TO INSTALLATION AND INSURE POSITIVE DRAINAGE OF ALL PLANTING AREAS, SEE NOTES AND SPECIFICATIONS. MAX. 1" DROP FROM ADJACENT PAVEMENT OR CURB



Shrub Planting Detail

O O

