The Southwest 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 35, Township 20 South, Range 25 East, Lake County, Florida;

Reginning at the Northeast corner of the Southwest 1/4 of the Northwest 1/4 of the Northwest 1/4 in Section 35 Township 20 South Range 25 East Lake County, Florida; run thence West approximately 330 feet to the Southeast corner of the Southwest 1/4 of the Northwest 1/4 of the Northwest 1/4 of the

Beginning at the East 1/2 mile corner of Section 35, Township 20 South, Range 25 East, Lake County, Florida; run West 1490 feet to an iron pipe on the North right—of—way line of said State Road now paved; thence Southwesterly along said right—of—way line 446.5 feet to a cement marker and the Point of Beginning o Cernetery property; run thence Southwesterly with the North right—of—way line of said road 509.4 feet; thence North 36°27' West, 573.8 feet; thence North 51°33' East, 500 feet; thence South 38°27 East, 500 feet to the Point of Beginning;

The West 1/2, Less and Except the North 3/4 of the Northeast 1/4 of the Northwest 1/4, in Section 35, Township 20 South, Range 25 East, Lake County, Florida

That part of the South 1/4 of the Southwest 1/4 of the Southwest 1/4, lying South of County Clay Road, in Section 26, Township 20 South, Range 25 East, Lak

A tract of land located in the Northeast 1/4 of the Northeast 1/4 of Section 35. Township 20 South, Range 25 East, Lake County, Florida, and generally described

All of Block D-14. according to the plat of Palm Gardens, filed February 26, 1951, and recorded in Plat Book 12, Page 11, of the Public Records of Lake County,

That part of the Northwest 1/4 of the Northeast 1/4 of Section 35, Township 20 South, Range 25 East, in the town of Howey in the Hills, Florida, bounded and Begin at the Northwest corner of the Southwest 1/4 of the Northwest 1/4

Southeasterly along a straight line to the Northeast corner of the Southwest 1/4 of the Northwest 1/4 of the Northeast 1/4 of said Section 35: thence run South along East line thereof, to the Southeast corner of the said Southwest 1/4 of the Northwest 1/4 of the Northeast 1/4; thence run West along the South line hereof to the Southwest corner of the said Northwest 1/4 of the Northeast 1/4; thence run North along the West line of the said Northwest 1/4 of the Northeast 1/4 to the Point of Beginning: Less all rights-of-way for streets in Howey in the Hills. Florida. All of Block D-14 in Palm Gardens, a subdivision in the town of Howey in the Hills, Florida, according to the plat thereof recorded in Plat Book 12, Page 11 of the

The South 3/4 of the West 1/2; the Northwest 1/4 of the Northwest 1/4, Less the right-of-way of a County Clay Road; and the South 1/4 of the Northeast 1/4

of the Northwest 1/4 of Section 35, Township 20 South, Range 25 East, Lake County, Florida, in the town of Howey in the Hills, Florida That part of the Southwest 1/4 of the Northeast 1/4 and that part of the Northwest 1/4 of the Southeast 1/4 lying North and West of the Westerly line of the right-of-way of State Road No. 19, in Section 35, Township 20 South, Range 25 East, Lake County, Florida, in the town of Howey in the Hills, Florida; Less and Except therefrom that part thereof lying within Taylor Memorial Cemetery, according to the plat thereof recorded in Plat Book 12, Page 5, of the Public Records of

That part of the East 1/2 of the Northeast 1/4 of Section 35, Township 20 South, Range 25 East, in the town of Howey in the Hills, Florida, bounded and

Begin at the Northwest corner of Lot 1, in Block D-14, in Palm Gardens, according to the plat thereof recorded in Book 12, Page 11, of the Public Records of Lake County, Florida; thence run West to the West line of the Northeast 1/4 of the Northeast 1/4 of the said Section 35; thence run South along the West line of the East 1/2 of the Northeast 1/4 of the said Section 35 to a point on the Northwesterly line of the right-of-way of State Road No. 19; thence run Northeasterly the said Block D-14, to the Point of Beginning: Less all rights-of-way for streets in Howey in the Hills. Florida

That part of the South 1/4 of the Southwest 1/4 of the Southwest 1/4 of Section 26, Township 20 South, Range 25 East, Lake County, Florida, lying South of the Southerly line of the right-of-way of the County Road.

Commence at the East 1/4 corner of Section 35, Township 20 South, Range 25 East, Lake County, Florida; thence run North 89°21'35" West along the South line of the Northeast 1/4 of said Section 35, 1487.79 feet to a point on the Northwesterly right-of-way line of State Road No. 19; thence run South 52'07'27" West along said Northwesterly right—of—way line, 459.23 feet to the point of curvature of a curve concave Southeasterly; thence run Southwesterly along the arc of said curve and said Northwesterly right—of—way line having a central angle of 14°35′56″, a radius of 2341.83 feet, an arc length of 596.69 feet, a chord bearing of South 44'49'31" West and a chord distance of 595.08 feet to the Point of Beginning; thence continue along said Northwesterly right—of—way line being a curve concave Southeasterly, thence run Southwesterly along said curve having a central angle of 22'58'29", a radius of 2341.83 feet, an arc length of 939.04 feet, a chord bearing of South 26'02'16" West and a chord distance of 932.76 feet; thence run North 75'26'58" West, 402.66 feet; thence run South 68'12'24" West, 668.73 feet; thence run North 53'42'00" West, 250.16 feet; thence run North 12'38'17" East, 257.60 feet; thence run North 77'21'43" West, 125.00 feet; thence run North 12'38'17" East, 13.01 feet to the point of curvature of a curve concave Easterly; thence run Northeasterly along the arc of said curve having a central angle of 39'28'41", a radius of 75.00 feet, an arc length of 51.68 feet, a chord bearing of North 32'22'37" East and a chord distance of 50.66 feet to the point of tangency, thence run North 52'06'58" East, 476.63 feet; thence run North 54'47'17" East, 150.16 feet; thence run North 52'06'58" East, 205.75 feet to the point of curvature of a curve concave Southerly, thence run Easterly along the arc of said curve having a central angle of 62°53'19", a radius of 24.99 feet, an arc length of 27.43 feet, a chord bearing of North 83°33'05" East and a chord distance of 26.08 feet to the point of reverse curvature of a curve concave Northwesterly, thence run Northeasterly along the arc of said curve having a central angle of 125.45'33", a radius of 99.99 feet, an arc length of 219.47 feet, a chord bearing of North 52'06'58" East and a chord distance of 178.00 feet to the point of reverse curvature of a curve concave Southeasterly, thence run Northeasterly along the arc of said curve having a central angle of 62°53′19″, a radius of 24.99 feet, an arc length of 27.43 feet, a chord begring of North 20'40'51" East and a chord distance of 26.08 feet to the point of tangency, thence run North 52'06'58" East, 560.98 feet to a point on the Northwesterly extension of the Southwesterly line of Taylor Memorial Cemetery; thence run South 3758'58" East along said Northwesterly extension line, 613.80 feet to the Point of Beginning.

Commence at the East 1/4 corner of Section 35, Township 20 South, Range 25 East, Lake County, Florida; thence run North 89°21'35" West along the South line of the Northeast 1/4 of said Section 35, 1487.79 feet to a point on the Northwesterly right-of-way line of State Road No. 19; thence run South 52'07'27" West along said Northwesterly right-of-way line, 66.25 feet to the Point of Beginning; thence continue South 52°07'27" West along said Northwesterly right-of-way line, 392.98 feet to the point of curvature of a curve concave Southeasterly, thence run Southwesterly along the arc of said curve having a central angle of 0212'24", a radius of 2341.83 feet, an arc length of 90.19 feet, a chord bearing of South 51'01'15" West and a chord distance of 90.19 feet to the most Easterly corner of Taylor Memorial Cemetery, thence run North 38'00'31" West, along the Northeasterly line of said Taylor Memorial Cemetery, 547.00 feet; thence run North 52'06'58" East 484.34 feet to the point of curvature of a curve concave Southerly; thence run Southeasterly along the arc of said curve having a central angle of 90'00'00", a radius of 10.00 feet, an arc length of 15.71 feet, a chord bearing of South 82'53'02" East and a chord distance of 14.14 feet to the point of tangency, thence run South 37'53'02" East, 525.33 feet to the point of curvature of a curve concave Northwesterly; thence run Southwesterly glong the grc of said curve having a central angle of 90'00'00", a radius of 10.00 feet, an arc length of 15.71 feet, a chord bearing of South 07'07'12" West and a chord distance of 14.14 feet to the Point of Beginning.

AND, ALSO LESS the following described parcel:


Commence at the East 1/4 corner of Section 35, Township 20 South, Range 25 East, Lake County, Florida; thence run North 89°21'35" West along the South line of the Northeast 1/4 of said Section 35, 1487.79 feet to a point on the Northwesterly right-of-way line of State Road No. 19 thence run North 52'07'27" East along said Northwesterly right-of-way line, 673.75 feet to the Point of Beginning; thence run North 37'53'02" West, 1008.88 feet; thence run North 00'35'47" East, 116.78 feet to a point on the North line of the Southwest 1/4 of the Northwest 1/4 of said Section 35; thence run South 89°24'13" East along said North line. 270.08 feet to a point on the West line of the Northeast 1/4 of the Northeast 1/4 of said Section 35; thence run North 00'35'58" East along said West line, 256.12 feet to a point on the South line of the residence of Don White; thence run South 89°24'13" East along said South line, 418.17 feet; thence run South 00°35'47" West, 709.10 feet; thence run South 37°52'33" East, 317.47 feet to a point on said Northwesterly right—of—way line of State Road No. 19; thence run South 52'07'27" West along said Northwesterly right-of-way line, 329.54 feet to the Point of Beginning.

That parcel described as the Taylor Memorial Cemetery in that Quitclaim Deed recorded in Official Records Book 1147, Page 1398, of the Public Records of Lake

Together with those appurtenant easements as set forth and granted by Eagles Landing at Ocoee, Inc., a Florida corporation, to Howey in the Hills, a Florida limited partnership, in that Development Agreement and Grant of Easements, recorded November 10, 2005 in Official Records Book 3003, Page 1377, of the Public Records

26-20-25-0400-D14-00000 HOWEY-IN-THE-HILLS LAKE COUNTY, FL

PREPARED FOR **LENNAR - ORLANDO** 6750 FORUM DRIVE, SUITE 310 PROJECT LOCATION **ORLANDO, FL 32821**






Engineering · Landscape Architecture Planning •

10060 SKINNER LAKE DR., SUITE 500 JACKSONVILLE, FLORIDA 32246 (904) 265-3030 FAX: (904) 265-3031 1560 NORTH ORANGE AVE., SUITE 210 WINTER PARK, FLORIDA 32789 (407) 261-3100 FAX: (407) 261-3099

FLORIDA REGISTRY: 3650 L.A. NUMBER: LC26000311 www.cwieng.com



THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE SHEET NUMBER

IN ACCORDANCE WITH RULE 61G15-23.004, F.A.C

	/	NDEX OF SHEETS
	SHEET	TI TLE
	C100	COVER
	C101	GENERAL NOTES
	- G15Q -	EXISTING CONDITIONS PLAN
$\langle \Delta \rangle$	C160	CLEARING, SEDIMENT & EROSION CONTROL PLAN
	C400	MASTER SHIE PLAN
	C500-C504	MASS GRADING PLAN
	C505	STRUCTURE TABLES
	C510	CONTROL STRUCTURE DETAILS
	C900	TOWN OF HOWEY-IN-THE-HILLS DETAILS
	C950	SWPPP

DEVELOPER LENNAR - ORLANDO 6750 FORUM DRIVE, SUITE 310 ORLANDO, FL 32821

CIVIL ENGINEER CONNELLY & WICKER INC 1560 NORTH ORANGE AVENUE, SUITE 210 WINTER PARK, FL 32789 (904) 265-3030 CONTACT: JUSTIN WILLIAMS, P.E.

PLANNER

William (Bill) A. Ray, AICP Ray and Associates Planning and Environmental Services 2712 SE 29th Street, Ocala, FL 34471 Office & Cell; 352-425-8881

OWNER EASTON & ASSOCIATES 10165 NW 19TH ST MIAMI, FL 33172

onnelly

21-04-0008 Designed: RAH Checked: RCW RRB **APRIL 2021** DATUM:

C100

GENERAL NOTES:

1. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH THE LATEST STANDARDS OF THE TOWN OF HOWEY-IN-THE-HILLS, FDOT AND FDEP.

2. PAVEMENT STRIPING TO BE IN ACCORDANCE WITH THE FLORIDA D.O.T. ROADWAY & TRAFFIC STANDARDS, INDEX 17346, AND AS REQUIRED BY THE TOWN OF HOWEY-IN-THE-HILLS.

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF SIZE AND LOCATION OF ALL EXISTING UTILITIES AND RELATED CONSTRUCTION PRIOR TO COMMENCEMENT OF WORK. SHOULD THE CONTRACTOR OBSERVE ANY DEVIATIONS FROM WHAT IS SHOWN ON THE PLANS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF SAID DEVIATIONS PRIOR TO COMMENCEMENT OF WORK. ANY WORK THAT MUST BE REDONE DUE TO FAILURE OF CONTRACTOR TO NOTIFY THE ENGINEER OF DEVIATIONS PRIOR TO CONSTRUCTION WILL BE AT THE CONTRACTORS SOLE EXPENSE.

- 4. WHERE MUCK OR OTHER ORGANIC MATERIAL IS FOUND, IT SHALL BE REPLACED WITH GOOD QUALITY BACKFILL MATERIAL OBTAINED FROM THE GRADING OPERATIONS OR OTHER SOURCE APPROVED BY THE GEOTECHNICAL ENGINEER. THE ORGANIC MATERIAL SHALL BE THEN USED AS TOP DRESSING WHEN MIXED WITH CLEAN BACKFILL SOIL AS APPROVED BY THE GEOTECHNICAL ENGINEER OR PLACED AS APPROVED BY OWNER.
- 5. ALL FINISHED GRADES AND ELEVATIONS ARE AS DENOTED BY THE APPLICABLE LEGEND.
- 6. AS PART OF THE CLEARING AND GRUBBING OPERATION, THE CONTRACTOR IS TO REMOVE ALL FENCING AND/OR EXISTING FACILITIES FROM THE SITE AS DIRECTED BY ARCHITECT.
- 7. MAINTAIN MINIMUM 3' COVER OVER PROPOSED LINES, UNLESS OTHERWISE NOTED.

 8. THE CONTRACTOR SHALL NOTIFY THE TOWN OF HOWEY-IN-THE-HILLS AND THE UTILITY OWNER CONSTRUCTION DEPARTMENTS 48 HOURS PRIOR TO ANY UTILITIES CONSTRUCTION.
- 9. THE LIMITS OF THE SWALES SHALL BE SODDED AS INDICATED ON THE PLANS.
- 10. THE CONSTRUCTION OF ALL UTILITIES CONNECTING TO UTILITY SYSTEMS SHALL CONFORM TO STANDARDS AND CONSTRUCTION SPECIFICATIONS OF THE UTILITY OWNER.

11. CONTRACTOR IS RESPONSIBLE FOR OBTAINING FDEP GENERIC PERMIT FOR THE DISCHARGE OF PRODUCED GROUND WATER FROM ANY NON—CONTAMINATED SITE ACTIVITY IN ACCORDANCE OF FLORIDA ADMINISTRATIVE CODE 62—621.300 (2), 62—620, AND FLORIDA STATUTES CHAPTER 403.

- 12. ALL EXCESS FILL MATERIAL SHALL BE HAULED OFFSITE
- 13. ALL DESIGNATED ENTRANCES AND EXITS FOR CONSTRUCTION SITE SHALL BE STABILIZED USING FILTER FABRIC AND GRAVEL OR OTHER PRE—APPROVED METHODS TO PREVENT OFF—SITE TRACKING OF SEDIMENTS.

 EROSION CONTROL NOTES:
- 1. DURING CONSTRUCTION, THE CONTRACTOR SHALL TAKE ALL REASONABLE MEASURES TO INSURE AGAINST POLLUTING, SILTING OR DISTURBING TO SUCH AN EXTENT AS TO CAUSE AN INCREASE IN TURBIDITY TO THE EXISTING SURFACE WATERS. SUCH MEASURES SHALL BE APPROVED BY THE PROJECT ENGINEER AND MAY INCLUDE, BUT NOT LIMITED TO, CONSTRUCTION OF TEMPORARY EROSION CONTROL STRUCTURES, SUCH AS SEDIMENT BASINS, SEDIMENT CHECKS, OR SILT BARRIERS.
- 2. SODDING (OR OTHER STABILIZATION) OF STORMWATER DETENTION AREAS SHOULD BE ACCOMPLISHED WITH IN SEVEN (7) DAYS FOLLOWING COMPLETION OF GRADING TO MINIMIZE EROSION POTENTIAL.
- 3. AT A MINIMUM, THE RETENTION/DETENTION STORAGE AREA MUST BE EXCAVATED TO ROUGH GRADE PRIOR TO BUILDING CONSTRUCTION OR PLACEMENT OF IMPERVIOUS SURFACE WITHIN THE AREA TO BE SERVED BY THOSE FACILITIES TO PREVENT REDUCTION IN STORAGE VOLUME AND PERCOLATION RATES. ALL ACCUMULATED SEDIMENT MUST BE REMOVED FROM THE STORAGE AREA PRIOR TO FINAL GRADING AND STABILIZATION.
- 4. IF DURING CONSTRUCTION, THE PROPOSED EROSION CONTROL SYSTEM DOES NOT PERFORM SATISFACTORILY, ALTERNATIVES AND ADDITIONAL METHODS OF PROTECTION SHALL BE IMPLEMENTED BY THE CONTRACTOR IN ORDER TO COMPLY WITH THE TOWN OF HOWEY-IN-THE-HILLS EROSION PROTECTION STANDARDS. CONTRACTOR IS ULTIMATELY RESPONSIBLE FOR ALL EROSION CONTROL COSTS INCLUDING ANY COSTS ASSOCIATED WITH COMPLIANCE ISSUES AND ENFORCEMENT ACTIONS.
- 5. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A DETAILED EROSION CONTROL PLAN TO THE TOWN OF HOWEY—IN—THE—HILLS FOR REVIEW AND APPROVAL A MINIMUM OF 2 WORKING DAYS PRIOR TO THE PRE—CONSTRUCTION MEETING. AT A MINIMUM, THE EROSION CONTROL PLAN SHALL PROPOSE SILT SCREEN OR SYNTHETIC HAY BALES AND TURBIDITY BARRIERS, IN ACCORDANCE WITH THE CONSTRUCTION PLANS.
- 6. ALL PERMANENT EROSION CONTROL MEASURES SHALL BE COMPLETED WITHIN 7 DAYS OF FINAL GRADING. ALL TEMPORARY EROSION CONTROL SHALL BE MAINTAINED UNTIL PERMANENT MEASURES ARE COMPLETED AND ESTABLISHED.
- 7. CONTRACTOR SHALL INSPECT THE EROSION/SEDIMENT CONTROL EFFORTS TO DETERMINE THE EFFECTIVENESS. INSPECTIONS SHALL BE CONDUCTED DAILY AND WITHIN 24 HOURS AFTER EACH 0.50 INCH OR GREATER RAINFALL EVENT. ANY NECESSARY REMEDIES SHALL BE PERFORMED IMMEDIATELY.
- 8. SEDIMENTATION CONTROLS/BMP'S SHALL PREVENT STORMWATER RUNOFF WITH TURBIDITY GREATER THAN 29 NTUs FROM LEAVING THE CONSTRUCTION SITE.

MAINTAINENCE OF TRAFFIC:

1. FDOT INDEX 102-602 & 102-603 TO BE USED.

<u>UTILITY NOTES:</u>

- 1. ALL PIPE, MATERIALS, AND WASTEWATER CONSTRUCTION SHALL COMPLY WITH CHAPTER 9 OF THE TOWN OF HOWEY-IN-THE-HILLS ENGINEERING STANDARDS MANUAL (ESM).
- 2. PER SECTION 9.03.05 OF THE ESM THE CONTRACTOR SHALL PROVIDE A DVD RECORDING OF VIDEO INSPECTION OF THE PRIVATE GRAVITY SANITARY SEWER SYSTEM TO THE CITY FOR WASTEWATER DIVISION REVIEW PRIOR TO ACCEPTANCE.
- 3. SEWER PIPE SHALL COMPLY WITH ASTM D3034 FOR GRAVITY SEWER.
- 4. SEWER JOINTS SHALL COMPLY WITH SECTION 9.03.01.B ASTM D3212 PUSH-ON ELASTOMERIC COMPRESSION GASKET TYPE.

PAVING AND DRAINAGE NOTES:

- 1. PIPE LENGTHS SHOWN REPRESENT SCALED DISTANCE BETWEEN CENTERLINES OF DRAINAGE STRUCTURES.
- 2. ALL CONCRETE DRAINAGE STRUCTURES TO BE CONSTRUCTED PER D.O.T. ROADWAY AND TRAFFIC DESIGN STANDARDS UNLESS OTHERWISE NOTED.
- 3. DITCH BOTTOM AND CONTROL STRUCTURE INLET GRATES SHALL BE SECURED WITH CHAIN AND EYEBOLT.
- 4. FIVE (5) FEET OF SOD IS REQUIRED AROUND ALL DITCH BOTTOM INLETS, MANHOLES, HEADWALLS AND MITERED END SECTIONS.
- 5. CONTRACTOR SHALL PLACE BLUE REFLECTIVE MARKERS ON PAVEMENT IN FRONT OF FIRE HYDRANTS.
- 6. TOP ELEVATIONS OF MANHOLES IN GRASSED AREAS SHALL BE AT MINIMUM 4 INCHES ABOVE FINISH GRADE.

AS-BUILT NOTE:

1. THE CONTRACTOR SHALL SUBMIT A CERTIFIED SET OF RECORD DRAWINGS TO THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RECORDING INFORMATION ON THE APPROVED PLANS CONCURRENTLY WITH CONSTRUCTION PROGRESS. RECORD DRAWINGS SUBMITTED TO THE ENGINEER AS PART OF THE PROJECT ACCEPTANCE SHALL COMPLY WITH THE TOWN OF HOWEY—IN—THE—HILLS REQUIREMENTS AND THE FOLLOWING REQUIREMENTS.

- A. DRAWINGS SHALL BE LEGIBLY MARKED TO RECORD ACTUAL CONSTRUCTION.
- B. DRAWINGS SHALL SHOW ACTUAL LOCATION OF ALL UNDERGROUND AND ABOVE GROUND STORM DRAINAGE, POTABLE WATER AND WASTEWATER PIPING, AND RELATED APPURTENANCES. ALL CHANGES TO PIPING LOCATION INCLUDING HORIZONTAL AND VERTICAL LOCATIONS OF UTILITIES AND APPURTENANCES SHALL BE CLEARLY SHOWN AND REFERENCED TO PERMANENT SURFACE IMPROVEMENTS. DRAWINGS SHALL ALSO SHOW ACTUAL INSTALLED PIPE MATERIAL, CLASS, ETC.
- C. DRAWINGS SHALL CLEARLY INDICATE VERTICAL AND HORIZONTAL SEPARATION BETWEEN POTABLE WATER MAIN AND STORM DRAINAGE/SANITARY SEWER/RECLAIMED WATER MAINS AT POINTS OF CROSSING IN ACCORDANCE WITH FDEP CRITERIA AT UTILITY CROSSINGS.
- D. DRAWINGS SHALL CLEARLY SHOW ALL FIELD CHANGES OF DIMENSION AND DETAIL INCLUDING CHANGES MADE BY FIELD ORDER OR BY CHANGE ORDER.
- E. DRAWINGS SHALL CLEARLY SHOW ALL DETAILS NOT ON ORIGINAL CONTRACT DRAWINGS, BUT CONSTRUCTED IN THE FIELD. ALL EQUIPMENT AND PIPING RELOCATION SHALL BE CLEARLY SHOWN.
- F. LOCATION OF ALL INLETS, MANHOLES, HYDRANTS, VALVES, AND VALVE BOXES SHALL BE SHOWN. ALL VALVES SHALL BE REFERENCED BY STATE PLANE COORDINATES.
- G. DIMENSIONS BETWEEN ALL INLETS AND MANHOLES SHALL BE FIELD VERIFIED AND THE INVERTS, AND GRADE ELEVATIONS OF ALL INLETS AND MANHOLES SHALL BE
- H. CONTRACTOR SHALL PROVIDE AS—BUILT SURVEY FOR POND GRADING. AS—BUILT POND CONTOURS SHALL BE PROVIDED AT TOP OF BANK, POND BOTTOM, AND ALL GRADE BREAKS AND ELEVATIONS SPECIFIED ON THE PLANS. CONTRACTOR SHAL BE RESPONSIBLE FOR RE—GRADING POND SLOPES THAT ARE STEEPER THAN SHOWN ON THE DESIGN PLANS.
- I. EACH SHEET OF THE PLANS SHALL BE SIGNED, SEALED AND DATED BY REGISTERED SURVEYOR WITH A NOTE READING "THESE AS—BUILT DRAWINGS ACCURATELY DEPICT THE ACTUAL IMPROVEMENTS AS CONSTRUCTED".
- J. WHERE THE POTABLE WATER MAIN CROSSES OTHER UTILITIES (STORM, GRAVITY SEWER, FORCEMAIN AND RECLAIMED WATER), THE CERTIFIED AS—BUILT DRAWINGS SHALL CLEARLY INDICATE THE CONSTRUCTED ELEVATIONS IN SUCH A WAY THAT THE VERTICAL SEPARATION BETWEEN THE WATER MAIN AND OTHER UTILITIES MAY BE VERIFIED BY THE ENGINEER. FAILURE TO PROVIDE THIS INFORMATION WILL RESULT IN THE CONTRACTOR EXCAVATING AND SURVEYING THE UTILITIES AT NO ADDITIONAL COST TO THE OWNER.
- K. WHERE THE POTABLE WATER MAIN CROSSES OTHER UTILITIES (STORM, GRAVITY SEWER, FORCEMAIN AND RECLAIMED WATER), THE CERTIFIED AS—BUILT DRAWINGS SHALL CLEARLY INDICATE THE LOCATIONS OF PIPE JOINTS IN SUCH A MANNER AS TO DEMONSTRATE THE PIPE IS CENTERED AT ALL THE CROSSINGS. FAILURE TO PROVIDE THIS INFORMATION WILL RESULT IN THE CONTRACTOR EXCAVATING AND SURVEYING THE UTILITIES AT NO ADDITIONAL COST TO THE OWNER.
- 2. CERTIFIED AS—BULT DRAWINGS SHALL BE PROVIDED TO THE ENGINEER PRIOR TO BACTERIOLOGICAL TESTING. FAILURE TO PROVIDE ACCURATE DRAWINGS MAY RESULT IN EXPIRED TEST RESULTS AND REQUIRE ADDITIONAL TESTING AT THE CONTRACTOR'S EXPENSE.
- 3. COORDINATE DATA SHALL BE PROVIDED IN STATE PLANE COORDINATES.
- 4. AS—BUILTS SHALL REFERENCE THE REQUIREMENTS OF CHAPTER 5 OF THE CITY'S ENGINEERING STANDARDS MANUAL.

ENGINEER'S CERTIFICATION NOTE:

"I, RYAN BLAIDA, P.E. HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE ALL EXISTING UTILITIES HAVE BEEN FIELD LOCATED AND THE LOCATION AND ELEVATION DEPICTED ON THESE PLANS IS BASED ON ACTUAL SURVEY, GROUND PENETRATING RADAR, SOFT DIG EXCAVATIONS, AND OTHER INDUSTRY METHODS. I FURTHER CERTIFY THAT ALL MEASURES HAVE BEEN TAKEN WITH REGARD TO UTILITY PROVIDERS' NOTIFICATION TO MARK UTILITIES IN ACCORDANCE WITH CHAPTER 556 F.S., SUNSHINE STATE ONE CALL."

"I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE AND BELIEF, THE DESIGN OF THE STORMWATER MANAGEMENT SYSTEM FOR THE PROJECT KNOWN AS: MASS GRADING RALEIGH STREET MEETS ALL OF THE REQUIREMENTS AND HAS BEEN DESIGNED SUBSTANTIALLY IN ACCORDANCE WITH THE TOWN OF HOWEY—IN—THE—HILLS STORMWATER MANAGEMENT CRITERIA."

| Planning | Planning

Wicke

onnelly

O

ING PLANS
E GROVES
THE HILLS

MASS GRADIN(
FOR HILLSIDE
HOWEY IN TH
PREPARED F
LENNAR - ORF
ORLANDO
ORLANDO

Sep 23, 2022 JUSTIN WILLIAMS, P.E FL P.E. #69260 **Rea. Engineer**

Project No.:
21-04-0008

Designed: Drawn:
RRB RAH

Checked: O.C.:
RRB RCW


Date:
APRIL 2021


Scale: DATUM:


Sheet C101


N/A


WETLAND	ACRE
А	6.59
В	14.31
С	7.94
D	62.25
E	10.19
F	3.39
G1	13.22
G2	6.31
G3	3.16
G4	0.18
G5	1.66
J	1.76
K	1.03
D2	0.19
D3	0.17




















Drainage Structure Table						
Name	Туре	Details	Location			
(B1-1)-1	'H' DBI	RIM = 81.00 INV OUT = 74.00 (NE)	N: 1590487.4478 E: 403555.7193			
(B1-1)-2	'C' DBI	RIM = 83.72 INV IN = 73.97 (SW)	N: 1590517.3890 E: 403595.7635			
(B2-1)-20	'H' DBI	RIM = 81.00 INV OUT = 74.00 (W)	N: 1590462.3094 E: 404391.1381			
(B2-1)-21	'C' DBI	RIM = 79.22 INV IN = 73.96 (E)	N: 1590450.9195 E: 404342.4526			
(B4-1)-18	'C' DBI	RIM = 84.69 INV IN = 73.98 (SE)	N: 1586729.7237 E: 404137.7254			
(B4-1)-20	'C' DBI	RIM = 85.00 INV IN = 73.98 (SW)	N: 1586690.3546 E: 404768.0442			
(B6)-2	'P' MH	RIM = 86.50 INV IN = 78.97 (W) INV OUT = 78.97 (NE)	N: 1590321.5469 E: 406133.5094			
(B6)-3	'C' DBI	RIM = 82.99 INV IN = 78.77 (SW)	N: 1590389.3743 E: 406172.8217			
(B9)-1	'C' DBI	RIM = 84.00 INV OUT = 79.22 (S)	N: 1590981.5085 E: 406067.3943			
(B9)-2	'P' MH	RIM = 85.00 INV IN = 78.67 (N) INV OUT = 78.67 (SE)	N: 1590705.4672 E: 406067.3943			
(B9)-3	'C' DBI	RIM = 83.38 INV IN = 78.38 (NW)	N: 1590597.3202 E: 406161.5856			
(B10)-2	'P' MH	RIM = 84.08 INV IN = 79.30 (SW) INV OUT = 79.30 (SE)	N: 1590337.9471 E: 407033.6499			
(B23)-1	'C' DBI	RIM = 82.99 INV OUT = 77.00 (E)	N: 1589343.3217 E: 406216.2088			
(B23)-3	'C' DBI	RIM = 82.98 INV IN = 73.96 (S)	N: 1589483.2381 E: 406510.5162			
(D1-1)-35	'P' MH	RIM = 86.65 INV IN = 81.94 (NE) INV OUT = 81.94 (SW)	N: 1588822.2260 E: 404013.0364			
(D1-2)-15	'P' MH	RIM = 87.19 INV IN = 82.03 (SE) INV OUT = 82.03 (NW)	N: 1589732.0243 E: 404687.9059			
(D1-2)-24	'P4' Cl	RIM = 90.09 INV IN = 85.30 (SE) INV OUT = 84.84 (N)	N: 1589493.6625 E: 404578.7770			
(D1-2)-35	'P3' CI-R	RIM = 90.77 INV IN = 85.64 (W) INV OUT = 85.64 (E)	N: 1589712.6383 E: 404438.3608			
(D1-3)-15	'P' MH	RIM = 87.00 INV OUT = 83.06 (W)	N: 1589976. 7082 E: 405566.0790			
(D1-4)-15	'P' MH	RIM = 88.30 INV IN = 80.12 (SW) INV OUT = 80.12 (SE)	N: 1588985.7717 E: 405729.4132			

Drainage Structure Table						
Name	Туре	Details	Location			
1-4)-17	'C' DBI	RIM = 83.00 $INV IN = 79.50 (NE)$	N: 1588983.0146 E: 405950.1727			
1-4)-18	'C' DBI	RIM = 83.00 INV OUT = 79.50 (SW)	N: 1589165.1794 E: 406202.7459			
02-1)-7	'P3' CI-R	RIM = 88.25 INV IN = 82.37 (N) INV IN = 83.37 (W) INV OUT = 81.87 (SE)	N: 1590518. 3552 E: 404655. 7864			
12-1)-15	P' MH	RIM = 86.00 INV OUT = 77.02 (W)	N: 1590498.5179 E: 405326.3260			
02-1)-16	'C' DBI	RIM = 83.00 INV IN = 77.00 (E)	N: 1590490.4766 E: 405305.3121			
02-2)-6	'P3' CI-L	RIM = 88.68 $INV IN = 82.14 (N)$ $INV IN = 83.79 (E)$ $INV OUT = 81.64 (W)$	N: 1591398.2676 E: 404495.1543			
2–2)–10	P'MH	RIM = 86.50 INV OUT = 77.02 (SW)	N: 1591728.4355 E: 403752.9500			
2-2)-11	'C' DBI	RIM = 83.00 $INV IN = 77.00 (NE)$	N: 1591706.9440 E: 403741.1979			
4-1)-15	'P' MH	RIM = 85.00 INV OUT = 79.00 (SW)	N: 1586597.9018 E: 405388.5952			
4-1)-16	'C' DBI	RIM = 83.00 INV IN = 76.70 (NE)	N: 1586578.9438 E: 405375.5723			
4-1)-17	'C' DBI	RIM = 83.00 INV IN = 79.50 (S)	N: 1586864.7710 E: 405878.6754			
4-1)-18	'P' MH	RIM = 86.50 INV IN = 79.50 (S) INV OUT = 79.50 (N)	N: 1586831.8669 E: 405888.2502			
4-1)-19	'P' MH	RIM = 85.00 INV IN = 79.50 (S) INV OUT = 79.50 (N)	N: 1586636.2773 E: 405887.4845			
4-1)-20	'C' DBI	RIM = 85.54 INV OUT = 79.50 (N)	N: 1586599.4136 E: 405876.2749			
/3–1)–15	'P' MH	RIM = 85.50 INV OUT = 77.04 (W)	N: 1590613.2596 E: 405986.4912			
(3–2)–15	'P' MH	RIM = 86.00 INV OUT = 77.09 (NE)	N: 1590955.8999 E: 406579.4621			
(3–2)–17	'C' DBI	RIM = 77.80 INV IN = 73.97 (NE)	N: 1591040.2441 E: 406451.1525			
(3–3)–15	'P' MH	RIM = 87.00 INV OUT = 78.08 (SW)	N: 1589882.1068 E: 407103.2258			
(3–3)–17	'P' MH	RIM = 87.00 INV OUT = 78.09 (NW)	N: 1589547.6729 E: 407100.2470			
(3–4)–20	'P' MH	RIM = 86.50 INV OUT = 77.09 (S)	N: 1589893.7446 E: 406153.0898			

	Dra	inage Structure Table	?
Name	Туре	Details	Location
(W4-1)-7	P' MH	RIM = 87.36 INV IN = 84.61 (NE) INV OUT = 69.16 (S)	N: 1588034.4423 E: 404902.5102
(W4-1)-33	P' MH	RIM = 87.50 INV IN = -1.55 (W) INV OUT = 77.06 (SE)	N: 1587928.8718 E: 404634.1131
(W4-2)-15	'P' MH	RIM = 86.50 INV OUT = 76.95 (S)	N: 1586828.8646 E: 403514.8492
(W4-2)-20	'C' DBI	RIM = 85.00 INV IN = 76.95 (NW)	N: 1586739.1286 E: 403761.1542
C-6	P' MH	RIM = 87.57 INV IN = 78.88 (SE) INV IN = 82.67 (NW) INV OUT = 81.09 (W)	N: 1588051.3909 E: 405698.3045
DS1-2	'E' DBI	RIM = 2.08 $INV OUT = -1.00 (SW)$	N: 1589609.2057 E: 404517.6567
DS2-1	'C' DBI	RIM = 85.08 INV IN = 82.00 (W)	N: 1590402.0570 E: 404666.0101
DS2-1A	'C' DBI	RIM = 85.41 INV OUT = 82.33 (E)	N: 1590461.2716 E: 404513.0702
DS3-1	'C' DBI	RIM = 85.00 INV OUT = 77.00 (W)	N: 1590687.5198 E: 405854.1681
DS3-2	'C' DBI	RIM = 85.00 INV OUT = 74.00 (SW)	N: 1591064.4909 E: 406491.9979
DS3-4	'C' DBI	RIM = 85.50 INV OUT = 74.00 (N)	N: 1589433.3103 E: 406513.2079
DS4-1	'C' DBI	RIM = 85.00 INV OUT = 77.00 (S)	N: 1587687.8424 E: 404929.0941
DS4-2	'E' DBI	RIM = 86.40 INV OUT = 77.00 (SE)	N: 1586768.3379 E: 403715.1426
H4-1-E	'E' DBI	RIM = 81.00 INV OUT = 74.00 (NE)	N: 1586654.0025 E: 404737.3604
H4-1-W	'E' DBI	RIM = 81.00 INV OUT = 74.00 (NW)	N: 1586701.2472 E: 404175.7825

Name	Туре	Details	Location
(B2-1)-1	MES	INV IN = 81.25 (E)	N: 1591090.8903 E: 404543.5809
(B2-1)-10	MES	INV IN = 80.94 (SE)	N: 1590263.4475 E: 404465.2081
(B2-1)-11	MES	INV OUT = 80.96 (NW)	N: 1590224.4837 E: 404546.3365
(B2-2)-1	MES	INV OUT = 81.45 (W)	N: 1591110.3098 E: 404631.4608
(B6)-1	MES	INV OUT = 79.50 (E)	N: 1590321.5469 E: 405955.4683
(B10)-1	MES	INV OUT = 79.48 (NE)	N: 1590240.1036 E: 406907.8904
(B10)-3	MES	INV IN = 79.21 (NW)	N: 1590301. 7939 E: 407073.8888
(B21)-1	MES	INV OUT = 80.90 (E)	N: 1587157.1827 E: 404209.6026
(B22)-1	MES	INV IN = 80.62 (W)	N: 1587162.8809 E: 404234.9060
(B23)-2	MES	INV IN = 76.94 (W)	N: 1589360.4420 E: 406277.8764
(D1-1)-36	MES	INV IN = 81.92 (NE)	N: 1588808.1004 E: 403994.8851
(D1-2)-16	MES	INV IN = 82.00 (SE)	N: 1589754.0969 E: 404672.3560
(D1-2)-48	MES	INV IN = 84.09 (NW)	N: 1589869.0135 E: 404461.1340
(D1-3)-16	MES	/NV /N = 83.00 (E)	N: 1589976.9796 E: 405534.0802
(D1-4)-16	MES	INV IN = 80.03 (NW)	N: 1588950.5011 E: 405796.7379
(D2-1)-8	MES	INV IN = 81.81 (NW)	N: 1590494.1449 E: 404694.4561
(D2-2)-7	MES	INV IN = 81.56 (E)	N: 1591402.0188 E: 404452.8202
(W3-1)-16	MES	INV IN = 77.00 (E)	N: 1590613.5903 E: 405942.4926
(W3-1)-17	MES	INV IN = 76.50 (E)	N: 1590686.9868 E: 405819.1722
(W3-2)-16	MES	INV IN = 77.00 (SW)	N: 1590993.8058 E: 406601.8036

<i>Name</i>	Туре	Details	Location	
(W3-3)-16	MES	INV IN = 78.00 (NE)	N: 1589856.3162 E: 407070.0770	
(W3-3)-18	MES	INV IN = 78.00 (SE)	N: 1589584.7306 E: 407071.3378	
(W3-3)-19	MES	INV IN = 76.97 (SE)	N: 1589739.1179 E: 406925.3072	
(W3-4)-21	MES	INV IN = 77.00 (N)	N: 1589847.3574 E: 406156.3374	
(W4-1)-8	MES	INV IN = 69.00 (N)	N: 1587957.1695 E: 404890.8511	
(W4-1)-34	MES	INV IN = 77.00 (NW)	N: 1587904.4818 E: 404691.8339	
(W4-1)-35	MES	INV IN = 76.92 (N)	N: 1587604.9019 E: 404910.4966	
(W4-2)-16	MES	INV IN = 77.00 (N)	N: 1586777.9057 E: 403512.8034	
D22-2	MES	INV OUT = 80.71 (E)	N: 1587387.8934 E: 405096.2266	
D22-3	MES	INV IN = 80.46 (W)	N: 1587402.3245 E: 405133.5096	
DS1-3	MES	INV /N = -1.00 (NE)	N: 1589520.7784 E: 404351.1418	

	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\		Planning • Engineering • Landscape Architectu	1560 NORTH ORANGE AVE., SUITE 210 WINTER PARK, FLORIDA 327	7000 13C (201) (100 13C (201)
		L (
	MASS GRADING PLANS	FOR HILSINE GROVES	HOWEY IN THE HILLS	PREPARED FOR	() ()
2		t No 4-00	n-	Sep 23, 2022	USTIN WILLIAMS, P.E.

 Project No.:
 21-04-0008

 Designed:
 Drawn:

 RRB
 RAH

 Checked:
 O.C.:


 RRB
 RCW

 Date:
 APRIL 2021

 Scale:
 DATUM:

 N/A
 N/A


Sheet C505




- NOTES: SECTION VIEW
- MOUNT BRACKETS TO SKIMMERS W/ 1/4" STAINLESS STEEL BOLTS.
 MOUNT BRACKETS TO STRUCTURES W/ 3/8" x 3-1/2" STAINLESS STEEL WEDGE ANCHORS.
- 3. A PERMANENT BENCH MARK IS TO BE SET IN A PERMANENT MANNER ON TOP OF THE OUTFALL CONTROL STRUCTURE.
- 4. SKIMMER TO BE MOUNTED TO DBI IN ACCORDANCE WITH MANUFACTURES SPECIFICATIONS USING 'Z' BRACKETS.
- 5. THE CONTROL STRUCTURES ARE TO BE LOCATED IN THE POND PER THE CONTROL STRUCTURE DETAIL.

 6. ALL BOX STRUCTURES ARE TO INCLUDE GRATES AND CHAINS.


 MOUNTING 'Z' BRACKET DETAIL



NOTE:
STRUCTURES SHALL HAVE AN OSCEOLA COUNTY
BRASS DISK BENCHMARK PERMANENTLY SET ON TOP
OF THE STRUCTURE USING NON—SHRINK GROUT.
ELEVATION OF BENCHMARK SHALL BE CERTIFIED TO
OSCEOLA COUNTY BY A FLORIDA REGISTERED
PROFESSIONAL SURVEYOR.



<u>TYPICAL CONTROL STRUCTURE DET</u> N.T.S.




PLAN	VIEW
N. T. S.	_

BROADCRESTED WEIR STRUCTURE DIM.						
POND						
W1 – 1	85.50	25'				
W1-2	86.50	25'				
W1-3	86.50	25'				
W1-4	84.50	25'				
W2-1	85.00	25'				
W2-2	85.50	25'				
W4-1	83.50	25'				

DRY POND ELEVATIONS										
POND ELEV. (A) ELEV. (B) ELEV. (C)										
D1-1	83.0	84.0	86.5							
D1-2	83.0	87.5	88.0							
D1-3	83.0	86.0	87.0							
D1-4	83.0	84.0	85.0							
D2-1	83.00	84.50	85.50							
D2-2	83.0	85.0	86.10							
D4-1	83.0	84.00	85.00							

	CONTROL STRUCTURE ELEVATIONS									
POND	I.D. NO.	STR. TYPE	PIPE DIA. (A)	ELEV. (B)	ELEV. (C)	ELEV. (D)	DIM. (E)	ELEV. (F)	DIM. (G)	ORIFICE QUANTITY
W4-2	DS4-2	DS	24"	81.00	82.50	86.40	<i>36"</i>	77.00	3.00"	1
W3-4	DS3-4	DS	24"	81.00	84.50	85.50	<i>36"</i>	77.00	3.00"	1
W4-1	DS4-1	DS	24"	81.00	84.00	85.00	<i>36</i> "	77.00	3.00"	1
W3-3	DS3-3	DS	24"	81.00	84.00	85.00	<i>36</i> "	77.00	3.00"	1
W3-2	DS3-2	DS	24"	81.00	84.00	85.00	<i>36</i> "	77.00	3.00"	1
W3-1	DS3-1	DS	24"	81.00	84.00	85.00	<i>36"</i>	77.00	3.00"	1
B4-1	H4-1-W	DS	<i>36"</i>	81.00						
B4-1	H4-1-E	DS	<i>36"</i>	81.00						
B2-1	DS-B2-1	DS	48"	81.00						
B1-1	H1-1	DS	48"	81.00						
WET G3	E-WETG	DS	24"	81.00						
WET J	E-WETJ	DS	24"	81.00						
WET F	E-WETF	DS	24"	81.00						
D2-1	DS2-1	DS	24"	81.00						
D1-3	DS1-3	DS	24"	81.00						
D1-2	DS1-2	DS	24"	81.00						




TYPICAL DRY POND SECTION
N.T.S.

TYPICAL WET POND SECTION N.T.S.

	WET AND BORROW POND ELEVATIONS						
POND	ELEV. (A)	ELEV. (B)	ELEV. (C)	ELEV. (D)	ELEV. (E)		
B1-1	71.0	79.0	81.0	84.5	<i>85.5</i>		
B2-1	71.0	79.0	81.0	84.5	<i>85.5</i>		
B4-1	69.0	79.0	81.0	84.0	<i>85.0</i>		
W3-1	69.0	79.00	81.00	84	<i>85.0</i>		
W3-2	69.0	79.0	81.00	84.00	85.00		
W3-3	69.00	79.00	81.00	84.00	85.00		
W3-4	69.00	79.0	81.0	84.00	<i>85.5</i>		
W4-1	71.00	79.00	81.00	84.50	85.00		
W4-2	71.5	79.00	81.00	<i>85.4</i>	86.4		

→ 2'	VARIES —	→ 2' ←
↓	WEIR WIDTH	TOP OF BANK
WEIR INV. EL. 'B'	3:7	4" CONCRETE WEIR
MENN MAY. EE. B		
	TYPICAL SECTION B N. T. S.	



BROADCRESTED WEIR STRUCTURE DETAIL
N.T.S.

	PEAK STAGE SUMMARY					
POND	NCL	TOP OF BANK	25YR/24HR	10YR/24HR	100YR/24HR	25YR/96HR
B1-1	81.0	85.5	83.6	83.6	83.6	83.6
B2-1	81.0	85.5	83.6	83.6	83.6	83.6
B4-1	81.0	85.00	82.2	81.9	82.7	83.0
D1-1	83.0	86.5	85.3	84.8	85.6	85.6
D1-2	83.0	88.0	86.6	86.0	87.4	87.9
D1-3	83.0	87.0	84.5	84.1	85.2	85.6
D1-4	83.0	87.0	85.2	85.6	85.44	85.52
D2-1	83.0	85.5	84.7	84.5	84.9	85.0
D2-2	83.00	86.1	85.6	85.6	85.8	85.9
D4-1	83.00	85.0	83.9	83.9	84.1	84.1
W3-1	81.00	85.0	83.99	83.3	84.4	84.5
W3-2	81.00	85.0	82.7	82.4	83.4	<i>83.7</i>
W3-3	81.00	85.0	83.4	82.9	84.2	84.2
W3-4	81.00	85.5	84.0	83.4	84.9	85.0
W4-1	81.00	85.0	84.5	84.1	85.0	85.1
W4-2	81.00	86.4	83.9	83.5	84.7	85.1

O.C.: RCW

Checked: RRB

Date:
 APRIL 2021
Scale:
 1" = 100'


Sheet C510

y & Wicker Inc. Landscape Architecture

Connelly

STRUCTURE TAILS

CONTROL (



THE FOLLOWING LIST REPRESENTS A BASIC EROSION AND SEDIMENT CONTROL PROGRAM WHICH IS TO BE IMPLEMENTED TO HELP PREVENT OFF—SITE SEDIMENTATION DURING AND AFTER CONSTRUCTION OF THE PROJECT.

PERMANENT EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTRUCTION ACTIVITIES SHOULD BE THE PLACEMENT OF PERMANENT AND TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES AROUND THE PERIMETER OF THE PROJECT OR THE INITIAL WORK AREA TO PROTECT THE PROJECT, ADJACENT PROPERTIES AND WATER RESOURCES.

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE COORDINATED WITH PERMANENT MEASURES TO ASSURE ECONOMICAL, EFFECTIVE AND CONTINUOUS CONTROL THROUGHOUT THE CONSTRUCTION PHASE. TEMPORARY MEASURES SHALL NOT BE CONSTRUCTED FOR EXPEDIENCY IN LIEU OF PERMANENT MEASURES.

EROSION AND SEDIMENT CONTROL MEASURES SHALL BE ADEQUATELY MAINTAINED TO PERFORM THEIR INTENDED FUNCTION DURING CONSTRUCTION OF THE PROJECT.

NECESSARY REPAIRS TO BARRIERS OR REPLACEMENT OF BARRIERS SHALL BE ACCOMPLISHED PROMPTLY.

SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH RAINFALL. THEY MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE—HALF THE HEIGHT OF THE BARRIER.


MATERIAL FROM SEDIMENT TRAPS SHALL NOT BE STOCKPILED OR DISPOSED OF IN A MANNER WHICH MAKES THEM READILY SUSCEPTIBLE TO BEING WASHED INTO ANY WATERCOURSE BY RUNOFF OR HIGH WATER.

SUSCEPTIBLE TO BEING WASHED INTO ANY WATERCOURSE BY RUNOFF OR HIGH WATER.


ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE BARRIERS ARE NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.


EROSION & SEDIMENT CONTROL (n.t.s.)







DETAIL G-1









Howey-in-the-Hills

Standard Details

DATE: FEB 2022 DETAIL G-4	TOWN OF HOWEY-IN-THE-HILLS DETAILS	
LTER	HOWE	
UIRED. 3" COURSE GREGATE NIMUM 6" CK (TYP) PR FLOWING R AND/OR	MASS GRADING PLANS FOR HILLSIDE GROVES HOWEY IN THE HILLS	PREPARED FOR
EGATE AND DATE: FEB 2022		Sep 23, 2022
DETAIL R-23	Project No.: 21-04-0008 Designed: Draw RRB R/ Checked: O.C. RRB R/ Date: R	Al .:
	Date: APRIL 2021 DAT	U

Wicker

Connelly

GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE

KNOWING VIOLATIONS.

SIGNED: .

DATED: _

BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I

AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE

INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR

THE CONTRACTOR SHALL AT A MINIMUM IMPLEMENT THE CONTRACTOR'S REQUIREMENTS OUTLINED BELOW AND THOSE MEASURES SHOWN ON THE EROSION AND TURBIDITY CONTROL PLAN. IN ADDITION THE CONTRACTOR SHALL UNDERTAKE ADDITIONAL MEASURES REQUIRED TO BE IN COMPLIANCE WITH APPLICABLE PERMIT CONDITIONS AND STATE WATER QUALITY STANDARDS. DEPENDING ON THE NATURE OF MATERIALS AND METHODS OF CONSTRUCTION THE CONTRACTOR MAY BE REQUIRED TO ADD FLOCCULANTS TO THE RETENTION SYSTEM PRIOR TO PLACING THE SYSTEM INTO OPERATION.

GENERAL

SEQUENCE OF MAJOR ACTIVITIES:

TIMING OF CONTROLS/MEASURES

AS INDICATED IN THE SEQUENCE OF MAJOR ACTIVITIES, THE SILT FENCES

AND HAY BALES AND STABILIZED CONSTRUCTION ENTRANCE

WILL BE CONSTRUCTED PRIOR TO CLEARING OR GRADING OF ANY

CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY

WITH THE PLANS. AFTER THE ENTIRE SITE IS STABILIZED, THE

IN ACCORDANCE WITH THE EROSION & TURBIDITY CONTROL PLAN.

OTHER PORTIONS OF THE SITE. STABILIZATION MEASURES SHALL BE

INITIATED AS SOON AS PRACTICAL IN PORTIONS OF THE SITE WHERE

CEASED. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN

AREA, THAT AREA WILL BE STABILIZED PERMANENTLY IN ACCORDANCE

ACCUMULATED SEDIMENT WILL BE REMOVED FROM THE SEDIMENT TRAPS

IT IS THE CONTRACTORS RESPONSIBILITY TO IMPLEMENT THE EROSION AND

TURBIDITY CONTROLS AS SHOWN ON THE EROSION AND TURBIDITY CONTROL

CONTROLS ARE PROPERLY INSTALLED, MAINTAINED AND FUNCTIONING PROPERLY

TO PREVENT TURBID OR POLLUTED WATER FROM LEAVING THE PROJECT SITE.

THE CONTRACTOR WILL ADJUST THE EROSION AND TURBIDITY CONTROLS SHOWN

ON THE EROSION AND TURBIDITY CONTROL PLAN AND ADD ADDITIONAL CONTROL

MEASURES, AS REQUIRED, TO ENSURE THE SITE MEETS ALL FEDERAL, STATE AND

LOCAL EROSION AND TURBIDITY CONTROL REQUIREMENTS. THE FOLLOWING BEST

REQUIRED BY THE EROSION AND TURBIDITY CONTROL PLAN AND AS REQUIRED

TO MEET THE EROSION AND TURBIDITY REQUIREMENTS IMPOSED ON THE PROJECT

MANAGEMENT PRACTICES WILL BE IMPLEMENTED BY THE CONTRACTOR AS

HAY BALE BARRIER: HAY BALE BARRIERS CAN BE USED BELOW

B. IN MINOR SWALES OR DITCH LINES WHERE THE MAXIMUM

DISTURBED AREAS SUBJECT TO SHEET AND RILL EROSION WITH THE

A. WHERE THE MAXIMUM SLOPE BEHIND THE BARRIER IS 33 PERCENT.

CONTRIBUTING DRAINAGE AREA IS NO GREATER THAN 2 ACRES.

D. EVERY EFFORT SHOULD BE MADE TO LIMIT THE USE OF STRAW BALE

BARRIERS CONSTRUCTED IN LIVE STREAMS OR IN SWALES WHERE

THERE IS THE POSSIBILITY OF A WASHOUT. IF NECESSARY, MEASURES

C. WHERE EFFECTIVENESS IS REQUIRED FOR LESS THAN 3 MONTHS.

SHALL BE TAKEN TO PROPERLY ANCHOR BALES TO INSURE

REFER TO LOCAL JURISDICTION DETAIL FOR CONSTRUCTING THE HAY

2. FILTER FABRIC BARRIER: FILTER FABRIC BARRIERS CAN BE USED BELOW

B. IN MINOR SWALES OR DITCH LINES WHERE THE MAXIMUM

3. BRUSH BARRIER WITH FILTER FABRIC: BRUSH BARRIER MAY BE USED

4. LEVEL SPREADER: A LEVEL SPREADER MAY BE USED WHERE SEDIMENT-

ENOUGH RESIDUE MATERIAL IS AVAILABLE ON SITE.

DISTURBED AREAS SUBJECT TO SHEET AND RILL EROSION WITH THE

A. WHERE THE MAXIMUM SLOPE BEHIND THE BARRIER IS 33 PERCENT.

CONTRIBUTING DRAINAGE AREA IS NO GREATER THAN 2 ACRES.

BELOW DISTURBED AREAS SUBJECT TO SHEET AND RILL EROSION WHERE

FREE STORM RUNOFF IS INTERCEPTED AND DIVERTED AWAY FROM THE

GRADED AREAS ONTO UNDISTURBED STABILIZED AREAS. THIS PRACTICE

APPLIES ONLY IN THOSE SITUATIONS WHERE THE SPREADER CAN BE

SITE BY THE REGULATORY AGENCIES.

EROSION AND SEDIMENT CONTROLS

FOLLOWING LIMITATIONS:

AGAINST WASHOUT

FOLLOWING LIMITATIONS:

BALE BARRIER.

STABILIZATION PRACTICES

PLAN. IT IS ALSO THE CONTRACTORS RESPONSIBILITY TO ENSURE THESE

AND THE EARTH DIKE/SWALES WILL BE REGRADED/REMOVED AND STABILIZED

THE ORDER OF ACTIVITIES WILL BE AS FOLLOWS:

- 1. INSTALL STABILIZED CONSTRUCTION ENTRANCE
- INSTALL SILT FENCES AND HAY BALES AS REQUIRED
- CLEAR AND GRUB FOR DIVERSION SWALES/DIKES AND SEDIMENT
- 4. CONSTRUCT SEDIMENTATION
- 5. CONTINUE CLEARING AND GRUBBING 6. STOCK PILE TOP SOIL IF REQUIRED
- 7. PERFORM PRELIMINARY GRADING ON SITE AS REQUIRED 8. STABILIZE DENUDED AREAS AND STOCKPILES AS SOON AS

PRACTICABLE

- 9. INSTALL UTILITIES, STORM SEWER, CURBS & GUTTER.
- 10. APPLY BASE TO PROJECT 11. COMPLETE GRADING AND INSTALL PERMANENT SEEDING/SOD AND PLANTING 12. COMPLETE FINAL PAVING

13. REMOVE ACCUMULATED

- SEDIMENT FROM BASINS 14. WHEN ALL CONSTRUCTION ACTIVITY IS COMPLETE AND THE SITE IS STABILIZED, REMOVE ANY TEMPORARY DIVERSION
 - 9. TEMPORARY SEEDING AND MULCHING: SLOPES STEEPER THAN 6:1 THAT SWALES/DIKES AND RESEED/SOD FALL WITHIN THE CATEGORY ESTABLISHED IN PARAGRAPH 8 ABOVE AS REQUIRED SHALL ADDITIONALLY RECEIVE MULCHING OF APPROXIMATELY 2 INCHES LOOSE MEASURE OF MULCH MATERIAL CUT INTO THE SOIL OF THE SEEDED AREA ADEQUATE TO PREVENT MOVEMENT OF SEED AND MULCH.
 - 10. TEMPORARY GRASSING: THE SEEDED OR SEEDED AND MULCHED AREA(S) SHALL BE ROLLED AND WATERED OR HYDROMULCHED OR OTHER SUITABLE METHODS IF REQUIRED TO ASSURE OPTIMUM GROWING CONDITIONS FOR THE ESTABLISHMENT OF A GOOD GRASS COVER. TEMPORARY GRASSING SHALL BE THE SAME MIX & AMOUNT REQUIRED FOR PERMANENT GRASSING IN THE CONTRACT SPECIFICATIONS.

CONSTRUCTED ON UNDISTURBED SOIL AND THE AREA BELOW THE LEVEL

STOCKPILED IN SUCH A MANNER AS TO DIRECT RUNOFF DIRECTLY OFF

6. EXPOSED AREA LIMITATION: THE SURFACE AREA OF OPEN, RAW ERODEABLE

EXCAVATION AND FILLING OPERATIONS SHALL NOT EXCEED 10 ACRES.

THIS REQUIREMENT MAY BE WAIVED FOR LARGE PROJECTS WITH AN

ADDITIONAL AREAS WILL NOT SIGNIFICANTLY AFFECT OFF-SITE DEPOSIT

DIRECTLY OFF-SITE SHALL BE PROTECTED FROM SEDIMENT-LADEN STORM

AND THAT ARE NOT ANTICIPATED TO BE RE-EXCAVATED OR DRESSED AND

RECEIVE FINAL GRASSING TREATMENT WITHIN 30 DAYS SHALL BE SEEDED

WITH A QUICK GROWING GRASS SPECIES WHICH WILL PROVIDE AN EARLY

COVER DURING THE SEASON IN WHICH IT IS PLANTED AND WILL NOT

RUNOFF UNTIL THE COMPLETION OF ALL CONSTRUCTION OPERATIONS

8. TEMPORARY SEEDING: AREAS OPENED BY CONSTRUCTION OPERATIONS

EROSION CONTROL PLAN WHICH DEMONSTRATES THAT OPENING OF

SOIL EXPOSED BY CLEARING AND GRUBBING OPERATIONS OR

7. INLET PROTECTION: INLETS AND CATCH BASINS WHICH DISCHARGE

THAT MAY CONTRIBUTE SEDIMENT TO THE INLET.

LATER COMPETE WITH THE PERMANENT GRASSING.

THE PROJECT SITE INTO ANY ADJACENT WATER BODY OR STORM WATER

RECONCENTRATE AFTER RELEASE. LEVEL SPREADER SHALL BE CONSTRUCTED

LIP IS STABILIZED. THE WATER SHOULD NOT BE ALLOWED TO

IN ACCORDANCE TO LOCAL JURISDICTION DETAIL.

OF SEDIMENTS.

5. STOCKPILING MATERIAL: NO EXCAVATED MATERIAL SHALL BE

- 11. TEMPORARY REGRASSING: IF, AFTER 14 DAYS FROM SEEDING, THE TEMPORARY GRASSED AREAS HAVE NOT ATTAINED A MINIMUM OF 75 PERCENT GOOD GRASS COVER, THE AREA WILL BE REWORKED AND ADDITIONAL SEED APPLIED SUFFICIENT TO ESTABLISH THE DESIRED VEGETATIVE COVER.
- 12. MAINTENANCE: ALL FEATURES OF THE PROJECT DESIGNED AND CONSTRUCTED TO PREVENT EROSION AND SEDIMENT SHALL BE MAINTAINED DURING THE LIFE OF THE CONSTRUCTION SO AS TO FUNCTION AS THEY WERE ORIGINALLY DESIGNED AND CONSTRUCTED.
- 13. PERMANENT EROSION CONTROL: THE EROSION CONTROL FACILITIES OF THE PROJECT SHOULD BE DESIGNED TO MINIMIZE THE IMPACT ON THE
- 14. PERMANENT SEEDING: ALL AREAS WHICH HAVE BEEN DISTURBED BY CONSTRUCTION WILL, AS A MINIMUM, BE SEEDED. THE SEEDING MIX MUST PROVIDE BOTH LONG-TERM VEGETATION AND RAPID GROWTH SEASONAL VEGETATION. SLOPES STEEPER THAN 4:1 SHALL BE SEEDED AND MULCHED

STRUCTURAL PRACTICES

- 1. TEMPORARY DIVERSION DIKE: TEMPORARY DIVERSION DIKES MAY BE USED TO DIVERT RUNOFF THROUGH A SEDIMENT-TRAPPING FACILITY.
- 2. TEMPORARY SEDIMENT TRAP: A SEDIMENT TRAP SHALL BE INSTALLED IN A DRAINAGEWAY AT A STORM DRAIN INLET OR AT OTHER POINTS OF DISCHARGE FROM A DISTURBED AREA. THE FOLLOWING SEDIMENT TRAPS MAY BE CONSTRUCTED EITHER INDEPENDENTLY OR IN CONJUNCTION WITH A TEMPORARY DIVERSION
 - A. BLOCK & GRAVEL SEDIMENT FILTER THIS PROTECTION IS APPLICABLE WHERE HEAVY FLOWS AND/OR WHERE AN OVERFLOW CAPACITY IS NECESSARY TO PREVENT EXCESSIVE PONDING AROUND THE STRUCTURE.
- B. GRAVEL SEDIMENT TRAP THIS PROTECTION IS APPLICABLE WHERE HEAVY CONCENTRATED FLOWS ARE EXPECTED, BUT NOT WHERE PONDING AROUND THE STRUCTURE MIGHT CAUSE EXCESSIVE INCONVENIENCE OR DAMAGE TO ADJACENT STRUCTURES & UNPROTECTED
- C. DROP INLET SEDIMENT TRAP THIS PROTECTION IS APPLICABLE WHERE THE INLET DRAINS A RELATIVELY FLAT AREA (S < 5%) AND WHERE SHEET OR OVERLAND FLOWS (Q < 0.5 CFS) ARE TYPICAL. THIS METHOD SHALL NOT APPLY TO INLETS RECEIVING CONCENTRATED FLOWS SUCH AS IN STREET OR HIGHWAY MEDIANS.
- 3. OUTLET PROTECTION: APPLICABLE TO THE OUTLETS OF ALL PIPES AND PAVED CHANNEL SECTIONS WHERE THE FLOW COULD CAUSE EROSION & SEDIMENT PROBLEM TO THE RECEIVING WATER BODY. SILT FENCES & HAY BALES ARE TO BE INSTALLED IMMEDIATELY DOWNSTREAM OF THE DISCHARGING STRUCTURE AS SHOWN ON THE OUTLET PROTECTION DETAIL.
- 4. SEDIMENT BASIN: WILL BE CONSTRUCTED AT THE COMMON DRAINAGE LOCATIONS THAT SERVE AN AREA WITH 10 OR MORE DISTURBED ACRES AT ONE TIME, THE PROPOSED STORM WATER PONDS (OR TEMPORARY PONDS) WILL BE CONSTRUCTED FOR USE AS SEDIMENT BASINS. THESE SEDIMENT BASINS MUST PROVIDE A MINIMUM OF 3,600 CUBIC FEET OF STORAGE PER ACRE DRAINED UNTIL FINAL STABILIZATION OF THE SITE.

THE 3,600 CUBIC FEET OF STORAGE AREA PER ACRE DRAINED DOES NOT APPLY TO FLOWS FROM OFFSITE AREAS AND FLOWS FROM ONSITE AREAS THAT ARE EITHER UNDISTURBED OR HAVE UNDERGONE FINAL STABILIZATION WHERE SUCH FLOWS ARE DIVERTED AROUND BOTH THE DISTURBED AREA AND THE SEDIMENT BASIN. ANY TEMPORARY SEDIMENT BASINS CONSTRUCTED MUST BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH THE SPECIFICATIONS FOR STRUCTURAL FILL. ALL SEDIMENT COLLECTED IN PERMANENT OR TEMPORARY SEDIMENT TRAPS MUST BE REMOVED UPON FINAL STABILIZATION.

OTHER CONTROLS

WASTE DISPOSAL

WASTE MATERIALS

ALL WASTE MATERIALS EXCEPT LAND CLEARING DEBRIS SHALL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS. THE DUMPSTER WILL BE EMPTIED AS NEEDED AND THE TRASH WILL BE HAULED TO A STATE APPROVED LANDFILL. ALL PERSONNEL WILL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL. NOTICES STATING THESE PRACTICES WILL BE POSTED AT THE CONSTRUCTION SITE BY THE CONSTRUCTION SUPERINTENDENT, THE INDIVIDUAL WHO MANAGES THE DAY-TO-DAY SITE OPERATIONS, WILL BE RESPONSIBLE FOR SEEING THAT THESE PROCEDURES ARE FOLLOWED.

ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER. SITE PERSONNEL WILL BE INSTRUCTED IN THESE PRACTICES AND THE SITE SUPERINTENDENT, THE INDIVIDUAL WHO MANAGES DAY-TO-DAY SITE OPERATIONS, WILL BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED.

ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NEEDED TO PREVENT POSSIBLE SPILLAGE. THE WASTE WILL BE COLLECTED AND DEPOSED OF IN ACCORDANCE WITH STATE AND LOCAL WASTE DISPOSAL REGULATIONS FOR SANITARY SEWER OR SEPTIC SYSTEMS.

OFFSITE VEHICLE TRACKING

A STABILIZED CONSTRUCTION ENTRANCE WILL BE PROVIDED TO HELP REDUCE VEHICLE TRACKING OF SEDIMENTS. THE PAVED STREET ADJACENT TO THE SITE ENTRANCE WILL BE SWEPT DAILY TO REMOVE ANY EXCESS MUD, DIRT OR ROCK TRACKED FROM THE SITE. DUMP TRUCKS HAULING MATERIAL FROM THE CONSTRUCTION SITE WILL BE COVERED WITH A

INVENTORY FOR POLLUTION PREVENTION PLAN

THE MATERIALS OR SUBSTANCES LISTED BELOW ARE EXPECTED TO BE PRESENT ONSITE DURING CONSTRUCTION:

Concrete		⊠ Wood	
Asphalt Asphalt	☐ Petroleum Based Products	⊠ Masonry Blocks	
☑ Tar	☑ Cleaning Solvents	🛮 Roofing Materials	
Detergents	□ Paints	⊠ Metal Studs	
]	□		

SPILL PREVENTION

MATERIAL MANAGEMENT PRACTICES THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE

THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED

ONSITE DURING THE CONSTRUCTION PROJECT.

OF MATERIALS AND SUBSTANCES TO STORM WATER RUNOFF.

* AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO

- * ALL MATERIALS STORED ONSITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE.
- PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL.
- * SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER.
- WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER.
- * MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED.
- * THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE MATERIALS ONSITE RECEIVE PROPER USE AND DISPOSAL.

HAZARDOUS PRODUCTS

- THESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS.
- PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE.
- ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED; THEY
- CONTAIN IMPORTANT PRODUCT INFORMATION. * IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S OR LOCAL

AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE

PRODUCT SPECIFIC PRACTICES

RECOMMENDATIONS.

THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ONSITE:

ALL ONSITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S

FERTILIZERS

PETROLEUM PRODUCTS

FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER. ONCE APPLIED, FERTILIZER WILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER. STORAGE WILL BE IN A COVERED AREA. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER WILL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS.

PAINTS

ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURERS' INSTRUCTIONS OR STATE AND LOCAL REGULATIONS. CONCRETE TRUCKS

CONCRETE TRUCKS WILL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON THE SITE.

SPILL CONTROL PRACTICES

IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

MANUFACTURERS' RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED ON SITE AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP

MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ONSITE. EQUIPMENT AND MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, LIQUID ABSORBENT (i.e. KITTY LITTER OR EQUAL), SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE.

ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.

THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.

SPILL OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE OF THE SPILL.

THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.

THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. HE/SHE WILL DESIGNATE AT LEAST ONE OTHER SITE PERSONNEL WHO WILL RECEIVE SPILL PREVENTION AND CLEANUP TRAINING. THESE INDIVIDUALS WILL EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE NAMES OF RESPONSIBLE SPILL PERSONNEL WILL BE POSTED IN THE MATERIAL STORAGE AREA AND IF APPLICABLE, IN THE OFFICE TRAILER ONSITE.

MAINTENANCE/INSPECTION PROCEDURES

EROSION AND SEDIMENT CONTROL INSPECTION AND MAINTENANCE PRACTICES THE FOLLOWING ARE INSPECTION AND MAINTENANCE PRACTICES THAT WILL BE USED TO MAINTAIN EROSION AND SEDIMENT CONTROLS.

- * NO MORE THAN 10 ACRES OF THE SITE WILL BE DENUDED AT ONE TIME WITHOUT WRITTEN PERMISSION FROM THE ENGINEER.
- * ALL CONTROL MEASURES WILL BE INSPECTED BY THE SUPERINTENDENT, THE PERSON RESPONSIBLE FOR THE DAY TO DAY SITE OPERATION OR SOMEONE APPOINTED BY THE SUPERINTENDENT. AT LEAST ONCE A WEEK AND FOLLOWING ANY STORM EVENT OF 0.25 INCHES OR GREATER.
- * ALL TURBIDITY CONTROL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER; IF A REPAIR IS NECESSARY, IT WILL BE INITIATED WITHIN 24 HOURS OF
- * BUILT UP SEDIMENT WILL BE REMOVED FROM SILT FENCE WHEN IT HAS REACHED ONE-THIRD THE HEIGHT OF THE FENCE.

- * SILT FENCE WILL BE INSPECTED FOR DEPTH OF SEDIMENT, TEARS, TO SEE IF THE FABRIC IS SECURELY ATTACHED TO THE FENCE POSTS, AND TO SEE THAT THE FENCE POSTS ARE FIRMLY IN THE GROUND.
- * THE SEDIMENT BASINS WILL BE INSPECTED FOR THE DEPTH OF SEDIMEN AND BUILT UP SEDIMENT WILL BE REMOVED WHEN IT REACHES 10 PERCENT OF THE DESIGN CAPACITY OR AT THE END OF THE JOB,
- * DIVERSION DIKES/SWALES WILL BE INSPECTED AND ANY BREACHES PROMPTLY REPAIRED.
- * TEMPORARY AND PERMANENT SEEDING AND PLANTING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND HEALTHY GROWTH.

ONN

* A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH

THE REPORTS WILL BE KEPT ON SITE DURING CONSTRUCTION AND AVAILABLE UPON REQUEST TO THE OWNER, ENGINEER OR ANY FEDERAL STATE OR LOCAL AGENCY APPROVING SEDIMENT AND AND EROSION PLANS, OR STORM WATER MANAGEMENT PLANS. THE REPORTS SHALL BE MADE AND RETAINED AS PART OF THE STORM WATER POLLUTION PREVENTION PLAN FOR AT LEAST THREE YEARS FROM

THE DATE THAT THE SITE IS FINALLY STABILIZED AND THE NOTICE OF

TERMINATION IS SUBMITTED THE REPORTS SHALL IDENTIFY ANY INCIDENTS

* THE SITE SUPERINTENDENT WILL SELECT UP TO THREE INDIVIDUALS WHO WILL BE RESPONSIBLE FOR INSPECTIONS. MAINTENANCE AND REPAIR ACTIVITIES, AND FILLING OUT THE INSPECTION AND MAINTENANCE

* PERSONNEL SELECTED FOR INSPECTION AND MAINTENANCE RESPONSIBILITIES WILL RECEIVE TRAINING FROM THE SITE. SUPERINTENDENT. THEY WILL BE TRAINED IN ALL THE INSPECTION AND MAINTENANCE PRACTICES NECESSARY FOR KEEPING THE EROSION AND SEDIMENT CONTROLS USED ONSITE IN GOOD WORKING ORDER.

NON-STORM WATER DISCHARGES

OF NON-COMPLIANCE.

WHICHEVER COMES FIRST.

IT IS EXPECTED THAT THE FOLLOWING NON-STORM WATER DISCHARGES WILL OCCUR FROM THE SITE DURING THE CONSTRUCTION PERIOD:


- * WATER FROM WATER LINE FLUSHING
- * PAVEMENT WASH WATERS (WHERE NO SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE OCCURRED).
- * UNCONTAMINATED GROUNDWATER (FROM DEWATERING EXCAVATION).
- ALL NON-STORM WATER DISCHARGES WILL BE DIRECTED TO THE PROPER SEDIMENT TRAPS PRIOR TO DISCHARGE.

CONTRACTOR'S CERTIFICATION

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

RESPONSIBLE FOR/DUTIES	GENERAL CONTRACTOR	SUB-CONTRACTOR	SUB-CONTRACTOR	SUB-CONTRACTOR	SUB-CONTRACTOR
BUSINESS NAME AND ADDRESS OF CONTRACTOR & ALL SUBS					
SIGNATURE					

21-04-0008 Designed: RRB RAH 0.C.: Checked: RRB RCW APRIL 2021 DATUM: Scale:



FLOODPLAIN FILL COMPENSATION MAP

Connelly

LSIDE GROVES

Y IN THE HILLS

C

HOWEY IN THE
PREPARED FOR LENNAR - ORLAN

Sep 23, 2022
JUSTIN WILLIAMS, P.E.
FL P.E. #69260
Reg. Engineer

Project No.:
21-04-0008

Designed: Drawn:
RRB RAH

Checked: O.C.:
RRB RCW

Date:
APRIL 2021

Date:
APRIL 2021

Scale:
1" = 300'

Sheet EX. 1 A

